Parametric Building Models

Cost Worksheet

PROJECT: MWL
PROJECT
PROJECT COMMENT:

GEOLOCATION: ALBUQUERQUE, NEW MEXICO

ESTIMATE BY: UA92T59
ESTIMATE DATE: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

DD Form 1391 Cost Worksheet

1. AIR FORCE	FY 2004 Military Construction Project Data		2. Date 07/26/2002
3. Installation and Location ALBUQUERQUE, NEW MEXICO		4. Project Title MWL	
5. Program Element	6. Category code 149-000	7. Project Number 1	8. Project Cost 197,000

9. Cost Estimates

Item	U/M	Quantity	Unit Cost	Cost ($000)
Primary Facilities				174,962
UnClass Soil Storage Warehouse 1	SF	569,999	51.58	(29,400)
UnClass Soil Storage Warehouse 2	SF	569,999	51.58	(29,400)
UnClass Soil Storage Warehouse 3	SF	569,999	51.58	(29,400)
Class Soil Storage Warehouse 1	SF	477,803	52.01	(24,850)
Class Soil Storage Warehouse 2	SF	477,803	52.01	(24,850)
UnClass Waste Storage Warehouse	SF	569,999	52.41	(29,875)
Classified Waste Storage Warehouse	SF	103,459	69.48	(7,188)
Supporting Facilities				2,695
MWL Storage Facility Office	SF	5,286	175.38	(927)
MWL Retrievable Storage Site Work	LS	--	--	(1,727)
Antiterrorism/Force Protection	LS	--	--	(42)
Subtotal				177,658
Contingency (5.00%)				8,883
Total Contract Cost				186,541
Supervision, Inspection & Overhead (5.70%)				10,633
Total Request				197,173
Total Request (Rounded)				197,000

Parametric Building Models

CONSTRUCTION COST SUMMARY REPORT

Project Name : MWL
Project Description :
Project Comment

GEOLOCATION ALBUQUERQUE, NEW MEXICO

Estimate by: UA92T59
Estimate Date: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

Parametric Building Models

CONSTRUCTION COST SUMMARY REPORT

Facility:	MWL Storage Facility Office	
Model Type:	GENERAL ADMINISTRATIVE FACILITY	Cost
Facility Direct Cost		$684,704
Total Direct Cost		$684,704

Facility:	MWL Retrievable Storage Site Work	
Model Type:	Site Work	Cost
Facility Direct Cost		$1,220,322
Total Direct Cost		$1,220,322

Facility:	Classified Waste Storage Warehouse	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$5,080,123
Total Direct Cost		$5,080,123

Facility:	Class Soil Storage Warehouse 1	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$17,563,199
Total Direct Cost		$17,563,199

Facility:	Class Soil Storage Warehouse 2	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$17,563,199
Total Direct Cost		$17,563,199

Facility:	UnClass Soil Storage Warehouse 1	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$20,778,390
Total Direct Cost		$20,778,390

Facility:	UnClass Soil Storage Warehouse 2	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$20,778,390
Total Direct Cost		$20,778,390

Facility:	UnClass Soil Storage Warehouse 3	
Model Type:	HIGH BAY WAREHOUSE	Cost
Facility Direct Cost		$20,778,390
Total Direct Cost		$20,778,390

Parametric Building Models

CONSTRUCTION COST SUMMARY REPORT

Facility: UnClass Waste Storage Warehouse
Model Type: HIGH BAY WAREHOUSE

		Cost
Facility Direct Cost		$21,114,374
Total Direct Cost		$21,114,374
Project Total Direct Cost		$125,561,091
Markups		$52,096,626
Project Marked Up Cost		$177,657,717
Contengency	5.00%	$8,882,886
SIOH	5.70%	$10,632,814
Project Cost		$197,173,417
Total Project Cost		$197,173,417

This page left intentionally blank.

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Project Name : MWL
Project Description :
Project Comment

GEOLOCATION ALBUQUERQUE, NEW MEXICO

Estimate by: UA92T59
Estimate Date: 07/11/2002

ESCALATION MODIFIER: MID-POINT OF CONSTRUCTION

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name ***UnClass Soil Storage Warehouse 1***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,894,266	$2,281,223	$102,809	$4,278,298	20.59%
02	SUPERSTRUCTURE	$5,042,847	$3,007,306	$262,882	$8,313,034	40.01%
03	EXTERIOR CLOSURE	$701,640	$206,167	$12,075	$919,882	4.43%
04	ROOFING	$1,654,925	$977,386	$0	$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	$542,503	$375,824	$0	$918,326	4.42%
06	INTERIOR FINISHES	$132,661	$223,431	$0	$356,092	1.71%
08	PLUMBING	$26,788	$36,934	$0	$63,722	0.31%
09	H.V.A.C	$581,857	$221,010	$338	$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	$379,430	$509,928	$1,089	$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	$518,835	$681,901	$144	$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	$188,070	$206,109	$0	$394,179	1.90%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.04%
	Facility Total	$11,669,247	$8,729,765	$379,378	$20,778,390	100%

Facility Name ***UnClass Soil Storage Warehouse 2***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,894,266	$2,281,223	$102,809	$4,278,298	20.59%
02	SUPERSTRUCTURE	$5,042,847	$3,007,306	$262,882	$8,313,034	40.01%
03	EXTERIOR CLOSURE	$701,640	$206,167	$12,075	$919,882	4.43%
04	ROOFING	$1,654,925	$977,386	$0	$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	$542,503	$375,824	$0	$918,326	4.42%
06	INTERIOR FINISHES	$132,661	$223,431	$0	$356,092	1.71%
08	PLUMBING	$26,788	$36,934	$0	$63,722	0.31%
09	H.V.A.C	$581,857	$221,010	$338	$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	$379,430	$509,928	$1,089	$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	$518,835	$681,901	$144	$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	$188,070	$206,109	$0	$394,179	1.90%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.04%
	Facility Total	$11,669,247	$8,729,765	$379,378	$20,778,390	100%

Facility Name ***UnClass Soil Storage Warehouse 3***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,894,266	$2,281,223	$102,809	$4,278,298	20.59%
02	SUPERSTRUCTURE	$5,042,847	$3,007,306	$262,882	$8,313,034	40.01%
03	EXTERIOR CLOSURE	$701,640	$206,167	$12,075	$919,882	4.43%
04	ROOFING	$1,654,925	$977,386	$0	$2,632,311	12.67%
05	INTERIOR CONSTRUCTION	$542,503	$375,824	$0	$918,326	4.42%
06	INTERIOR FINISHES	$132,661	$223,431	$0	$356,092	1.71%
08	PLUMBING	$26,788	$36,934	$0	$63,722	0.31%
09	H.V.A.C	$581,857	$221,010	$338	$803,205	3.87%
10	FIRE PROTECTION SYSTEMS	$379,430	$509,928	$1,089	$890,446	4.29%
11	ELECTRIC POWER & LIGHTING	$518,835	$681,901	$144	$1,200,880	5.78%
12	ELECTRICAL SYSTEMS	$188,070	$206,109	$0	$394,179	1.90%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.04%
	Facility Total	$11,669,247	$8,729,765	$379,378	$20,778,390	100%

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name ***Class Soil Storage Warehouse 1***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,588,534	$1,912,914	$86,206	$3,587,654	20.43%
02	SUPERSTRUCTURE	$4,228,015	$2,521,381	$220,405	$6,969,801	39.68%
03	EXTERIOR CLOSURE	$630,330	$182,673	$10,777	$823,780	4.69%
04	ROOFING	$1,387,549	$819,528	$0	$2,207,077	12.57%
05	INTERIOR CONSTRUCTION	$454,711	$315,195	$0	$769,906	4.38%
06	INTERIOR FINISHES	$112,296	$188,580	$0	$300,876	1.71%
08	PLUMBING	$22,889	$31,747	$0	$54,636	0.31%
09	H.V.A.C	$476,800	$186,894	$301	$663,995	3.78%
10	FIRE PROTECTION SYSTEMS	$318,103	$427,509	$913	$746,525	4.25%
11	ELECTRIC POWER & LIGHTING	$490,290	$614,983	$330	$1,105,603	6.29%
12	ELECTRICAL SYSTEMS	$153,956	$171,378	$0	$325,334	1.85%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.05%
	Facility Total	$9,868,899	$7,375,327	$318,973	$17,563,199	100%

Facility Name ***Class Soil Storage Warehouse 2***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,588,534	$1,912,914	$86,206	$3,587,654	20.43%
02	SUPERSTRUCTURE	$4,228,015	$2,521,381	$220,405	$6,969,801	39.68%
03	EXTERIOR CLOSURE	$630,330	$182,673	$10,777	$823,780	4.69%
04	ROOFING	$1,387,549	$819,528	$0	$2,207,077	12.57%
05	INTERIOR CONSTRUCTION	$454,711	$315,195	$0	$769,906	4.38%
06	INTERIOR FINISHES	$112,296	$188,580	$0	$300,876	1.71%
08	PLUMBING	$22,889	$31,747	$0	$54,636	0.31%
9	H.V.A.C	$476,800	$186,894	$301	$663,995	3.78%
10	FIRE PROTECTION SYSTEMS	$318,103	$427,509	$913	$746,525	4.25%
11	ELECTRIC POWER & LIGHTING	$490,290	$614,983	$330	$1,105,603	6.29%
12	ELECTRICAL SYSTEMS	$153,956	$171,378	$0	$325,334	1.85%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.05%
	Facility Total	$9,868,899	$7,375,327	$318,973	$17,563,199	100%

Facility Name ***UnClass Waste Storage Warehouse***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$1,894,266	$2,281,223	$102,809	$4,278,298	20.26%
02	SUPERSTRUCTURE	$5,042,847	$3,007,306	$262,882	$8,313,034	39.37%
03	EXTERIOR CLOSURE	$1,007,005	$236,786	$12,075	$1,255,867	5.95%
04	ROOFING	$1,654,925	$977,386	$0	$2,632,311	12.47%
05	INTERIOR CONSTRUCTION	$542,503	$375,824	$0	$918,326	4.35%
06	INTERIOR FINISHES	$132,661	$223,431	$0	$356,092	1.69%
08	PLUMBING	$26,788	$36,934	$0	$63,722	0.30%
09	H.V.A.C	$581,857	$221,010	$338	$803,205	3.80%
10	FIRE PROTECTION SYSTEMS	$379,430	$509,928	$1,089	$890,446	4.22%
11	ELECTRIC POWER & LIGHTING	$518,835	$681,901	$144	$1,200,880	5.69%
12	ELECTRICAL SYSTEMS	$188,070	$206,109	$0	$394,179	1.87%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.04%
	Facility Total	$11,974,613	$8,760,384	$379,378	$21,114,374	100%

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facility Name ***Classified Waste Storage Warehouse***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$337,475	$415,949	$18,477	$771,901	15.19%
02	SUPERSTRUCTURE	$1,318,050	$1,075,924	$53,848	$2,447,822	48.18%
03	EXTERIOR CLOSURE	$388,508	$80,391	$4,234	$473,133	9.31%
04	ROOFING	$301,898	$178,514	$0	$480,412	9.46%
05	INTERIOR CONSTRUCTION	$98,270	$69,026	$0	$167,296	3.29%
06	INTERIOR FINISHES	$29,609	$47,075	$0	$76,683	1.51%
08	PLUMBING	$7,959	$8,096	$0	$16,055	0.32%
09	H.V.A.C	$97,334	$57,712	$174	$155,220	3.06%
10	FIRE PROTECTION SYSTEMS	$69,203	$93,004	$199	$162,405	3.20%
11	ELECTRIC POWER & LIGHTING	$109,082	$133,854	$64	$243,001	4.78%
12	ELECTRICAL SYSTEMS	$38,261	$39,922	$0	$78,183	1.54%
13	EQUIPMENT	$5,426	$2,546	$41	$8,013	0.16%
	Facility Total	$2,801,073	$2,202,014	$77,037	$5,080,123	100%

Facility Name ***MWL Storage Facility Office***

System	Description	Material	Labor	Equipment	Total	% of Total
01	SUBSTRUCTURE	$13,493	$16,801	$969	$31,264	4.57%
02	SUPERSTRUCTURE	$39,446	$37,856	$2,065	$79,367	11.59%
03	EXTERIOR CLOSURE	$69,894	$54,659	$227	$124,781	18.22%
04	ROOFING	$12,721	$8,204	$0	$20,925	3.06%
05	INTERIOR CONSTRUCTION	$25,323	$24,540	$10	$49,873	7.28%
06	INTERIOR FINISHES	$20,977	$22,010	$197	$43,184	6.31%
07	CONVEYING SYSTEMS	$6,069	$598	$0	$6,667	0.97%
)8	PLUMBING	$7,303	$10,158	$0	$17,460	2.55%
09	H.V.A.C	$78,701	$78,368	$7	$157,076	22.94%
10	FIRE PROTECTION SYSTEMS	$4,875	$6,646	$0	$11,521	1.68%
11	ELECTRIC POWER & LIGHTING	$57,984	$55,436	$44	$113,463	16.57%
12	ELECTRICAL SYSTEMS	$12,246	$15,118	$0	$27,364	4.00%
13	EQUIPMENT	$746	$31	$0	$778	0.11%
15	SPECIAL CONSTRUCTION	$869	$113	$0	$982	0.14%
	Facility Total	$350,648	$330,537	$3,519	$684,704	100%

Facility Name ***MWL Retrievable Storage Site Work***

System	Description	Material	Labor	Equipment	Total	% of Total
17	SITE PREPARATION	$16,542	$124,666	$81,164	$222,372	18.22%
18	SITE IMPROVEMENTS	$305,687	$68,238	$28,776	$402,701	33.00%
19	SITE CIVIL/MECHANICAL UTILITIES	$42,364	$38,352	$5,218	$85,934	7.04%
20	SITE ELECTRICAL UTILITIES	$314,780	$182,813	$11,721	$509,315	41.74%
	Facility Total	$679,374	$414,069	$126,879	$1,220,322	100%

Parametric Building Models

PRORATED SYSTEM CONSTRUCTION COST

Facilities Total	$70,551,248	$52,646,952	$2,362,892	$125,561,092	100%

Total Direct Cost		**$125,561,092**
Comparative Supporting Facilities		
PAVEMENT		$0
SITE IMPROVEMENTS		$0
UTILITIES		$0
		$0
Project Total Direct Cost		$125,561,092
Markups		$52,096,626
Project Marked Up Cost		$177,657,718
Contengency	5.00%	$8,882,886
SIOH	5.70%	$10,632,814
Program Amount		**$197,173,418**

This page left intentionally blank.

Paces



Project Summary Report

PArametric
Cost
Engineering
System

Notes:

All costs are 'Direct Costs' except as indicated at the Project level.
Markups are added to the Project level direct costs to arrive at the Total Project

All costs are listed in the order:
Material, Labor, Equipment, Total. (M,L,E,T)

Project:		**Name:**	MWL	**Service:**	AIR FORCE
Start	07/11/2002	**Descr:**		**Est. By:**	UA92T59
Num:	1	**Loc:**	ALBUQUERQUE, NEW MEXICO		
		Comments			

Paces

Project Summary Report

Date 07/26/2002

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF	$11.15	$10.90	$0.17	$22.22
			Qty:	4622	$51,550	$50,376	$784	$102,709
Assm:	01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF	$21.62	$17.86	$0.29	$39.77
			Qty:	2558	$55,296	$45,684	$748	$101,728
Assm:	01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF	$20.15	$26.26	$0.21	$46.63
			Qty:	4622	$93,158	$121,396	$959	$215,512
Assm:	01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF	$14.13	$21.63	$0.07	$35.83
			Qty:	5116	$72,275	$110,653	$377	$183,305
Assm:	01010201	**Descr:** Spread Footing	**UOM:**	CY	$73.57	$45.75	$2.16	$121.48
			Qty:	1360	$100,050	$62,224	$2,937	$165,211
Assm:	01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA	$87.34	$173.72	$1.69	$262.75
			Qty:	245	$21,399	$42,561	$414	$64,374
Assm:	01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON	$551.26	$645.22	$0.00	$1,196.47
			Qty:	15	$8,164	$9,556	$0	$17,720
Assm:	01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF	$14.64	$18.55	$0.16	$33.35
			Qty:	13991	$204,791	$259,584	$2,262	$466,637
Assm:	01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF	$2.01	$2.62	$0.16	$4.79
			Qty:	570581	$1,146,868	$1,495,550	$91,464	$2,733,882

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01030115	**Descr:** Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
			Qty:	36155	$140,715	$83,641	$2,863	$227,220
Assm:	02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
			Qty:	235108	$1,408,438	$1,894,030	$22,194	$3,324,662
Assm:	02020313	**Descr:** Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
			Qty:	634056	$3,145,171	$754,463	$215,325	$4,114,960
Assm:	02020314	**Descr:** 3" Topping Slab	**UOM:**	SF	$0.77	$0.57	$0.04	$1.38
			Qty:	634056	$489,238	$358,812	$25,362	$873,412
Assm:	03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF	$11.02	$1.21	$0.17	$12.40
			Qty:	42194	$465,134	$51,004	$7,215	$523,353
Assm:	03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
			Qty:	42194	$9,679	$15,270	$1,063	$26,013
Assm:	03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF	$0.51	$0.46	$0.00	$0.98
			Qty:	42194	$21,548	$19,612	$0	$41,160
Assm:	03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF	$0.19	$0.53	$0.00	$0.72
			Qty:	42194	$7,819	$22,494	$0	$30,312
Assm:	03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF	$29.84	$12.28	$0.00	$42.12
			Qty:	956	$28,526	$11,738	$0	$40,264
Assm:	03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA	$608.95	$579.12	$0.00	$1,188.07
			Qty:	3	$1,827	$1,737	$0	$3,564
Assm:	03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA	$1,287.09	$468.13	$0.00	$1,755.22
			Qty:	20	$25,742	$9,363	$0	$35,104

Paces

Project Summary Report

Date 07/26/2002

				Mat $	Lab $	Eqp $	Ttl $
Assm: 03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
		Qty:	3	$6,986	$2,204	$0	$9,191
Assm: 03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA	$3,536.29	$1,914.35	$99.90	$5,550.54
		Qty:	38	$134,379	$72,745	$3,796	$210,921
Assm: 04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
		Qty:	634056	$1,287,768	$797,706	$0	$2,085,474
Assm: 04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
		Qty:	634056	$223,378	$152,871	$0	$376,249
Assm: 04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
		Qty:	6071	$143,492	$26,159	$0	$169,652
Assm: 04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
		Qty:	180	$287	$650	$0	$937
Assm: 08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
		Qty:	24	$4,890	$17,297	$0	$22,188
Assm: 08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
		Qty:	13	$1,182	$326	$0	$1,508
Assm: 08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
		Qty:	24	$1,888	$1,976	$0	$3,864
Assm: 08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
		Qty:	30	$5,404	$10,856	$0	$16,261
Assm: 08030202	**Descr:** PVC Vent Piping	**UOM:**	EA	$13.95	$47.57	$0.00	$61.51
		Qty:	30	$418	$1,427	$0	$1,845

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA		$409.55	$63.67	$0.00	$473.21
		Qty:	6		$2,457	$382	$0	$2,839
Assm: 08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA		$299.10	$172.74	$0.00	$471.84
		Qty:	2		$598	$345	$0	$944
Assm: 08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA		$400.59	$43.19	$0.00	$443.77
		Qty:	3		$1,202	$130	$0	$1,331
Assm: 08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA		$2,609.25	$939.01	$0.00	$3,548.25
		Qty:	2		$5,218	$1,878	$0	$7,097
Assm: 08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA		$362.85	$935.23	$0.00	$1,298.08
		Qty:	2		$726	$1,870	$0	$2,596
Assm: 08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA		$1,401.67	$222.85	$0.00	$1,624.52
		Qty:	2		$2,803	$446	$0	$3,249
Assm: 09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA		$10,823.28	$10,577.38	$148.33	$21,548.98
		Qty:	1		$10,823	$10,577	$148	$21,549
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA		$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	112		$337,806	$94,021	$190	$432,017
Assm: 09030209	**Descr:** 15 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA		$8,123.97	$3,365.04	$0.00	$11,489.01
		Qty:	2		$16,248	$6,730	$0	$22,978
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM		$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	1		$659	$984	$0	$1,642
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM		$418.17	$71.07	$0.00	$489.24
		Qty:	359		$150,205	$25,530	$0	$175,735

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM	$3,520.33	$790.73	$0.00	$4,311.06
			Qty:	10	$34,781	$7,812	$0	$42,593
Assm:	09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM	$1,370.16	$1,955.73	$0.00	$3,325.89
			Qty:	0	$356	$508	$0	$865
Assm:	09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM	$3,706.36	$4,390.65	$0.00	$8,097.01
			Qty:	2	$8,636	$10,230	$0	$18,866
Assm:	09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM	$1,645.75	$4,920.50	$0.00	$6,566.24
			Qty:	2	$2,847	$8,512	$0	$11,360
Assm:	09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA	$122.32	$58.85	$0.00	$181.17
			Qty:	2	$245	$118	$0	$362
Assm:	09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA	$19,211.52	$29,488.79	$0.00	$48,700.31
			Qty:	1	$19,212	$29,489	$0	$48,700
Assm:	09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA	$0.00	$206.44	$0.00	$206.44
			Qty:	35	$0	$7,225	$0	$7,225
Assm:	09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA	$0.00	$309.73	$0.00	$309.73
			Qty:	58	$0	$17,964	$0	$17,964
Assm:	09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA	$0.00	$413.28	$0.00	$413.28
			Qty:	3	$0	$1,240	$0	$1,240
Assm:	09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA	$39.90	$68.74	$0.00	$108.64
			Qty:	1	$40	$69	$0	$109
Assm:	10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
			Qty:	4962	$238,327	$105,928	$1,089	$345,344

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
			Qty:	4962	$141,102	$404,000	$0	$545,102
Assm:	11010108	**Descr:** Electrical 2500A Main Transformer	**UOM:**	EA	$29,512.44	$4,886.87	$96.72	$34,496.03
			Qty:	1	$29,512	$4,887	$97	$34,496
Assm:	11010211	**Descr:** Electrical 2500A Secondary	**UOM:**	EA	$37,780.63	$23,682.69	$47.01	$61,510.33
			Qty:	1	$37,781	$23,683	$47	$61,510
Assm:	11010311	**Descr:** Electrical 2500A Main Switchboard	**UOM:**	EA	$91,215.75	$9,632.58	$0.00	$100,848.33
			Qty:	1	$91,216	$9,633	$0	$100,848
Assm:	11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
			Qty:	9	$19,349	$9,348	$0	$28,697
Assm:	11010502	**Descr:** Panelbd 208V 100A 30 Cir Mlo W/Bkr	**UOM:**	EA	$1,153.60	$899.36	$0.00	$2,052.95
			Qty:	8	$9,229	$7,195	$0	$16,424
Assm:	11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
			Qty:	8	$14,177	$17,881	$0	$32,058
Assm:	11010516	**Descr:** Panelbd 208V 225A MCB 42 Cir W/Bkr	**UOM:**	EA	$2,088.56	$2,391.53	$0.00	$4,480.09
			Qty:	1	$2,089	$2,392	$0	$4,480
Assm:	11010561	**Descr:** Panelbd 480V 600A MCB 42 Cir W/Bkr	**UOM:**	EA	$7,082.74	$3,958.17	$0.00	$11,040.92
			Qty:	2	$14,165	$7,916	$0	$22,082
Assm:	11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA	$1,805.61	$1,767.07	$0.00	$3,572.68
			Qty:	1	$1,806	$1,767	$0	$3,573
Assm:	12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT	$102.32	$374.83	$0.00	$477.15
			Qty:	192	$19,646	$71,968	$0	$91,614

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA		$6,181.75	$3,465.03	$0.00	$9,646.78
		Qty:	2		$12,363	$6,930	$0	$19,294
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA		$42.39	$176.98	$0.00	$219.38
		Qty:	55		$2,332	$9,734	$0	$12,066
Assm: 12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF		$0.03	$0.07	$0.00	$0.10
		Qty:	570584		$16,889	$40,968	$0	$57,857
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA		$222.34	$177.74	$0.00	$400.08
		Qty:	25		$5,559	$4,444	$0	$10,002
Assm: 12010602	**Descr:** Time Clock System	**UOM:**	EA		$334.18	$866.03	$0.00	$1,200.22
		Qty:	9		$3,008	$7,794	$0	$10,802
Assm: 12020221	**Descr:** Battery Charger	**UOM:**	EA		$1,043.18	$619.45	$0.00	$1,662.63
		Qty:	34		$35,468	$21,061	$0	$56,529
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	30		$2,356	$4,241	$0	$6,598
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	97		$90,449	$38,969	$0	$129,418
FSA:	**ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY							
Facility Type: Primary	**ID:** 9 **Name:** UnClass Soil Storage Warehouse 1							
Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601

FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 9 **Name:** UnClass Soil Storage Warehouse 1

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	18778		$36,906	$69,184	$0	$106,090
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF		$1.68	$1.66	$0.00	$3.34
		Qty:	139792		$234,655	$231,565	$0	$466,220
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF		$3.37	$1.04	$0.00	$4.41
		Qty:	3901		$13,144	$4,039	$0	$17,184
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF		$35.54	$9.59	$0.00	$45.13
		Qty:	7231		$257,009	$69,340	$0	$326,349
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	11265		$3,235	$8,084	$0	$11,319

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF		$0.04	$0.05	$0.00	$0.08
		Qty:	568936		$20,994	$27,252	$0	$48,246
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF		$0.18	$0.32	$0.00	$0.49
		Qty:	568936		$101,441	$179,727	$0	$281,168
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	240		$11,687	$71,386	$0	$83,072
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	175		$46,751	$92,240	$0	$138,991
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	72		$12,625	$17,013	$0	$29,638
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	931		$187,080	$349,963	$0	$537,043
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	125		$37,089	$58,498	$0	$95,588
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	21		$2,462	$4,464	$0	$6,925

FSA: **ID:** **Name:** Building Shell

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	29		$328	$320	$5	$653
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	69		$1,483	$1,225	$20	$2,728

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01010201	**Descr:** Spread Footing	**UOM:**	CY	$73.57	$45.75	$2.16	$121.48
			Qty:	4	$294	$183	$9	$486
Assm:	01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON	$551.26	$645.22	$0.00	$1,196.47
			Qty:	0	$61	$71	$0	$132
Assm:	01010277	**Descr:** Spread Footing Column Bolts	**UOM:**	EA	$1.22	$4.37	$0.00	$5.59
			Qty:	28	$34	$122	$0	$156
Assm:	01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF	$14.64	$18.55	$0.16	$33.35
			Qty:	130	$1,897	$2,405	$21	$4,323
Assm:	01030103	**Descr:** 6" Standard Slab On Grade	**UOM:**	SF	$1.70	$2.17	$0.16	$4.03
			Qty:	5286	$8,968	$11,491	$842	$21,301
Assm:	01030601	**Descr:** Drainage	**UOM:**	LF	$2.28	$5.23	$0.39	$7.89
			Qty:	188	$428	$983	$73	$1,484
Assm:	02020115	**Descr:** Med Span, Lt Ld, Stl Frm, Mtl Joist	**UOM:**	SF	$4.52	$2.20	$0.31	$7.04
			Qty:	5286	$23,918	$11,639	$1,642	$37,199
Assm:	02020136	**Descr:** Structural Steel, Lt Load, Columns	**UOM:**	SF	$0.61	$0.20	$0.05	$0.86
			Qty:	3491	$2,139	$706	$163	$3,008
Assm:	02020351	**Descr:** 102 MM (4") MEDIUMREINFORCED CONCRETE ROOF	**UOM:**	SF	$2.53	$4.83	$0.05	$7.41
			Qty:	5286	$13,389	$25,511	$260	$39,160
Assm:	03010117	**Descr:** 8 X 8 X 16 Split Rib Block	**UOM:**	SF	$4.36	$6.25	$0.02	$10.64
			Qty:	4698	$20,506	$29,360	$109	$49,974
Assm:	03010141	**Descr:** 3-5/8" Mtl. Stud Non-Load Bearing	**UOM:**	SF	$0.18	$0.62	$0.00	$0.79
			Qty:	4698	$827	$2,890	$0	$3,717

Project Summary Report

Date 07/26/2002

				Mat $	Lab $	Eqp $	Ttl $
Assm: 03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
		Qty:	4698	$1,078	$1,700	$118	$2,896
Assm: 03010211	**Descr:** 4" Batt Insulation W/Vapor Barrier	**UOM:**	SF	$0.29	$0.35	$0.00	$0.64
		Qty:	4698	$1,350	$1,650	$0	$3,000
Assm: 03010310	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF	$0.31	$0.59	$0.00	$0.90
		Qty:	4698	$1,436	$2,793	$0	$4,230
Assm: 03010311	**Descr:** Paint to Gypsum Board Walls Using Roller	**UOM:**	SF	$0.10	$0.28	$0.00	$0.38
		Qty:	4698	$479	$1,300	$0	$1,779
Assm: 03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF	$29.84	$12.28	$0.00	$42.12
		Qty:	122	$3,640	$1,498	$0	$5,138
Assm: 03010801	**Descr:** Gypsum Plaster Exterior Soffits	**UOM:**	SF	$1.00	$3.74	$0.02	$4.76
		Qty:	20	$20	$75	$0	$95
Assm: 03020172	**Descr:** 9.525 mm (3/8") Mono TTG	**UOM:**	SF	$26.00	$8.47	$0.00	$34.47
		Qty:	1378	$35,829	$11,665	$0	$47,494
Assm: 03030104	**Descr:** 6'0" X 7'0" Pair Aluminum And Glass Doors With Transom	**UOM:**	EA	$1,483.46	$890.91	$0.00	$2,374.37
		Qty:	1	$1,483	$891	$0	$2,374
Assm: 03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
		Qty:	1	$2,329	$735	$0	$3,064
Assm: 03030250	**Descr:** 18 GA HM EXTERIOR DOOR 914 MM X 2134 MM (3'-0 X 7'-0)	**UOM:**	EA	$305.73	$34.14	$0.00	$339.87
		Qty:	3	$917	$102	$0	$1,020
Assm: 04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
		Qty:	5286	$10,736	$6,650	$0	$17,386

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
			Qty:	5286	$1,862	$1,274	$0	$3,137
Assm:	04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
			Qty:	77	$123	$279	$0	$402
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	5	$1,019	$3,604	$0	$4,622
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	2	$182	$50	$0	$232
Assm:	08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
			Qty:	5	$393	$412	$0	$805
Assm:	08020502	**Descr:** Domestic Water Supply Specialties, 1"	**UOM:**	EA	$136.23	$39.26	$0.00	$175.49
			Qty:	1	$136	$39	$0	$175
Assm:	08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
			Qty:	6	$1,081	$2,171	$0	$3,252
Assm:	08030201	**Descr:** C.I. No Hub Vent Pipe Systm	**UOM:**	EA	$10.99	$57.80	$0.00	$68.80
			Qty:	5	$55	$289	$0	$344
Assm:	08030303	**Descr:** Medium Duty And Heavy Duty Cast Iron Floor Drains	**UOM:**	EA	$283.27	$71.63	$0.00	$354.90
			Qty:	1	$283	$72	$0	$355
Assm:	09010206	**Descr:** 900 MBH Gas Supply	**UOM:**	EA	$1,779.16	$2,109.91	$0.00	$3,889.07
			Qty:	1	$1,779	$2,110	$0	$3,889
Assm:	09020215	**Descr:** HOT WATER BOILER, GAS FIRED 203 MBH	**UOM:**	EA	$1,755.65	$1,085.34	$0.00	$2,840.99
			Qty:	1	$1,756	$1,085	$0	$2,841

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09030102	**Descr:** 20 Ton Air Cooled Recip. Chiller W/Mech. Room Piping	**UOM:**	EA		$24,028.22	$10,209.00	$7.16	$34,244.37
		Qty:	1		$24,028	$10,209	$7	$34,244
Assm: 09040302	**Descr:** Hot And Chilled Water Distribution System - 540 MBH	**UOM:**	MBH		$12.68	$14.26	$0.00	$26.93
		Qty:	142		$1,800	$2,024	$0	$3,825
Assm: 09040720	**Descr:** Ventilation System, Mechanical Room 4.695 MCFM	**UOM:**	MCFM		$228.93	$60.10	$0.00	$289.04
		Qty:	1		$114	$30	$0	$145
Assm: 09049001	**Descr:** Exhaust Ventilation System	**UOM:**	MCFM		$231.80	$77.09	$0.00	$308.89
		Qty:	1		$130	$43	$0	$173
Assm: 09049902	**Descr:** .8 MCFM AIR DIST SYS FOR FAN COIL UNIT	**UOM:**	MCFM		$3,444.79	$1,186.52	$0.00	$4,631.30
		Qty:	0		$276	$95	$0	$371
Assm: 09049906	**Descr:** 0 - .3 MCFM Vav Assembly	**UOM:**	MCFM		$1,285.27	$1,323.87	$0.00	$2,609.14
		Qty:	1		$655	$675	$0	$1,331
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	2		$2,727	$3,892	$0	$6,619
Assm: 09049908	**Descr:** Air Dist Sys .8 - 1.2 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,287.00	$2,135.60	$0.00	$3,422.61
		Qty:	3		$4,144	$6,877	$0	$11,021
Assm: 09049909	**Descr:** Air Dist Sys 1.2 - 2.8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,242.71	$2,340.45	$0.00	$3,583.16
		Qty:	4		$4,673	$8,800	$0	$13,473
Assm: 09049938	**Descr:** 7.5-9.2 MCFM AHU Low Pressure W/Vav Boxes	**UOM:**	MCFM		$1,375.34	$2,640.94	$0.00	$4,016.29
		Qty:	1		$1,252	$2,403	$0	$3,655
Assm: 09049945	**Descr:** 13.2 MCFM A.D.S. WITH RETURN AIR FAN	**UOM:**	MCFM		$1,284.64	$1,472.93	$0.00	$2,757.57
		Qty:	1		$1,683	$1,930	$0	$3,612

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09049953	**Descr:** Air Dist, 20 MCFM Air Handler, Med Pressure Supply	**UOM:**	MCFM		$2,309.17	$4,605.55	$0.00	$6,914.72
		Qty:	2		$5,057	$10,086	$0	$15,143
Assm: 09060101	**Descr:** Vav Boxes Controls, Portion Of Electric A.C. Controls	**UOM:**	EA		$1,783.44	$1,630.37	$0.00	$3,413.81
		Qty:	9		$16,051	$14,673	$0	$30,724
Assm: 09060149	**Descr:** Heat Generation System Controls For Heat Exchgr, Xtra	**UOM:**	EA		$2,928.43	$608.69	$0.00	$3,537.12
		Qty:	1		$2,928	$609	$0	$3,537
Assm: 09060175	**Descr:** Cooling Generation System Controls	**UOM:**	EA		$1,815.28	$943.55	$0.00	$2,758.83
		Qty:	1		$1,815	$944	$0	$2,759
Assm: 09070101	**Descr:** Water Test & Balance Water Main Balancing Valves	**UOM:**	EA		$0.00	$52.51	$0.00	$52.51
		Qty:	1		$0	$53	$0	$53
Assm: 09070103	**Descr:** Water, Test & Balance Air Cooled Condenser	**UOM:**	EA		$0.00	$122.56	$0.00	$122.56
		Qty:	1		$0	$123	$0	$123
Assm: 09070107	**Descr:** Water, Test & Balance Fan Coil, Fin Tube	**UOM:**	EA		$0.00	$70.02	$0.00	$70.02
		Qty:	21		$0	$1,470	$0	$1,470
Assm: 09070109	**Descr:** Water, Test & Balance Pump	**UOM:**	EA		$0.00	$154.05	$0.00	$154.05
		Qty:	1		$0	$154	$0	$154
Assm: 09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA		$0.00	$206.44	$0.00	$206.44
		Qty:	1		$0	$206	$0	$206
Assm: 09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA		$0.00	$413.28	$0.00	$413.28
		Qty:	1		$0	$413	$0	$413
Assm: 09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA		$39.90	$68.74	$0.00	$108.64
		Qty:	7		$279	$481	$0	$760

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	09070212	**Descr:** Test & Balance Register Average Ceiling Height	**UOM:**	EA	$0.00	$41.31	$0.00	$41.31
			Qty:	58	$0	$2,396	$0	$2,396
Assm:	10010105	**Descr:** Fire Protection Water Supply	**UOM:**	EA	$37.08	$6.70	$0.00	$43.77
			Qty:	46	$1,705	$308	$0	$2,014
Assm:	10020102	**Descr:** Concealed Sprinkler Heads, Pipes & Fittings - Ord. Haz.	**UOM:**	EA	$45.50	$128.81	$0.00	$174.31
			Qty:	46	$2,093	$5,925	$0	$8,018
Assm:	10030101	**Descr:** 6" Standpipe System	**UOM:**	EA	$997.75	$371.80	$0.00	$1,369.55
			Qty:	1	$998	$372	$0	$1,370
Assm:	10040101	**Descr:** 5 Pound All Purpose Abc Type Fire Extinguishers	**UOM:**	EA	$39.56	$20.19	$0.00	$59.76
			Qty:	2	$79	$40	$0	$120
Assm:	11010101	**Descr:** Undergrd 200 Amp Main Transformer	**UOM:**	EA	$8,818.14	$1,739.91	$33.61	$10,591.66
			Qty:	1	$8,818	$1,740	$34	$10,592
Assm:	11010204	**Descr:** Undergrd 200 Amp Secondary	**UOM:**	EA	$1,270.14	$1,438.27	$10.07	$2,718.48
			Qty:	1	$1,270	$1,438	$10	$2,718
Assm:	11010304	**Descr:** Undergrd 200 Amp Main Switchboard	**UOM:**	EA	$12,768.04	$1,722.21	$0.00	$14,490.25
			Qty:	1	$12,768	$1,722	$0	$14,490
Assm:	11010401	**Descr:** (10-30 Amps 480V) 25 KVA Dry Type Transformer	**UOM:**	EA	$1,291.40	$674.69	$0.00	$1,966.09
			Qty:	2	$2,583	$1,349	$0	$3,932
Assm:	11010501	**Descr:** Panelbd 208V 100A 24 Cir Mlo W/Bkr	**UOM:**	EA	$882.61	$1,140.56	$0.00	$2,023.17
			Qty:	1	$883	$1,141	$0	$2,023
Assm:	11010506	**Descr:** Panelbd 208V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$1,554.41	$2,086.31	$0.00	$3,640.72
			Qty:	1	$1,554	$2,086	$0	$3,641

Project Summary Report

Date 07/26/2002

				Mat $	Lab $	Eqp $	Ttl $
Assm: 11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
		Qty:	1	$1,772	$2,235	$0	$4,007
Assm: 11010536	**Descr:** Panelbd 480V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$2,296.82	$2,123.79	$0.00	$4,420.61
		Qty:	1	$2,297	$2,124	$0	$4,421
Assm: 11010602	**Descr:** Enclosed Cir Bkr 600V 60A	**UOM:**	EA	$691.57	$1,188.21	$0.00	$1,879.78
		Qty:	1	$692	$1,188	$0	$1,880
Assm: 11010609	**Descr:** Enclosed Cir Bkr 600V 30A	**UOM:**	EA	$260.10	$281.26	$0.00	$541.36
		Qty:	2	$520	$563	$0	$1,083
Assm: 11010701	**Descr:** MCC Starter 10HP (20-30 Amps) Fvnr Size 1	**UOM:**	EA	$1,067.87	$581.73	$0.00	$1,649.60
		Qty:	2	$2,136	$1,163	$0	$3,299
Assm: 11010702	**Descr:** MCC Starter 25HP (60-80 Amps) Fvnr Size 2	**UOM:**	EA	$1,511.61	$655.73	$0.00	$2,167.34
		Qty:	1	$1,512	$656	$0	$2,167
Assm: 12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT	$102.32	$374.83	$0.00	$477.15
		Qty:	5	$512	$1,874	$0	$2,386
Assm: 12010112	**Descr:** 8 Zone Fire Alarm Panel And Remote Annunciator	**UOM:**	EA	$1,423.01	$1,578.16	$0.00	$3,001.17
		Qty:	1	$1,423	$1,578	$0	$3,001
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA	$42.39	$176.98	$0.00	$219.38
		Qty:	32	$1,357	$5,663	$0	$7,020
Assm: 12010401	**Descr:** Sound And Public Address	**UOM:**	SF	$0.44	$0.30	$0.00	$0.75
		Qty:	5286	$2,351	$1,612	$0	$3,962
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA	$222.34	$177.74	$0.00	$400.08
		Qty:	1	$222	$178	$0	$400

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12020231	**Descr:** Exit Lighting	**UOM:**	EA		$118.06	$331.48	$0.00	$449.54
		Qty:	3		$354	$994	$0	$1,349
Assm: 12020303	**Descr:** Transformer Grounding	**UOM:**	EA		$40.06	$100.74	$0.00	$140.80
		Qty:	1		$40	$101	$0	$141
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	5		$393	$707	$0	$1,100
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	6		$5,595	$2,410	$0	$8,005

FSA: **ID:** BSP **Name:** BUILDING SUPPORT AREA

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010101	**Descr:** Mtl Stud Partition, 3-5/8"	**UOM:**	SF		$0.18	$0.62	$0.00	$0.79
		Qty:	5		$1	$3	$0	$4
Assm: 05010102	**Descr:** Mtl Stud Partition, 3-5/8", Sound Rated	**UOM:**	SF		$0.59	$0.94	$0.00	$1.54
		Qty:	22		$13	$21	$0	$34
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	11		$22	$41	$0	$62
Assm: 05010113	**Descr:** Non-Load Brg Partition Of 8 X 8 X 16 Concrete	**UOM:**	SF		$2.08	$3.86	$0.00	$5.94
		Qty:	71		$148	$274	$0	$422
Assm: 05010401	**Descr:** Aluminum Balcony Rail	**UOM:**	LF		$81.26	$18.89	$0.40	$100.55
		Qty:	1		$81	$19	$0	$101
Assm: 05010504	**Descr:** Fixed Type Window With Aluminum Frm - 3/4" Clear Glass	**UOM:**	SF		$16.81	$6.30	$0.00	$23.11
		Qty:	2		$34	$13	$0	$46

Paces

Project Summary Report

Date 07/26/2002

				Mat $	Lab $	Eqp $	Ttl $
Assm: 05010601	**Descr:** Storefront With Lt Aluminum Frm - 3/8" Clear Glass	**UOM:**	SF	$13.29	$10.81	$0.00	$24.11
		Qty:	3	$40	$32	$0	$72
Assm: 05040101	**Descr:** Urinal Screens	**UOM:**	EA	$111.66	$62.36	$0.00	$174.02
		Qty:	1	$112	$62	$0	$174
Assm: 05040102	**Descr:** Toilet Partition And Accessories	**UOM:**	EA	$708.99	$197.03	$0.00	$906.02
		Qty:	1	$709	$197	$0	$906
Assm: 05040106	**Descr:** Lavoratory Accessories	**UOM:**	EA	$409.42	$46.78	$0.00	$456.20
		Qty:	1	$409	$47	$0	$456
Assm: 05040301	**Descr:** Porcelain Enamel Chalkboard	**UOM:**	SF	$16.66	$22.28	$0.00	$38.94
		Qty:	1	$17	$22	$0	$39
Assm: 05040403	**Descr:** Bronze Letters With Satin Finish 8" High	**UOM:**	EA	$34.43	$22.28	$0.00	$56.71
		Qty:	1	$34	$22	$0	$57
Assm: 05040406	**Descr:** Aluminum Framed Glass Covered Directory Board	**UOM:**	EA	$161.15	$267.31	$0.00	$428.47
		Qty:	1	$161	$267	$0	$428
Assm: 05040601	**Descr:** 10" Wide Stock Prefinished Shelves With Supports	**UOM:**	LF	$3.84	$4.29	$0.00	$8.13
		Qty:	1	$4	$4	$0	$8
Assm: 06010301	**Descr:** 5/8" Gypsum Board On 7/8" Furring Channel	**UOM:**	SF	$0.73	$3.09	$0.00	$3.83
		Qty:	17	$12	$53	$0	$65
Assm: 06010303	**Descr:** Two Layers Of 5/8" Fire Resistant Gypsum Board	**UOM:**	SF	$1.04	$1.29	$0.00	$2.33
		Qty:	3	$3	$4	$0	$7
Assm: 06010304	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF	$0.31	$0.59	$0.00	$0.90
		Qty:	8	$2	$5	$0	$7

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	06010401	**Descr:** 4-1/4" X 4-1/4" Ceramic Tile To Walls	**UOM:**	SF	$2.53	$2.54	$0.00	$5.07
			Qty:	27	$68	$69	$0	$137
Assm:	06010501	**Descr:** Paint To Gypsum Board Walls Using Roller	**UOM:**	SF	$0.10	$0.28	$0.00	$0.38
			Qty:	53	$5	$15	$0	$20
Assm:	06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF	$0.29	$0.72	$0.00	$1.00
			Qty:	49	$14	$35	$0	$49
Assm:	06010602	**Descr:** Medium Weight Vinyl Wallcovering With Fabric Backing	**UOM:**	SF	$0.63	$0.55	$0.00	$1.18
			Qty:	24	$15	$13	$0	$28
Assm:	06020101	**Descr:** Thin Set Natural Clay Ceramic Tile Floor And Base	**UOM:**	SF	$6.69	$3.84	$0.00	$10.53
			Qty:	15	$100	$58	$0	$158
Assm:	06020401	**Descr:** Vinyl Tile 1/8" X 12" X 12"	**UOM:**	SF	$2.96	$0.82	$0.00	$3.78
			Qty:	7	$21	$6	$0	$26
Assm:	06020501	**Descr:** Commercial Grade 26 Oz. Nylon Carpet	**UOM:**	SY	$14.84	$6.16	$0.00	$21.00
			Qty:	4	$59	$25	$0	$84
Assm:	06020601	**Descr:** Floor Pavers 8x4, 1" To 1-1/4" Thick	**UOM:**	SF	$3.06	$9.31	$0.00	$12.37
			Qty:	13	$40	$121	$0	$161
Assm:	06030302	**Descr:** 5/8" Gypsum Wallboard Ceiling, 3 Layers, Over 8 Ft.	**UOM:**	SF	$0.78	$1.47	$0.00	$2.25
			Qty:	26	$20	$38	$0	$58
Assm:	06030402	**Descr:** 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	**UOM:**	SF	$0.43	$0.42	$0.00	$0.85
			Qty:	56	$24	$23	$0	$47
Assm:	06030601	**Descr:** Painting To Drywall Or Plaster Using Rollers, 2 Coats	**UOM:**	SF	$0.10	$0.28	$0.00	$0.38
			Qty:	26	$3	$7	$0	$10

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	06030703	**Descr:** T-Bar Ceiling Suspension System 2' X 4' Grid	**UOM:**	SF	$0.31	$0.37	$0.00	$0.67
			Qty:	56	$17	$21	$0	$38
Assm:	06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF	$0.75	$4.08	$0.00	$4.83
			Qty:	26	$20	$106	$0	$126
Assm:	11020101	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	**UOM:**	EA	$26.43	$164.10	$0.00	$190.53
			Qty:	2	$53	$328	$0	$381
Assm:	11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA	$31.01	$170.59	$0.00	$201.60
			Qty:	1	$31	$171	$0	$202
Assm:	11020107	**Descr:** 120 Volt, 15 Amp Duplex Ground Fault Receptacle	**UOM:**	EA	$51.22	$154.98	$0.00	$206.20
			Qty:	1	$51	$155	$0	$206
Assm:	11020137	**Descr:** Equipment Connections For Up To 10 HP	**UOM:**	EA	$301.38	$572.98	$0.00	$874.36
			Qty:	1	$301	$573	$0	$874
Assm:	11020138	**Descr:** 480 Volt Equipment Connections For Motors - 15 To 25 HP	**UOM:**	EA	$342.85	$508.54	$0.00	$851.40
			Qty:	1	$343	$509	$0	$851
Assm:	11020139	**Descr:** 480 Volt Equipment Connections For Motors - 30 T0 40 HP	**UOM:**	EA	$370.76	$524.17	$0.00	$894.93
			Qty:	1	$371	$524	$0	$895
Assm:	11020201	**Descr:** Four Foot Strip Fluorescent Fixture	**UOM:**	EA	$54.85	$176.03	$0.00	$230.87
			Qty:	1	$55	$176	$0	$231
Assm:	11020202	**Descr:** 2' X 4' Lay-In Fluorescent Fixture	**UOM:**	EA	$69.29	$182.23	$0.00	$251.52
			Qty:	1	$69	$182	$0	$252
Assm:	11020220	**Descr:** Ceiling Recessed Incandescent 100 Watt Fixture	**UOM:**	EA	$72.89	$144.66	$0.00	$217.55
			Qty:	1	$73	$145	$0	$218

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11029011	**Descr:** Fire Alarm Pull Station	**UOM:**	EA		$41.30	$155.77	$0.00	$197.07
		Qty:	1		$41	$156	$0	$197
FSA:	**ID:** DET	**Name:**	DEPOT MAINTENANCE ROOM					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				
Assm: 05010113	**Descr:** Non-Load Brg Partition Of 8 X 8 X 16 Concrete	**UOM:**	SF		$2.08	$3.86	$0.00	$5.94
		Qty:	2493		$5,195	$9,616	$0	$14,811
Assm: 05020101	**Descr:** 3'0" X 7'0" Hollow Metal Door	**UOM:**	EA		$441.64	$173.13	$0.00	$614.77
		Qty:	2		$883	$346	$0	$1,230
Assm: 05030101	**Descr:** Coiling Overhead Door	**UOM:**	EA		$1,101.78	$1,107.72	$0.00	$2,209.50
		Qty:	3		$3,305	$3,323	$0	$6,629
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	2063		$592	$1,480	$0	$2,073
Assm: 06020801	**Descr:** Epoxy Floor Coating	**UOM:**	SF		$2.87	$2.58	$0.10	$5.56
		Qty:	1800		$5,169	$4,650	$187	$10,005
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	15		$730	$4,462	$0	$5,192
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	3		$801	$1,581	$0	$2,383
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	7		$1,407	$2,631	$0	$4,038
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	2		$593	$936	$0	$1,529
FSA:	**ID:** DPS	**Name:**	DATA SUPPLY ROOM					

Project Summary Report

Date 07/26/2002

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010101	**Descr:** Mtl Stud Partition, 3-5/8"	**UOM:**	SF		$0.18	$0.62	$0.00	$0.79
		Qty:	188		$33	$116	$0	$149
Assm: 05020208	**Descr:** 3'0" X 7'0" S.C. Wood Door W/Wd. Frame & Glazing	**UOM:**	EA		$439.36	$209.37	$0.00	$648.73
		Qty:	1		$439	$209	$0	$649
Assm: 06010302	**Descr:** 5/8" Gypsum Board On Furring Channel W/Rigid Insulation	**UOM:**	SF		$0.85	$3.24	$0.00	$4.09
		Qty:	607		$516	$1,965	$0	$2,481
Assm: 06010304	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$0.31	$0.59	$0.00	$0.90
		Qty:	416		$127	$247	$0	$375
Assm: 06010501	**Descr:** Paint To Gypsum Board Walls Using Roller	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	94		$10	$26	$0	$36
Assm: 06010701	**Descr:** 4' X 8' X 1" Fiberglass Sound Absorbing Panels	**UOM:**	SF		$1.56	$0.58	$0.00	$2.14
		Qty:	929		$1,446	$543	$0	$1,989
Assm: 06020502	**Descr:** Commercial Grade 35 Oz. Nylon	**UOM:**	SY		$18.07	$6.16	$0.00	$24.23
		Qty:	64		$1,156	$394	$0	$1,551
Assm: 06030402	**Descr:** 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	**UOM:**	SF		$0.43	$0.42	$0.00	$0.85
		Qty:	576		$246	$241	$0	$488
Assm: 06030703	**Descr:** T-Bar Ceiling Suspension System 2' X 4' Grid	**UOM:**	SF		$0.31	$0.37	$0.00	$0.67
		Qty:	576		$176	$213	$0	$389
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	7		$341	$2,082	$0	$2,423
Assm: 11020205	**Descr:** Fluorescent Troffer W/Parabolic Baffle	**UOM:**	EA		$66.91	$186.76	$0.00	$253.67
		Qty:	10		$669	$1,868	$0	$2,537

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
FSA:	**ID:** FLS	**Name:**	FIRE STATION LOCKERS AND SHOWERS					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				
Assm:	05010118	**Descr:**	8 X 8 X 16 Load Bearing Concrete Masonry Unit Wall	**UOM:**	SF	$4.07	$5.38	$0.02	$9.47
				Qty:	334	$1,359	$1,798	$8	$3,164
Assm:	05020101	**Descr:**	3'0" X 7'0" Hollow Metal Door	**UOM:**	EA	$441.64	$173.13	$0.00	$614.77
				Qty:	1	$442	$173	$0	$615
Assm:	05020116	**Descr:**	3'0" X 7'0" S.C. Wood Door W/H.M. Frame W/Passage Set	**UOM:**	EA	$214.34	$167.64	$0.00	$381.99
				Qty:	1	$214	$168	$0	$382
Assm:	05040101	**Descr:**	Urinal Screens	**UOM:**	EA	$111.66	$62.36	$0.00	$174.02
				Qty:	1	$112	$62	$0	$174
Assm:	05040102	**Descr:**	Toilet Partition And Accessories	**UOM:**	EA	$708.99	$197.03	$0.00	$906.02
				Qty:	1	$709	$197	$0	$906
Assm:	05040401	**Descr:**	Door Sign, 3" X 8"	**UOM:**	EA	$8.77	$7.35	$0.00	$16.12
				Qty:	1	$9	$7	$0	$16
Assm:	05040501	**Descr:**	12" X 15" X 36" Double Tier Lockers	**UOM:**	EA	$70.41	$8.44	$0.00	$78.84
				Qty:	8	$563	$67	$0	$631
Assm:	05050201	**Descr:**	Plastic Laminate Cabinets With Countertop And Drawers	**UOM:**	LF	$135.86	$32.22	$0.00	$168.08
				Qty:	6	$815	$193	$0	$1,008
Assm:	05050204	**Descr:**	Bathroom Vanity 30" Wide X 24" Deep X 34" High	**UOM:**	LF	$91.83	$22.89	$0.00	$114.71
				Qty:	6	$551	$137	$0	$688
Assm:	06010311	**Descr:**	1/2" WP Gypsum Board/Installed/Taped & Finished	**UOM:**	SF	$0.35	$0.59	$0.00	$0.94
				Qty:	516	$179	$307	$0	$486

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	06010401	**Descr:** 4-1/4" X 4-1/4" Ceramic Tile To Walls	**UOM:**	SF	$2.53	$2.54	$0.00	$5.07
			Qty:	735	$1,859	$1,869	$0	$3,727
Assm:	06010505	**Descr:** Paint To Concrete Walls-One Coat Primer, One Coat Paint	**UOM:**	SF	$0.19	$0.53	$0.00	$0.72
			Qty:	333	$62	$178	$0	$239
Assm:	06020101	**Descr:** Thin Set Natural Clay Ceramic Tile Floor And Base	**UOM:**	SF	$6.69	$3.84	$0.00	$10.53
			Qty:	280	$1,874	$1,074	$0	$2,948
Assm:	06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF	$0.32	$0.59	$0.00	$0.92
			Qty:	336	$108	$200	$0	$308
Assm:	06030601	**Descr:** Painting To Drywall Or Plaster Using Rollers, 2 Coats	**UOM:**	SF	$0.10	$0.28	$0.00	$0.38
			Qty:	336	$34	$93	$0	$127
Assm:	06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF	$0.75	$4.08	$0.00	$4.83
			Qty:	336	$252	$1,371	$0	$1,623
Assm:	08010101	**Descr:** Floor Mounted Water Closet	**UOM:**	EA	$117.80	$120.14	$0.00	$237.94
			Qty:	1	$118	$120	$0	$238
Assm:	08010201	**Descr:** Floor Mounted Urinal	**UOM:**	EA	$446.88	$254.69	$0.00	$701.56
			Qty:	1	$447	$255	$0	$702
Assm:	08010303	**Descr:** Wall Hung 20" By 18" White Single Bowl Lavatory	**UOM:**	EA	$346.08	$304.54	$0.00	$650.62
			Qty:	1	$346	$305	$0	$651
Assm:	08010407	**Descr:** Janitor Sink - Floor Type	**UOM:**	EA	$468.25	$144.70	$0.00	$612.95
			Qty:	1	$468	$145	$0	$613
Assm:	08010502	**Descr:** Shower Valve, Drain For Ceramic Tile Shower	**UOM:**	EA	$563.55	$937.27	$0.00	$1,500.82
			Qty:	2	$1,127	$1,875	$0	$3,002

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	08010508	**Descr:** Fiberglass Shower Unit	**UOM:**	EA	$338.53	$265.30	$0.00	$603.82
			Qty:	2	$677	$531	$0	$1,208
Assm:	08010601	**Descr:** 8 GPH Electic Water Cooler - Wall Mounted	**UOM:**	EA	$531.74	$159.18	$0.00	$690.92
			Qty:	1	$532	$159	$0	$691
Assm:	11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA	$31.01	$170.59	$0.00	$201.60
			Qty:	2	$62	$341	$0	$403
Assm:	11020105	**Descr:** 120V Clock Receptacle	**UOM:**	EA	$38.58	$166.65	$0.00	$205.22
			Qty:	1	$39	$167	$0	$205
Assm:	11020108	**Descr:** Duplex GFI Receptacle Long Run	**UOM:**	EA	$68.91	$281.83	$0.00	$350.73
			Qty:	1	$69	$282	$0	$351
Assm:	11020109	**Descr:** 120V, 20 Amp Duplex Ground Fault Receptacle	**UOM:**	EA	$32.43	$173.15	$0.00	$205.59
			Qty:	1	$32	$173	$0	$206
Assm:	11020158	**Descr:** Thermal Motor Switch	**UOM:**	EA	$24.57	$160.34	$0.00	$184.91
			Qty:	1	$25	$160	$0	$185
Assm:	11020209	**Descr:** Surface Mount 2' X 4' Fluorescent Fixture	**UOM:**	EA	$90.67	$205.07	$0.00	$295.75
			Qty:	2	$181	$410	$0	$591
Assm:	11020210	**Descr:** 4' Vapor Tight Fluorescent Fixture	**UOM:**	EA	$105.85	$197.68	$0.00	$303.53
			Qty:	8	$847	$1,581	$0	$2,428
Assm:	11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA	$117.22	$212.56	$0.00	$329.78
			Qty:	1	$117	$213	$0	$330
Assm:	11020274	**Descr:** 6V Emergency Battery Pack	**UOM:**	EA	$75.96	$241.46	$0.00	$317.42
			Qty:	1	$76	$241	$0	$317

					Mat $	Lab $	Eqp $	Ttl $
Assm: 13011509	**Descr:** Oak Bench - 42"	**UOM:**	EA		$373.19	$15.59	$0.00	$388.78
		Qty:	2		$746	$31	$0	$778
Assm: 15900111	**Descr:** SAUNA	**UOM:**	SF		$66.86	$8.68	$0.00	$75.54
		Qty:	13		$869	$113	$0	$982

FSA: **ID:** KSM **Name:** KITCHEN (SMALL)

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010102	**Descr:** Mtl Stud Partition, 3-5/8", Sound Rated	**UOM:**	SF		$0.59	$0.94	$0.00	$1.54
		Qty:	291		$173	$274	$0	$447
Assm: 05050101	**Descr:** Plastic Laminate Countertop With Backsplash	**UOM:**	LF		$4.61	$10.00	$0.00	$14.61
		Qty:	9		$41	$90	$0	$132
Assm: 05050220	**Descr:** Plastic Laminated Wall Cabinet - 30" High, 12" Deep	**UOM:**	LF		$55.77	$7.50	$0.00	$63.27
		Qty:	4		$204	$27	$0	$232
Assm: 05050222	**Descr:** Plastic Laminated Base Cabinet - 24" Deep	**UOM:**	LF		$76.05	$15.00	$0.00	$91.04
		Qty:	9		$710	$140	$0	$850
Assm: 06010304	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$0.31	$0.59	$0.00	$0.90
		Qty:	262		$80	$156	$0	$236
Assm: 06010501	**Descr:** Paint To Gypsum Board Walls Using Roller	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	262		$27	$73	$0	$99
Assm: 06020404	**Descr:** Sheet Vinyl Resilient Flooring	**UOM:**	SF		$2.58	$1.16	$0.00	$3.73
		Qty:	89		$229	$103	$0	$332
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	120		$39	$71	$0	$110

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06030601	**Descr:** Painting To Drywall Or Plaster Using Rollers, 2 Coats	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	120		$12	$33	$0	$45
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	120		$90	$490	$0	$580
Assm: 08010402	**Descr:** S.S. Sink, Double Bowl 32 X 21 X 7	**UOM:**	EA		$438.37	$132.65	$0.00	$571.02
		Qty:	1		$438	$133	$0	$571
Assm: 11020101	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	**UOM:**	EA		$26.43	$164.10	$0.00	$190.53
		Qty:	2		$53	$328	$0	$381
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	1		$31	$171	$0	$202
Assm: 11020109	**Descr:** 120V, 20 Amp Duplex Ground Fault Receptacle	**UOM:**	EA		$32.43	$173.15	$0.00	$205.59
		Qty:	1		$32	$173	$0	$206
Assm: 11020214	**Descr:** Surface Mounted 1' X 4' Fluorescent Fixture	**UOM:**	EA		$101.83	$186.65	$0.00	$288.48
		Qty:	1		$102	$187	$0	$288

FSA: **ID:** MHF **Name:** HAZARDOUS MATERIAL STORAGE - FLAMMABLE

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 05010119	**Descr:** 8 X 12 X 16 Load Bearing Concrete Masonry Unit Wall	**UOM:**	SF		$6.59	$8.57	$0.09	$15.26
		Qty:	19		$125	$163	$2	$290
Assm: 05030101	**Descr:** Coiling Overhead Door	**UOM:**	EA		$1,101.78	$1,107.72	$0.00	$2,209.50
		Qty:	1		$1,102	$1,108	$0	$2,210
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	62		$18	$44	$0	$62

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06020801	**Descr:** Epoxy Floor Coating	**UOM:**	SF		$2.87	$2.58	$0.10	$5.56
		Qty:	100		$287	$258	$10	$556
Assm: 11020146	**Descr:** Explosion Proof Equipment Connection 5 - 25 HP	**UOM:**	EA		$1,336.04	$537.38	$0.00	$1,873.42
		Qty:	1		$1,336	$537	$0	$1,873
Assm: 11020228	**Descr:** 250W Hps Wall Pack	**UOM:**	EA		$291.34	$229.01	$0.00	$520.35
		Qty:	1		$291	$229	$0	$520
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020264	**Descr:** Explosion Proof Hps Low Bay	**UOM:**	EA		$629.98	$351.27	$0.00	$981.25
		Qty:	1		$630	$351	$0	$981
Assm: 11020265	**Descr:** Explosion Proof Exit W/Batt. Back Up	**UOM:**	EA		$744.78	$336.13	$0.00	$1,080.91
		Qty:	1		$745	$336	$0	$1,081
Assm: 11020274	**Descr:** 6V Emergency Battery Pack	**UOM:**	EA		$75.96	$241.46	$0.00	$317.42
		Qty:	1		$76	$241	$0	$317

FSA: **ID:** OFC **Name:** OFFICE - CLOSED OFFICE SPACE

Facility Type: Supporting **ID:** 13 **Name:** MWL Storage Facility Office

Assm: 05010101	**Descr:** Mtl Stud Partition, 3-5/8"	**UOM:**	SF		$0.18	$0.62	$0.00	$0.79
		Qty:	563		$99	$346	$0	$445
Assm: 05010102	**Descr:** Mtl Stud Partition, 3-5/8", Sound Rated	**UOM:**	SF		$0.59	$0.94	$0.00	$1.54
		Qty:	63		$37	$59	$0	$97
Assm: 05010504	**Descr:** Fixed Type Window With Aluminum Frm - 3/4" Clear Glass	**UOM:**	SF		$16.81	$6.30	$0.00	$23.11
		Qty:	1		$17	$6	$0	$23

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05020117	**Descr:** 3'0" X 7'0" Wood Door, H.M. Frm	**UOM:**	EA		$367.74	$177.69	$0.00	$545.43
		Qty:	2		$735	$355	$0	$1,091
Assm: 05020303	**Descr:** 3'0" X 7'0" Fire Rated Wood Door	**UOM:**	EA		$512.62	$187.37	$0.00	$699.99
		Qty:	1		$513	$187	$0	$700
Assm: 05020304	**Descr:** 6'0" X 7'0" Pair Fire Rated Wood Doors	**UOM:**	EA		$961.62	$345.72	$0.00	$1,307.34
		Qty:	1		$962	$346	$0	$1,307
Assm: 05040301	**Descr:** Porcelain Enamel Chalkboard	**UOM:**	SF		$16.66	$22.28	$0.00	$38.94
		Qty:	5		$83	$111	$0	$195
Assm: 05040601	**Descr:** 10" Wide Stock Prefinished Shelves With Supports	**UOM:**	LF		$3.84	$4.29	$0.00	$8.13
		Qty:	600		$2,302	$2,574	$0	$4,876
Assm: 05050101	**Descr:** Plastic Laminate Countertop With Backsplash	**UOM:**	LF		$4.61	$10.00	$0.00	$14.61
		Qty:	12		$55	$120	$0	$175
Assm: 05050201	**Descr:** Plastic Laminate Cabinets With Countertop And Drawers	**UOM:**	LF		$135.86	$32.22	$0.00	$168.08
		Qty:	9		$1,223	$290	$0	$1,513
Assm: 06010301	**Descr:** 5/8" Gypsum Board On 7/8" Furring Channel	**UOM:**	SF		$0.73	$3.09	$0.00	$3.83
		Qty:	68		$50	$210	$0	$260
Assm: 06010303	**Descr:** Two Layers Of 5/8" Fire Resistant Gypsum Board	**UOM:**	SF		$1.04	$1.29	$0.00	$2.33
		Qty:	13		$13	$17	$0	$30
Assm: 06010304	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$0.31	$0.59	$0.00	$0.90
		Qty:	717		$219	$426	$0	$646
Assm: 06010501	**Descr:** Paint To Gypsum Board Walls Using Roller	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	771		$79	$213	$0	$292

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06010601	**Descr:** Light Weight Vinyl Wallcovering With Fabric Backing	**UOM:**	SF		$0.51	$0.41	$0.00	$0.92
		Qty:	75		$38	$31	$0	$69
Assm: 06010701	**Descr:** 4' X 8' X 1" Fiberglass Sound Absorbing Panels	**UOM:**	SF		$1.56	$0.58	$0.00	$2.14
		Qty:	14		$22	$8	$0	$30
Assm: 06020401	**Descr:** Vinyl Tile 1/8" X 12" X 12"	**UOM:**	SF		$2.96	$0.82	$0.00	$3.78
		Qty:	56		$166	$46	$0	$212
Assm: 06020501	**Descr:** Commercial Grade 26 Oz. Nylon Carpet	**UOM:**	SY		$14.84	$6.16	$0.00	$21.00
		Qty:	58		$861	$357	$0	$1,218
Assm: 06030402	**Descr:** 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	**UOM:**	SF		$0.43	$0.42	$0.00	$0.85
		Qty:	576		$246	$241	$0	$488
Assm: 06030703	**Descr:** T-Bar Ceiling Suspension System 2' X 4' Grid	**UOM:**	SF		$0.31	$0.37	$0.00	$0.67
		Qty:	576		$176	$213	$0	$389
Assm: 11020101	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	**UOM:**	EA		$26.43	$164.10	$0.00	$190.53
		Qty:	9		$238	$1,477	$0	$1,715
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020121	**Descr:** 230 Volt, 30 Amp Receptacle - Stud Partition	**UOM:**	EA		$93.48	$381.13	$0.00	$474.61
		Qty:	1		$93	$381	$0	$475
Assm: 11020202	**Descr:** 2' X 4' Lay-In Fluorescent Fixture	**UOM:**	EA		$69.29	$182.23	$0.00	$251.52
		Qty:	10		$693	$1,822	$0	$2,515
Assm: 11020220	**Descr:** Ceiling Recessed Incandescent 100 Watt Fixture	**UOM:**	EA		$72.89	$144.66	$0.00	$217.55
		Qty:	1		$73	$145	$0	$218

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11029011	**Descr:** Fire Alarm Pull Station	**UOM:**	EA		$41.30	$155.77	$0.00	$197.07
		Qty:	1		$41	$156	$0	$197
FSA:	**ID:** OFO	**Name:**	OFFICE - OPEN OFFICE SPACE					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				
Assm: 05010101	**Descr:** Mtl Stud Partition, 3-5/8"	**UOM:**	SF		$0.18	$0.62	$0.00	$0.79
		Qty:	223		$39	$137	$0	$176
Assm: 05010102	**Descr:** Mtl Stud Partition, 3-5/8", Sound Rated	**UOM:**	SF		$0.59	$0.94	$0.00	$1.54
		Qty:	64		$38	$60	$0	$98
Assm: 05010113	**Descr:** Non-Load Brg Partition Of 8 X 8 X 16 Concrete	**UOM:**	SF		$2.08	$3.86	$0.00	$5.94
		Qty:	32		$67	$123	$0	$190
Assm: 06010301	**Descr:** 5/8" Gypsum Board On 7/8" Furring Channel	**UOM:**	SF		$0.73	$3.09	$0.00	$3.83
		Qty:	52		$38	$161	$0	$199
Assm: 06010303	**Descr:** Two Layers Of 5/8" Fire Resistant Gypsum Board	**UOM:**	SF		$1.04	$1.29	$0.00	$2.33
		Qty:	10		$10	$13	$0	$23
Assm: 06010304	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$0.31	$0.59	$0.00	$0.90
		Qty:	469		$143	$279	$0	$422
Assm: 06010501	**Descr:** Paint To Gypsum Board Walls Using Roller	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	521		$53	$144	$0	$197
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	87		$25	$62	$0	$87
Assm: 06020401	**Descr:** Vinyl Tile 1/8" X 12" X 12"	**UOM:**	SF		$2.96	$0.82	$0.00	$3.78
		Qty:	163		$483	$133	$0	$616

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06020501	**Descr:** Commercial Grade 26 Oz. Nylon Carpet	**UOM:**	SY		$14.84	$6.16	$0.00	$21.00
		Qty:	107		$1,588	$659	$0	$2,247
Assm: 06030302	**Descr:** 5/8" Gypsum Wallboard Ceiling, 3 Layers, Over 8 Ft.	**UOM:**	SF		$0.78	$1.47	$0.00	$2.25
		Qty:	49		$38	$72	$0	$110
Assm: 06030402	**Descr:** 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	**UOM:**	SF		$0.43	$0.42	$0.00	$0.85
		Qty:	1079		$461	$452	$0	$913
Assm: 06030601	**Descr:** Painting To Drywall Or Plaster Using Rollers, 2 Coats	**UOM:**	SF		$0.10	$0.28	$0.00	$0.38
		Qty:	49		$5	$14	$0	$19
Assm: 06030703	**Descr:** T-Bar Ceiling Suspension System 2' X 4' Grid	**UOM:**	SF		$0.31	$0.37	$0.00	$0.67
		Qty:	1079		$330	$398	$0	$728
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	49		$37	$200	$0	$237
Assm: 11020101	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Stud Partition	**UOM:**	EA		$26.43	$164.10	$0.00	$190.53
		Qty:	6		$159	$985	$0	$1,143
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020111	**Descr:** 120 Volt, 20 Amp Duplex Floor Mounted Receptacle	**UOM:**	EA		$145.66	$215.25	$0.00	$360.91
		Qty:	1		$146	$215	$0	$361
Assm: 11020202	**Descr:** 2' X 4' Lay-In Fluorescent Fixture	**UOM:**	EA		$69.29	$182.23	$0.00	$251.52
		Qty:	17		$1,178	$3,098	$0	$4,276
Assm: 11020220	**Descr:** Ceiling Recessed Incandescent 100 Watt Fixture	**UOM:**	EA		$72.89	$144.66	$0.00	$217.55
		Qty:	1		$73	$145	$0	$218

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11029011	**Descr:** Fire Alarm Pull Station	**UOM:**	EA		$41.30	$155.77	$0.00	$197.07
		Qty:	1		$41	$156	$0	$197
FSA:	**ID:** SEC	**Name:**	SECURITY					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				
Assm: 05010113	**Descr:** Non-Load Brg Partition Of 8 X 8 X 16 Concrete	**UOM:**	SF		$2.08	$3.86	$0.00	$5.94
		Qty:	84		$175	$324	$0	$499
Assm: 06010301	**Descr:** 5/8" Gypsum Board On 7/8" Furring Channel	**UOM:**	SF		$0.73	$3.09	$0.00	$3.83
		Qty:	145		$106	$449	$0	$555
Assm: 06010303	**Descr:** Two Layers Of 5/8" Fire Resistant Gypsum Board	**UOM:**	SF		$1.04	$1.29	$0.00	$2.33
		Qty:	29		$30	$37	$0	$67
Assm: 06010701	**Descr:** 4' X 8' X 1" Fiberglass Sound Absorbing Panels	**UOM:**	SF		$1.56	$0.58	$0.00	$2.14
		Qty:	50		$78	$29	$0	$107
Assm: 06020501	**Descr:** Commercial Grade 26 Oz. Nylon Carpet	**UOM:**	SY		$14.84	$6.16	$0.00	$21.00
		Qty:	6		$89	$37	$0	$126
Assm: 06030703	**Descr:** T-Bar Ceiling Suspension System 2' X 4' Grid	**UOM:**	SF		$0.31	$0.37	$0.00	$0.67
		Qty:	50		$15	$18	$0	$34
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	1		$31	$171	$0	$202
Assm: 11020202	**Descr:** 2' X 4' Lay-In Fluorescent Fixture	**UOM:**	EA		$69.29	$182.23	$0.00	$251.52
		Qty:	1		$69	$182	$0	$252
FSA:	**ID:** WOR	**Name:**	WORK AREA					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	06010504	**Descr:** Special Coating	**UOM:**	SF	$0.35	$0.72	$0.00	$1.07
			Qty:	59	$21	$42	$0	$63
Assm:	06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF	$0.18	$0.32	$0.00	$0.49
			Qty:	384	$68	$121	$0	$190
Assm:	07030201	**Descr:** Overhead Monorail - 2000 Lb Capacity	**UOM:**	EA	$2,092.46	$269.53	$0.00	$2,361.99
			Qty:	1	$2,092	$270	$0	$2,362
Assm:	07030203	**Descr:** Overhead Monorail - 6000 Lb Capacity	**UOM:**	EA	$3,976.38	$328.25	$0.00	$4,304.63
			Qty:	1	$3,976	$328	$0	$4,305
Assm:	09089010	**Descr:** Compressed Air System For Material Cutting Area (8 Out)	**UOM:**	EA	$7,553.80	$6,586.32	$0.00	$14,140.12
			Qty:	1	$7,554	$6,586	$0	$14,140
Assm:	11020132	**Descr:** Explosion Proof 30A Rec	**UOM:**	EA	$1,590.17	$766.06	$0.00	$2,356.23
			Qty:	1	$1,590	$766	$0	$2,356
Assm:	11020146	**Descr:** Explosion Proof Equipment Connection 5 - 25 HP	**UOM:**	EA	$1,336.04	$537.38	$0.00	$1,873.42
			Qty:	1	$1,336	$537	$0	$1,873
Assm:	11020147	**Descr:** Explosion Proof Equipment Connection 30 - 60 HP	**UOM:**	EA	$1,981.83	$667.92	$0.00	$2,649.75
			Qty:	1	$1,982	$668	$0	$2,650
Assm:	11020242	**Descr:** 150W Hps Hazardous Flood	**UOM:**	EA	$688.89	$285.48	$0.00	$974.37
			Qty:	1	$689	$285	$0	$974
Assm:	11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA	$200.94	$375.90	$0.00	$576.85
			Qty:	1	$201	$376	$0	$577
Assm:	11020256	**Descr:** Twin Mounted High Bay 400W Hps Fixture W/Quartz Standby	**UOM:**	EA	$464.53	$574.55	$0.00	$1,039.08
			Qty:	1	$465	$575	$0	$1,039

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	1		$117	$213	$0	$330
Assm: 11020274	**Descr:** 6V Emergency Battery Pack	**UOM:**	EA		$75.96	$241.46	$0.00	$317.42
		Qty:	1		$76	$241	$0	$317
Assm: 11020278	**Descr:** Accent Wall Fixture, 100W	**UOM:**	EA		$34.93	$200.29	$0.00	$235.22
		Qty:	1		$35	$200	$0	$235
FSA:	**ID:** XDA	**Name:**	DINING AREA					
Facility Type:	Supporting	**ID:** 13	**Name:**	MWL Storage Facility Office				
Assm: 05010113	**Descr:** Non-Load Brg Partition Of 8 X 8 X 16 Concrete	**UOM:**	SF		$2.08	$3.86	$0.00	$5.94
		Qty:	36		$75	$139	$0	$214
Assm: 05040401	**Descr:** Door Sign, 3" X 8"	**UOM:**	EA		$8.77	$7.35	$0.00	$16.12
		Qty:	1		$9	$7	$0	$16
Assm: 05040702	**Descr:** Fire Extinguisher Cabinet, 8" X 16" X 38"	**UOM:**	EA		$124.88	$111.47	$0.00	$236.35
		Qty:	1		$125	$111	$0	$236
Assm: 06010504	**Descr:** Special Coating	**UOM:**	SF		$0.35	$0.72	$0.00	$1.07
		Qty:	67		$24	$48	$0	$72
Assm: 06020401	**Descr:** Vinyl Tile 1/8" X 12" X 12"	**UOM:**	SF		$2.96	$0.82	$0.00	$3.78
		Qty:	120		$356	$98	$0	$454
Assm: 06030402	**Descr:** 2' X 2' Or 2' X 4' Fiberglass Acoustical Ceiling Tiles	**UOM:**	SF		$0.43	$0.42	$0.00	$0.85
		Qty:	120		$51	$50	$0	$102
Assm: 06030702	**Descr:** T-Bar Ceiling Suspension System 2' X 2' Grid	**UOM:**	SF		$0.37	$0.45	$0.00	$0.82
		Qty:	120		$44	$54	$0	$99

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	1		$31	$171	$0	$202
Assm: 11020111	**Descr:** 120 Volt, 20 Amp Duplex Floor Mounted Receptacle	**UOM:**	EA		$145.66	$215.25	$0.00	$360.91
		Qty:	1		$146	$215	$0	$361
Assm: 11020137	**Descr:** Equipment Connections For Up To 10 HP	**UOM:**	EA		$301.38	$572.98	$0.00	$874.36
		Qty:	1		$301	$573	$0	$874
Assm: 11020202	**Descr:** 2' X 4' Lay-In Fluorescent Fixture	**UOM:**	EA		$69.29	$182.23	$0.00	$251.52
		Qty:	2		$139	$364	$0	$503
Assm: 11020207	**Descr:** 2' X 4' Lay-In Fluorescent Fixture With Emergency Unit	**UOM:**	EA		$146.08	$182.23	$0.00	$328.32
		Qty:	1		$146	$182	$0	$328
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	1		$117	$213	$0	$330
FSA: **ID:**	**Name:** Building Shell							
Facility Type: Primary	**ID:** 45	**Name:** UnClass Soil Storage Warehouse 2						
Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	4622		$51,550	$50,376	$784	$102,709
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	2558		$55,296	$45,684	$748	$101,728
Assm: 01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF		$20.15	$26.26	$0.21	$46.63
		Qty:	4622		$93,158	$121,396	$959	$215,512
Assm: 01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF		$14.13	$21.63	$0.07	$35.83
		Qty:	5116		$72,275	$110,653	$377	$183,305

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01010201	**Descr:** Spread Footing	**UOM:**	CY	$73.57	$45.75	$2.16	$121.48
			Qty:	1360	$100,050	$62,224	$2,937	$165,211
Assm:	01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA	$87.34	$173.72	$1.69	$262.75
			Qty:	245	$21,399	$42,561	$414	$64,374
Assm:	01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON	$551.26	$645.22	$0.00	$1,196.47
			Qty:	15	$8,164	$9,556	$0	$17,720
Assm:	01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF	$14.64	$18.55	$0.16	$33.35
			Qty:	13991	$204,791	$259,584	$2,262	$466,637
Assm:	01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF	$2.01	$2.62	$0.16	$4.79
			Qty:	570581	$1,146,868	$1,495,550	$91,464	$2,733,882
Assm:	01030115	**Descr:** Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
			Qty:	36155	$140,715	$83,641	$2,863	$227,220
Assm:	02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
			Qty:	235108	$1,408,438	$1,894,030	$22,194	$3,324,662
Assm:	02020313	**Descr:** Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
			Qty:	634056	$3,145,171	$754,463	$215,325	$4,114,960
Assm:	02020314	**Descr:** 3" Topping Slab	**UOM:**	SF	$0.77	$0.57	$0.04	$1.38
			Qty:	634056	$489,238	$358,812	$25,362	$873,412
Assm:	03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF	$11.02	$1.21	$0.17	$12.40
			Qty:	42194	$465,134	$51,004	$7,215	$523,353
Assm:	03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
			Qty:	42194	$9,679	$15,270	$1,063	$26,013

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF		$0.51	$0.46	$0.00	$0.98
		Qty:	42194		$21,548	$19,612	$0	$41,160
Assm: 03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF		$0.19	$0.53	$0.00	$0.72
		Qty:	42194		$7,819	$22,494	$0	$30,312
Assm: 03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF		$29.84	$12.28	$0.00	$42.12
		Qty:	956		$28,526	$11,738	$0	$40,264
Assm: 03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA		$608.95	$579.12	$0.00	$1,188.07
		Qty:	3		$1,827	$1,737	$0	$3,564
Assm: 03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA		$1,287.09	$468.13	$0.00	$1,755.22
		Qty:	20		$25,742	$9,363	$0	$35,104
Assm: 03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA		$2,328.71	$734.80	$0.00	$3,063.51
		Qty:	3		$6,986	$2,204	$0	$9,191
Assm: 03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA		$3,536.29	$1,914.35	$99.90	$5,550.54
		Qty:	38		$134,379	$72,745	$3,796	$210,921
Assm: 04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF		$2.03	$1.26	$0.00	$3.29
		Qty:	634056		$1,287,768	$797,706	$0	$2,085,474
Assm: 04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF		$0.35	$0.24	$0.00	$0.59
		Qty:	634056		$223,378	$152,871	$0	$376,249
Assm: 04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF		$23.64	$4.31	$0.00	$27.94
		Qty:	6071		$143,492	$26,159	$0	$169,652
Assm: 04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF		$1.59	$3.61	$0.00	$5.20
		Qty:	180		$287	$650	$0	$937

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	24	$4,890	$17,297	$0	$22,188
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	13	$1,182	$326	$0	$1,508
Assm:	08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
			Qty:	24	$1,888	$1,976	$0	$3,864
Assm:	08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
			Qty:	30	$5,404	$10,856	$0	$16,261
Assm:	08030202	**Descr:** PVC Vent Piping	**UOM:**	EA	$13.95	$47.57	$0.00	$61.51
			Qty:	30	$418	$1,427	$0	$1,845
Assm:	08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA	$409.55	$63.67	$0.00	$473.21
			Qty:	6	$2,457	$382	$0	$2,839
Assm:	08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA	$299.10	$172.74	$0.00	$471.84
			Qty:	2	$598	$345	$0	$944
Assm:	08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA	$400.59	$43.19	$0.00	$443.77
			Qty:	3	$1,202	$130	$0	$1,331
Assm:	08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA	$2,609.25	$939.01	$0.00	$3,548.25
			Qty:	2	$5,218	$1,878	$0	$7,097
Assm:	08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA	$362.85	$935.23	$0.00	$1,298.08
			Qty:	2	$726	$1,870	$0	$2,596
Assm:	08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA	$1,401.67	$222.85	$0.00	$1,624.52
			Qty:	2	$2,803	$446	$0	$3,249

Project Summary Report

Date 07/26/2002

				Mat $	Lab $	Eqp $	Ttl $
Assm: 09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA	$10,823.28	$10,577.38	$148.33	$21,548.98
		Qty:	1	$10,823	$10,577	$148	$21,549
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA	$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	112	$337,806	$94,021	$190	$432,017
Assm: 09030209	**Descr:** 15 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA	$8,123.97	$3,365.04	$0.00	$11,489.01
		Qty:	2	$16,248	$6,730	$0	$22,978
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM	$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	1	$659	$984	$0	$1,642
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM	$418.17	$71.07	$0.00	$489.24
		Qty:	359	$150,205	$25,530	$0	$175,735
Assm: 09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM	$3,520.33	$790.73	$0.00	$4,311.06
		Qty:	10	$34,781	$7,812	$0	$42,593
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM	$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	0	$356	$508	$0	$865
Assm: 09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM	$3,706.36	$4,390.65	$0.00	$8,097.01
		Qty:	2	$8,636	$10,230	$0	$18,866
Assm: 09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM	$1,645.75	$4,920.50	$0.00	$6,566.24
		Qty:	2	$2,847	$8,512	$0	$11,360
Assm: 09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA	$122.32	$58.85	$0.00	$181.17
		Qty:	2	$245	$118	$0	$362
Assm: 09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA	$19,211.52	$29,488.79	$0.00	$48,700.31
		Qty:	1	$19,212	$29,489	$0	$48,700

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA	$0.00	$206.44	$0.00	$206.44
			Qty:	35	$0	$7,225	$0	$7,225
Assm:	09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA	$0.00	$309.73	$0.00	$309.73
			Qty:	58	$0	$17,964	$0	$17,964
Assm:	09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA	$0.00	$413.28	$0.00	$413.28
			Qty:	3	$0	$1,240	$0	$1,240
Assm:	09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA	$39.90	$68.74	$0.00	$108.64
			Qty:	1	$40	$69	$0	$109
Assm:	10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
			Qty:	4962	$238,327	$105,928	$1,089	$345,344
Assm:	10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
			Qty:	4962	$141,102	$404,000	$0	$545,102
Assm:	11010108	**Descr:** Electrical 2500A Main Transformer	**UOM:**	EA	$29,512.44	$4,886.87	$96.72	$34,496.03
			Qty:	1	$29,512	$4,887	$97	$34,496
Assm:	11010211	**Descr:** Electrical 2500A Secondary	**UOM:**	EA	$37,780.63	$23,682.69	$47.01	$61,510.33
			Qty:	1	$37,781	$23,683	$47	$61,510
Assm:	11010311	**Descr:** Electrical 2500A Main Switchboard	**UOM:**	EA	$91,215.75	$9,632.58	$0.00	$100,848.33
			Qty:	1	$91,216	$9,633	$0	$100,848
Assm:	11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
			Qty:	9	$19,349	$9,348	$0	$28,697
Assm:	11010502	**Descr:** Panelbd 208V 100A 30 Cir Mlo W/Bkr	**UOM:**	EA	$1,153.60	$899.36	$0.00	$2,052.95
			Qty:	8	$9,229	$7,195	$0	$16,424

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
			Qty:	8	$14,177	$17,881	$0	$32,058
Assm:	11010516	**Descr:** Panelbd 208V 225A MCB 42 Cir W/Bkr	**UOM:**	EA	$2,088.56	$2,391.53	$0.00	$4,480.09
			Qty:	1	$2,089	$2,392	$0	$4,480
Assm:	11010561	**Descr:** Panelbd 480V 600A MCB 42 Cir W/Bkr	**UOM:**	EA	$7,082.74	$3,958.17	$0.00	$11,040.92
			Qty:	2	$14,165	$7,916	$0	$22,082
Assm:	11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA	$1,805.61	$1,767.07	$0.00	$3,572.68
			Qty:	1	$1,806	$1,767	$0	$3,573
Assm:	12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT	$102.32	$374.83	$0.00	$477.15
			Qty:	192	$19,646	$71,968	$0	$91,614
Assm:	12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA	$6,181.75	$3,465.03	$0.00	$9,646.78
			Qty:	2	$12,363	$6,930	$0	$19,294
Assm:	12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA	$42.39	$176.98	$0.00	$219.38
			Qty:	55	$2,332	$9,734	$0	$12,066
Assm:	12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF	$0.03	$0.07	$0.00	$0.10
			Qty:	570584	$16,889	$40,968	$0	$57,857
Assm:	12010601	**Descr:** Clock System	**UOM:**	EA	$222.34	$177.74	$0.00	$400.08
			Qty:	25	$5,559	$4,444	$0	$10,002
Assm:	12010602	**Descr:** Time Clock System	**UOM:**	EA	$334.18	$866.03	$0.00	$1,200.22
			Qty:	9	$3,008	$7,794	$0	$10,802
Assm:	12020221	**Descr:** Battery Charger	**UOM:**	EA	$1,043.18	$619.45	$0.00	$1,662.63
			Qty:	34	$35,468	$21,061	$0	$56,529

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	30		$2,356	$4,241	$0	$6,598
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	97		$90,449	$38,969	$0	$129,418

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601
FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT								
Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2								
Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199
FSA: **ID:** SRM **Name:** STOCKROOM								
Facility Type: Primary **ID:** 45 **Name:** UnClass Soil Storage Warehouse 2								

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF	$1.97	$3.68	$0.00	$5.65
		Qty:	18778	$36,906	$69,184	$0	$106,090
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF	$1.68	$1.66	$0.00	$3.34
		Qty:	139792	$234,655	$231,565	$0	$466,220
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF	$3.37	$1.04	$0.00	$4.41
		Qty:	3901	$13,144	$4,039	$0	$17,184
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF	$35.54	$9.59	$0.00	$45.13
		Qty:	7231	$257,009	$69,340	$0	$326,349
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF	$0.29	$0.72	$0.00	$1.00
		Qty:	11265	$3,235	$8,084	$0	$11,319
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF	$0.04	$0.05	$0.00	$0.08
		Qty:	568936	$20,994	$27,252	$0	$48,246
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF	$0.18	$0.32	$0.00	$0.49
		Qty:	568936	$101,441	$179,727	$0	$281,168
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA	$48.69	$297.44	$0.00	$346.13
		Qty:	240	$11,687	$71,386	$0	$83,072
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA	$267.15	$527.09	$0.00	$794.24
		Qty:	175	$46,751	$92,240	$0	$138,991
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA	$175.34	$236.30	$0.00	$411.64
		Qty:	72	$12,625	$17,013	$0	$29,638
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA	$200.94	$375.90	$0.00	$576.85
		Qty:	931	$187,080	$349,963	$0	$537,043

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	125		$37,089	$58,498	$0	$95,588
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	21		$2,462	$4,464	$0	$6,925

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

					Mat $	Lab $	Eqp $	Ttl $
Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	4622		$51,550	$50,376	$784	$102,709
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	2558		$55,296	$45,684	$748	$101,728
Assm: 01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF		$20.15	$26.26	$0.21	$46.63
		Qty:	4622		$93,158	$121,396	$959	$215,512
Assm: 01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF		$14.13	$21.63	$0.07	$35.83
		Qty:	5116		$72,275	$110,653	$377	$183,305
Assm: 01010201	**Descr:** Spread Footing	**UOM:**	CY		$73.57	$45.75	$2.16	$121.48
		Qty:	1360		$100,050	$62,224	$2,937	$165,211
Assm: 01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA		$87.34	$173.72	$1.69	$262.75
		Qty:	245		$21,399	$42,561	$414	$64,374
Assm: 01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON		$551.26	$645.22	$0.00	$1,196.47
		Qty:	15		$8,164	$9,556	$0	$17,720
Assm: 01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF		$14.64	$18.55	$0.16	$33.35
		Qty:	13991		$204,791	$259,584	$2,262	$466,637

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF	$2.01	$2.62	$0.16	$4.79
			Qty:	570581	$1,146,868	$1,495,550	$91,464	$2,733,882
Assm:	01030115	**Descr:** Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
			Qty:	36155	$140,715	$83,641	$2,863	$227,220
Assm:	02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
			Qty:	235108	$1,408,438	$1,894,030	$22,194	$3,324,662
Assm:	02020313	**Descr:** Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
			Qty:	634056	$3,145,171	$754,463	$215,325	$4,114,960
Assm:	02020314	**Descr:** 3" Topping Slab	**UOM:**	SF	$0.77	$0.57	$0.04	$1.38
			Qty:	634056	$489,238	$358,812	$25,362	$873,412
Assm:	03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF	$11.02	$1.21	$0.17	$12.40
			Qty:	42194	$465,134	$51,004	$7,215	$523,353
Assm:	03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
			Qty:	42194	$9,679	$15,270	$1,063	$26,013
Assm:	03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF	$0.51	$0.46	$0.00	$0.98
			Qty:	42194	$21,548	$19,612	$0	$41,160
Assm:	03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF	$0.19	$0.53	$0.00	$0.72
			Qty:	42194	$7,819	$22,494	$0	$30,312
Assm:	03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF	$29.84	$12.28	$0.00	$42.12
			Qty:	956	$28,526	$11,738	$0	$40,264
Assm:	03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA	$608.95	$579.12	$0.00	$1,188.07
			Qty:	3	$1,827	$1,737	$0	$3,564

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA	$1,287.09	$468.13	$0.00	$1,755.22
			Qty:	20	$25,742	$9,363	$0	$35,104
Assm:	03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
			Qty:	3	$6,986	$2,204	$0	$9,191
Assm:	03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA	$3,536.29	$1,914.35	$99.90	$5,550.54
			Qty:	38	$134,379	$72,745	$3,796	$210,921
Assm:	04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
			Qty:	634056	$1,287,768	$797,706	$0	$2,085,474
Assm:	04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
			Qty:	634056	$223,378	$152,871	$0	$376,249
Assm:	04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
			Qty:	6071	$143,492	$26,159	$0	$169,652
Assm:	04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
			Qty:	180	$287	$650	$0	$937
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	24	$4,890	$17,297	$0	$22,188
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	13	$1,182	$326	$0	$1,508
Assm:	08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
			Qty:	24	$1,888	$1,976	$0	$3,864
Assm:	08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
			Qty:	30	$5,404	$10,856	$0	$16,261

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	08030202	**Descr:** PVC Vent Piping	**UOM:**	EA	$13.95	$47.57	$0.00	$61.51
			Qty:	30	$418	$1,427	$0	$1,845
Assm:	08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA	$409.55	$63.67	$0.00	$473.21
			Qty:	6	$2,457	$382	$0	$2,839
Assm:	08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA	$299.10	$172.74	$0.00	$471.84
			Qty:	2	$598	$345	$0	$944
Assm:	08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA	$400.59	$43.19	$0.00	$443.77
			Qty:	3	$1,202	$130	$0	$1,331
Assm:	08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA	$2,609.25	$939.01	$0.00	$3,548.25
			Qty:	2	$5,218	$1,878	$0	$7,097
Assm:	08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA	$362.85	$935.23	$0.00	$1,298.08
			Qty:	2	$726	$1,870	$0	$2,596
Assm:	08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA	$1,401.67	$222.85	$0.00	$1,624.52
			Qty:	2	$2,803	$446	$0	$3,249
Assm:	09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA	$10,823.28	$10,577.38	$148.33	$21,548.98
			Qty:	1	$10,823	$10,577	$148	$21,549
Assm:	09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA	$3,016.12	$839.47	$1.70	$3,857.29
			Qty:	112	$337,806	$94,021	$190	$432,017
Assm:	09030209	**Descr:** 15 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA	$8,123.97	$3,365.04	$0.00	$11,489.01
			Qty:	2	$16,248	$6,730	$0	$22,978
Assm:	09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM	$1,116.15	$1,667.16	$0.00	$2,783.31
			Qty:	1	$659	$984	$0	$1,642

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM	$418.17	$71.07	$0.00	$489.24
			Qty:	359	$150,205	$25,530	$0	$175,735
Assm:	09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM	$3,520.33	$790.73	$0.00	$4,311.06
			Qty:	10	$34,781	$7,812	$0	$42,593
Assm:	09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM	$1,370.16	$1,955.73	$0.00	$3,325.89
			Qty:	0	$356	$508	$0	$865
Assm:	09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM	$3,706.36	$4,390.65	$0.00	$8,097.01
			Qty:	2	$8,636	$10,230	$0	$18,866
Assm:	09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM	$1,645.75	$4,920.50	$0.00	$6,566.24
			Qty:	2	$2,847	$8,512	$0	$11,360
Assm:	09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA	$122.32	$58.85	$0.00	$181.17
			Qty:	2	$245	$118	$0	$362
Assm:	09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA	$19,211.52	$29,488.79	$0.00	$48,700.31
			Qty:	1	$19,212	$29,489	$0	$48,700
Assm:	09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA	$0.00	$206.44	$0.00	$206.44
			Qty:	35	$0	$7,225	$0	$7,225
Assm:	09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA	$0.00	$309.73	$0.00	$309.73
			Qty:	58	$0	$17,964	$0	$17,964
Assm:	09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA	$0.00	$413.28	$0.00	$413.28
			Qty:	3	$0	$1,240	$0	$1,240
Assm:	09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA	$39.90	$68.74	$0.00	$108.64
			Qty:	1	$40	$69	$0	$109

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
			Qty:	4962	$238,327	$105,928	$1,089	$345,344
Assm:	10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
			Qty:	4962	$141,102	$404,000	$0	$545,102
Assm:	11010108	**Descr:** Electrical 2500A Main Transformer	**UOM:**	EA	$29,512.44	$4,886.87	$96.72	$34,496.03
			Qty:	1	$29,512	$4,887	$97	$34,496
Assm:	11010211	**Descr:** Electrical 2500A Secondary	**UOM:**	EA	$37,780.63	$23,682.69	$47.01	$61,510.33
			Qty:	1	$37,781	$23,683	$47	$61,510
Assm:	11010311	**Descr:** Electrical 2500A Main Switchboard	**UOM:**	EA	$91,215.75	$9,632.58	$0.00	$100,848.33
			Qty:	1	$91,216	$9,633	$0	$100,848
Assm:	11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
			Qty:	9	$19,349	$9,348	$0	$28,697
Assm:	11010502	**Descr:** Panelbd 208V 100A 30 Cir Mlo W/Bkr	**UOM:**	EA	$1,153.60	$899.36	$0.00	$2,052.95
			Qty:	8	$9,229	$7,195	$0	$16,424
Assm:	11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
			Qty:	8	$14,177	$17,881	$0	$32,058
Assm:	11010516	**Descr:** Panelbd 208V 225A MCB 42 Cir W/Bkr	**UOM:**	EA	$2,088.56	$2,391.53	$0.00	$4,480.09
			Qty:	1	$2,089	$2,392	$0	$4,480
Assm:	11010561	**Descr:** Panelbd 480V 600A MCB 42 Cir W/Bkr	**UOM:**	EA	$7,082.74	$3,958.17	$0.00	$11,040.92
			Qty:	2	$14,165	$7,916	$0	$22,082
Assm:	11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA	$1,805.61	$1,767.07	$0.00	$3,572.68
			Qty:	1	$1,806	$1,767	$0	$3,573

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT		$102.32	$374.83	$0.00	$477.15
		Qty:	192		$19,646	$71,968	$0	$91,614
Assm: 12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA		$6,181.75	$3,465.03	$0.00	$9,646.78
		Qty:	2		$12,363	$6,930	$0	$19,294
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA		$42.39	$176.98	$0.00	$219.38
		Qty:	55		$2,332	$9,734	$0	$12,066
Assm: 12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF		$0.03	$0.07	$0.00	$0.10
		Qty:	570584		$16,889	$40,968	$0	$57,857
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA		$222.34	$177.74	$0.00	$400.08
		Qty:	25		$5,559	$4,444	$0	$10,002
Assm: 12010602	**Descr:** Time Clock System	**UOM:**	EA		$334.18	$866.03	$0.00	$1,200.22
		Qty:	9		$3,008	$7,794	$0	$10,802
Assm: 12020221	**Descr:** Battery Charger	**UOM:**	EA		$1,043.18	$619.45	$0.00	$1,662.63
		Qty:	34		$35,468	$21,061	$0	$56,529
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	30		$2,356	$4,241	$0	$6,598
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	97		$90,449	$38,969	$0	$129,418

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601

FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 46 **Name:** UnClass Soil Storage Warehouse 3

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	18778		$36,906	$69,184	$0	$106,090
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF		$1.68	$1.66	$0.00	$3.34
		Qty:	139792		$234,655	$231,565	$0	$466,220
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF		$3.37	$1.04	$0.00	$4.41
		Qty:	3901		$13,144	$4,039	$0	$17,184
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF		$35.54	$9.59	$0.00	$45.13
		Qty:	7231		$257,009	$69,340	$0	$326,349

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	11265		$3,235	$8,084	$0	$11,319
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF		$0.04	$0.05	$0.00	$0.08
		Qty:	568936		$20,994	$27,252	$0	$48,246
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF		$0.18	$0.32	$0.00	$0.49
		Qty:	568936		$101,441	$179,727	$0	$281,168
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	240		$11,687	$71,386	$0	$83,072
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	175		$46,751	$92,240	$0	$138,991
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	72		$12,625	$17,013	$0	$29,638
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	931		$187,080	$349,963	$0	$537,043
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	125		$37,089	$58,498	$0	$95,588
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	21		$2,462	$4,464	$0	$6,925

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 47 **Name:** Class Soil Storage Warehouse 1

Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	3875		$43,219	$42,235	$657	$86,111

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01010105	**Descr:**	1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF	$21.62	$17.86	$0.29	$39.77
				Qty:	2144	$46,360	$38,301	$627	$85,288
Assm:	01010112	**Descr:**	1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF	$20.15	$26.26	$0.21	$46.63
				Qty:	3875	$78,103	$101,778	$804	$180,685
Assm:	01010117	**Descr:**	16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF	$14.13	$21.63	$0.07	$35.83
				Qty:	4289	$60,596	$92,771	$316	$153,683
Assm:	01010201	**Descr:**	Spread Footing	**UOM:**	CY	$73.57	$45.75	$2.16	$121.48
				Qty:	1144	$84,160	$52,341	$2,471	$138,972
Assm:	01010212	**Descr:**	Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA	$87.34	$173.72	$1.69	$262.75
				Qty:	206	$17,993	$35,786	$349	$54,127
Assm:	01010241	**Descr:**	Spread Footing, Reinforcing Steel	**UOM:**	TON	$551.26	$645.22	$0.00	$1,196.47
				Qty:	12	$6,869	$8,039	$0	$14,908
Assm:	01029050	**Descr:**	Tie Beams (Seismic Modification)	**UOM:**	LF	$14.64	$18.55	$0.16	$33.35
				Qty:	11730	$171,700	$217,640	$1,897	$391,237
Assm:	01030104	**Descr:**	7" Standard Slab On Grade	**UOM:**	SF	$2.01	$2.62	$0.16	$4.79
				Qty:	478386	$961,556	$1,253,898	$76,685	$2,292,139
Assm:	01030115	**Descr:**	Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
				Qty:	30313	$117,978	$70,126	$2,401	$190,505
Assm:	02020204	**Descr:**	8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
				Qty:	197119	$1,180,861	$1,587,991	$18,608	$2,787,460
Assm:	02020313	**Descr:**	Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
				Qty:	531604	$2,636,968	$632,556	$180,533	$3,450,057

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 02020314	**Descr:** 3" Topping Slab	**UOM:**	SF		$0.77	$0.57	$0.04	$1.38
		Qty:	531604		$410,186	$300,835	$21,264	$732,285
Assm: 03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF		$11.02	$1.21	$0.17	$12.40
		Qty:	38635		$425,901	$46,702	$6,607	$479,209
Assm: 03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF		$0.23	$0.36	$0.03	$0.62
		Qty:	38635		$8,863	$13,982	$974	$23,818
Assm: 03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF		$0.51	$0.46	$0.00	$0.98
		Qty:	38635		$19,731	$17,958	$0	$37,688
Assm: 03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF		$0.19	$0.53	$0.00	$0.72
		Qty:	38635		$7,159	$20,596	$0	$27,755
Assm: 03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF		$29.84	$12.28	$0.00	$42.12
		Qty:	875		$26,109	$10,744	$0	$36,853
Assm: 03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA		$608.95	$579.12	$0.00	$1,188.07
		Qty:	3		$1,827	$1,737	$0	$3,564
Assm: 03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA		$1,287.09	$468.13	$0.00	$1,755.22
		Qty:	16		$20,593	$7,490	$0	$28,084
Assm: 03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA		$2,328.71	$734.80	$0.00	$3,063.51
		Qty:	3		$6,986	$2,204	$0	$9,191
Assm: 03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA		$3,536.29	$1,914.35	$99.90	$5,550.54
		Qty:	32		$113,161	$61,259	$3,197	$177,617
Assm: 04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF		$2.03	$1.26	$0.00	$3.29
		Qty:	531604		$1,079,688	$668,811	$0	$1,748,499

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
		Qty:	531604	$187,284	$128,170	$0	$315,454
Assm: 04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
		Qty:	5090	$120,306	$21,932	$0	$142,238
Assm: 04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
		Qty:	170	$271	$615	$0	$886
Assm: 08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
		Qty:	20	$4,075	$14,414	$0	$18,490
Assm: 08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
		Qty:	11	$1,000	$276	$0	$1,276
Assm: 08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
		Qty:	20	$1,573	$1,647	$0	$3,220
Assm: 08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
		Qty:	26	$4,684	$9,409	$0	$14,093
Assm: 08030202	**Descr:** PVC Vent Piping	**UOM:**	EA	$13.95	$47.57	$0.00	$61.51
		Qty:	26	$363	$1,237	$0	$1,599
Assm: 08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA	$409.55	$63.67	$0.00	$473.21
		Qty:	5	$2,048	$318	$0	$2,366
Assm: 08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA	$299.10	$172.74	$0.00	$471.84
		Qty:	2	$598	$345	$0	$944
Assm: 08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA	$400.59	$43.19	$0.00	$443.77
		Qty:	3	$1,202	$130	$0	$1,331

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA		$2,609.25	$939.01	$0.00	$3,548.25
		Qty:	2		$5,218	$1,878	$0	$7,097
Assm: 08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA		$362.85	$935.23	$0.00	$1,298.08
		Qty:	2		$726	$1,870	$0	$2,596
Assm: 08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA		$1,401.67	$222.85	$0.00	$1,624.52
		Qty:	1		$1,402	$223	$0	$1,625
Assm: 09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA		$10,823.28	$10,577.38	$148.33	$21,548.98
		Qty:	1		$10,823	$10,577	$148	$21,549
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA		$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	90		$271,451	$75,553	$153	$347,156
Assm: 09030210	**Descr:** 20 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA		$16,247.49	$7,178.80	$0.00	$23,426.29
		Qty:	1		$16,247	$7,179	$0	$23,426
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM		$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	0		$525	$784	$0	$1,308
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM		$418.17	$71.07	$0.00	$489.24
		Qty:	289		$120,850	$20,540	$0	$141,390
Assm: 09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM		$3,520.33	$790.73	$0.00	$4,311.06
		Qty:	8		$27,987	$6,286	$0	$34,273
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	0		$288	$411	$0	$698
Assm: 09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM		$3,706.36	$4,390.65	$0.00	$8,097.01
		Qty:	2		$6,968	$8,254	$0	$15,222

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM	$1,645.75	$4,920.50	$0.00	$6,566.24
		Qty:	1	$2,288	$6,839	$0	$9,127
Assm: 09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA	$122.32	$58.85	$0.00	$181.17
		Qty:	1	$122	$59	$0	$181
Assm: 09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA	$19,211.52	$29,488.79	$0.00	$48,700.31
		Qty:	1	$19,212	$29,489	$0	$48,700
Assm: 09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA	$0.00	$206.44	$0.00	$206.44
		Qty:	28	$0	$5,780	$0	$5,780
Assm: 09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA	$0.00	$309.73	$0.00	$309.73
		Qty:	46	$0	$14,248	$0	$14,248
Assm: 09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA	$0.00	$413.28	$0.00	$413.28
		Qty:	2	$0	$827	$0	$827
Assm: 09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA	$39.90	$68.74	$0.00	$108.64
		Qty:	1	$40	$69	$0	$109
Assm: 10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
		Qty:	4160	$199,807	$88,807	$913	$289,527
Assm: 10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
		Qty:	4160	$118,296	$338,702	$0	$456,998
Assm: 11010107	**Descr:** Ungrd 2000 Amp Main Transformer	**UOM:**	EA	$25,284.04	$4,296.94	$84.17	$29,665.15
		Qty:	1	$25,284	$4,297	$84	$29,665
Assm: 11010210	**Descr:** Ungrd 2000 Amp Secondary	**UOM:**	EA	$24,757.16	$15,830.50	$33.58	$40,621.24
		Qty:	1	$24,757	$15,831	$34	$40,621

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11010310	**Descr:** Ungrd 2000 Amp Main Switchboard	**UOM:**	EA	$102,879.41	$11,704.28	$0.00	$114,583.70
		Qty:	1	$102,879	$11,704	$0	$114,584
Assm: 11010402	**Descr:** (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	**UOM:**	EA	$1,367.54	$843.36	$0.00	$2,210.90
		Qty:	6	$8,205	$5,060	$0	$13,265
Assm: 11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
		Qty:	3	$6,450	$3,116	$0	$9,566
Assm: 11010404	**Descr:** (90-135 Amps 480V) 112.5 KVA Dry Type Transformer	**UOM:**	EA	$2,559.47	$933.62	$106.03	$3,599.13
		Qty:	2	$5,119	$1,867	$212	$7,198
Assm: 11010501	**Descr:** Panelbd 208V 100A 24 Cir Mlo W/Bkr	**UOM:**	EA	$882.61	$1,140.56	$0.00	$2,023.17
		Qty:	7	$6,178	$7,984	$0	$14,162
Assm: 11010506	**Descr:** Panelbd 208V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$1,554.41	$2,086.31	$0.00	$3,640.72
		Qty:	5	$7,772	$10,432	$0	$18,204
Assm: 11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
		Qty:	4	$7,089	$8,941	$0	$16,029
Assm: 11010536	**Descr:** Panelbd 480V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$2,296.82	$2,123.79	$0.00	$4,420.61
		Qty:	4	$9,187	$8,495	$0	$17,682
Assm: 11010537	**Descr:** Panelbd 480V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$2,950.05	$2,311.21	$0.00	$5,261.26
		Qty:	3	$8,850	$6,934	$0	$15,784
Assm: 11010541	**Descr:** Panelbd 480V 400A 42 Cir Mlo W/Bkr	**UOM:**	EA	$3,383.52	$2,561.48	$0.00	$5,944.99
		Qty:	2	$6,767	$5,123	$0	$11,890
Assm: 11010602	**Descr:** Enclosed Cir Bkr 600V 60A	**UOM:**	EA	$691.57	$1,188.21	$0.00	$1,879.78
		Qty:	5	$3,458	$5,941	$0	$9,399

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11010603	**Descr:** Enclosed Cir Bkr 600V 100A	**UOM:**	EA	$1,967.78	$2,379.44	$0.00	$4,347.21
		Qty:	3	$5,903	$7,138	$0	$13,042
Assm: 11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA	$1,805.61	$1,767.07	$0.00	$3,572.68
		Qty:	5	$9,028	$8,835	$0	$17,863
Assm: 11010609	**Descr:** Enclosed Cir Bkr 600V 30A	**UOM:**	EA	$260.10	$281.26	$0.00	$541.36
		Qty:	8	$2,081	$2,250	$0	$4,331
Assm: 12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT	$102.32	$374.83	$0.00	$477.15
		Qty:	162	$16,576	$60,723	$0	$77,299
Assm: 12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA	$6,181.75	$3,465.03	$0.00	$9,646.78
		Qty:	1	$6,182	$3,465	$0	$9,647
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA	$42.39	$176.98	$0.00	$219.38
		Qty:	46	$1,950	$8,141	$0	$10,091
Assm: 12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF	$0.03	$0.07	$0.00	$0.10
		Qty:	478388	$14,160	$34,348	$0	$48,509
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA	$222.34	$177.74	$0.00	$400.08
		Qty:	21	$4,669	$3,733	$0	$8,402
Assm: 12010602	**Descr:** Time Clock System	**UOM:**	EA	$334.18	$866.03	$0.00	$1,200.22
		Qty:	8	$2,673	$6,928	$0	$9,602
Assm: 12020221	**Descr:** Battery Charger	**UOM:**	EA	$1,043.18	$619.45	$0.00	$1,662.63
		Qty:	29	$30,252	$17,964	$0	$48,216
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA	$78.54	$141.38	$0.00	$219.92
		Qty:	25	$1,964	$3,534	$0	$5,498

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	81		$75,530	$32,541	$0	$108,071
FSA:	**ID:** CVN	**Name:**	COVERED EXTERIOR ENTRYWAY					
Facility Type:	Primary	**ID:** 47	**Name:**	Class Soil Storage Warehouse 1				
Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461
FSA:	**ID:** CVT	**Name:**	COVERED EXTERIOR LOADING DOCK W/LEVELER					
Facility Type:	Primary	**ID:** 47	**Name:**	Class Soil Storage Warehouse 1				
Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601

FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 47 **Name:** Class Soil Storage Warehouse 1

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 47 **Name:** Class Soil Storage Warehouse 1

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	15735		$30,926	$57,972	$0	$88,898

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF		$1.68	$1.66	$0.00	$3.34
		Qty:	117139		$196,630	$194,041	$0	$390,670
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF		$3.37	$1.04	$0.00	$4.41
		Qty:	3269		$11,015	$3,385	$0	$14,400
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF		$35.54	$9.59	$0.00	$45.13
		Qty:	6059		$215,353	$58,102	$0	$273,454
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	9439		$2,711	$6,773	$0	$9,484
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF		$0.04	$0.05	$0.00	$0.08
		Qty:	476740		$17,592	$22,836	$0	$40,428
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF		$0.18	$0.32	$0.00	$0.49
		Qty:	476740		$85,003	$150,602	$0	$235,605
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	201		$9,788	$59,785	$0	$69,573
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	147		$39,271	$77,482	$0	$116,753
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	60		$10,521	$14,178	$0	$24,698
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	780		$156,737	$293,202	$0	$449,939
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	105		$31,155	$49,138	$0	$80,294

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	17		$1,993	$3,613	$0	$5,606

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 48 **Name:** Class Soil Storage Warehouse 2

Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	3875		$43,219	$42,235	$657	$86,111
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	2144		$46,360	$38,301	$627	$85,288
Assm: 01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF		$20.15	$26.26	$0.21	$46.63
		Qty:	3875		$78,103	$101,778	$804	$180,685
Assm: 01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF		$14.13	$21.63	$0.07	$35.83
		Qty:	4289		$60,596	$92,771	$316	$153,683
Assm: 01010201	**Descr:** Spread Footing	**UOM:**	CY		$73.57	$45.75	$2.16	$121.48
		Qty:	1144		$84,160	$52,341	$2,471	$138,972
Assm: 01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA		$87.34	$173.72	$1.69	$262.75
		Qty:	206		$17,993	$35,786	$349	$54,127
Assm: 01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON		$551.26	$645.22	$0.00	$1,196.47
		Qty:	12		$6,869	$8,039	$0	$14,908
Assm: 01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF		$14.64	$18.55	$0.16	$33.35
		Qty:	11730		$171,700	$217,640	$1,897	$391,237
Assm: 01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF		$2.01	$2.62	$0.16	$4.79
		Qty:	478386		$961,556	$1,253,898	$76,685	$2,292,139

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	01030115	**Descr:** Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
			Qty:	30313	$117,978	$70,126	$2,401	$190,505
Assm:	02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
			Qty:	197119	$1,180,861	$1,587,991	$18,608	$2,787,460
Assm:	02020313	**Descr:** Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
			Qty:	531604	$2,636,968	$632,556	$180,533	$3,450,057
Assm:	02020314	**Descr:** 3" Topping Slab	**UOM:**	SF	$0.77	$0.57	$0.04	$1.38
			Qty:	531604	$410,186	$300,835	$21,264	$732,285
Assm:	03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF	$11.02	$1.21	$0.17	$12.40
			Qty:	38635	$425,901	$46,702	$6,607	$479,209
Assm:	03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
			Qty:	38635	$8,863	$13,982	$974	$23,818
Assm:	03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF	$0.51	$0.46	$0.00	$0.98
			Qty:	38635	$19,731	$17,958	$0	$37,688
Assm:	03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF	$0.19	$0.53	$0.00	$0.72
			Qty:	38635	$7,159	$20,596	$0	$27,755
Assm:	03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF	$29.84	$12.28	$0.00	$42.12
			Qty:	875	$26,109	$10,744	$0	$36,853
Assm:	03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA	$608.95	$579.12	$0.00	$1,188.07
			Qty:	3	$1,827	$1,737	$0	$3,564
Assm:	03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA	$1,287.09	$468.13	$0.00	$1,755.22
			Qty:	16	$20,593	$7,490	$0	$28,084

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
			Qty:	3	$6,986	$2,204	$0	$9,191
Assm:	03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA	$3,536.29	$1,914.35	$99.90	$5,550.54
			Qty:	32	$113,161	$61,259	$3,197	$177,617
Assm:	04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
			Qty:	531604	$1,079,688	$668,811	$0	$1,748,499
Assm:	04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
			Qty:	531604	$187,284	$128,170	$0	$315,454
Assm:	04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
			Qty:	5090	$120,306	$21,932	$0	$142,238
Assm:	04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
			Qty:	170	$271	$615	$0	$886
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	20	$4,075	$14,414	$0	$18,490
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	11	$1,000	$276	$0	$1,276
Assm:	08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
			Qty:	20	$1,573	$1,647	$0	$3,220
Assm:	08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
			Qty:	26	$4,684	$9,409	$0	$14,093
Assm:	08030202	**Descr:** PVC Vent Piping	**UOM:**	EA	$13.95	$47.57	$0.00	$61.51
			Qty:	26	$363	$1,237	$0	$1,599

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA		$409.55	$63.67	$0.00	$473.21
		Qty:	5		$2,048	$318	$0	$2,366
Assm: 08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA		$299.10	$172.74	$0.00	$471.84
		Qty:	2		$598	$345	$0	$944
Assm: 08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA		$400.59	$43.19	$0.00	$443.77
		Qty:	3		$1,202	$130	$0	$1,331
Assm: 08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA		$2,609.25	$939.01	$0.00	$3,548.25
		Qty:	2		$5,218	$1,878	$0	$7,097
Assm: 08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA		$362.85	$935.23	$0.00	$1,298.08
		Qty:	2		$726	$1,870	$0	$2,596
Assm: 08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA		$1,401.67	$222.85	$0.00	$1,624.52
		Qty:	1		$1,402	$223	$0	$1,625
Assm: 09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA		$10,823.28	$10,577.38	$148.33	$21,548.98
		Qty:	1		$10,823	$10,577	$148	$21,549
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA		$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	90		$271,451	$75,553	$153	$347,156
Assm: 09030210	**Descr:** 20 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA		$16,247.49	$7,178.80	$0.00	$23,426.29
		Qty:	1		$16,247	$7,179	$0	$23,426
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM		$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	0		$525	$784	$0	$1,308
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM		$418.17	$71.07	$0.00	$489.24
		Qty:	289		$120,850	$20,540	$0	$141,390

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM		$3,520.33	$790.73	$0.00	$4,311.06
		Qty:	8		$27,987	$6,286	$0	$34,273
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	0		$288	$411	$0	$698
Assm: 09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM		$3,706.36	$4,390.65	$0.00	$8,097.01
		Qty:	2		$6,968	$8,254	$0	$15,222
Assm: 09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM		$1,645.75	$4,920.50	$0.00	$6,566.24
		Qty:	1		$2,288	$6,839	$0	$9,127
Assm: 09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA		$122.32	$58.85	$0.00	$181.17
		Qty:	1		$122	$59	$0	$181
Assm: 09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA		$19,211.52	$29,488.79	$0.00	$48,700.31
		Qty:	1		$19,212	$29,489	$0	$48,700
Assm: 09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA		$0.00	$206.44	$0.00	$206.44
		Qty:	28		$0	$5,780	$0	$5,780
Assm: 09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA		$0.00	$309.73	$0.00	$309.73
		Qty:	46		$0	$14,248	$0	$14,248
Assm: 09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA		$0.00	$413.28	$0.00	$413.28
		Qty:	2		$0	$827	$0	$827
Assm: 09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA		$39.90	$68.74	$0.00	$108.64
		Qty:	1		$40	$69	$0	$109
Assm: 10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA		$48.03	$21.35	$0.22	$69.60
		Qty:	4160		$199,807	$88,807	$913	$289,527

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
		Qty:	4160	$118,296	$338,702	$0	$456,998
Assm: 11010107	**Descr:** Ungrd 2000 Amp Main Transformer	**UOM:**	EA	$25,284.04	$4,296.94	$84.17	$29,665.15
		Qty:	1	$25,284	$4,297	$84	$29,665
Assm: 11010210	**Descr:** Ungrd 2000 Amp Secondary	**UOM:**	EA	$24,757.16	$15,830.50	$33.58	$40,621.24
		Qty:	1	$24,757	$15,831	$34	$40,621
Assm: 11010310	**Descr:** Ungrd 2000 Amp Main Switchboard	**UOM:**	EA	$102,879.41	$11,704.28	$0.00	$114,583.70
		Qty:	1	$102,879	$11,704	$0	$114,584
Assm: 11010402	**Descr:** (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	**UOM:**	EA	$1,367.54	$843.36	$0.00	$2,210.90
		Qty:	6	$8,205	$5,060	$0	$13,265
Assm: 11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
		Qty:	3	$6,450	$3,116	$0	$9,566
Assm: 11010404	**Descr:** (90-135 Amps 480V) 112.5 KVA Dry Type Transformer	**UOM:**	EA	$2,559.47	$933.62	$106.03	$3,599.13
		Qty:	2	$5,119	$1,867	$212	$7,198
Assm: 11010501	**Descr:** Panelbd 208V 100A 24 Cir Mlo W/Bkr	**UOM:**	EA	$882.61	$1,140.56	$0.00	$2,023.17
		Qty:	7	$6,178	$7,984	$0	$14,162
Assm: 11010506	**Descr:** Panelbd 208V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$1,554.41	$2,086.31	$0.00	$3,640.72
		Qty:	5	$7,772	$10,432	$0	$18,204
Assm: 11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
		Qty:	4	$7,089	$8,941	$0	$16,029
Assm: 11010536	**Descr:** Panelbd 480V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$2,296.82	$2,123.79	$0.00	$4,420.61
		Qty:	4	$9,187	$8,495	$0	$17,682

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11010537	**Descr:** Panelbd 480V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA		$2,950.05	$2,311.21	$0.00	$5,261.26
		Qty:	3		$8,850	$6,934	$0	$15,784
Assm: 11010541	**Descr:** Panelbd 480V 400A 42 Cir Mlo W/Bkr	**UOM:**	EA		$3,383.52	$2,561.48	$0.00	$5,944.99
		Qty:	2		$6,767	$5,123	$0	$11,890
Assm: 11010602	**Descr:** Enclosed Cir Bkr 600V 60A	**UOM:**	EA		$691.57	$1,188.21	$0.00	$1,879.78
		Qty:	5		$3,458	$5,941	$0	$9,399
Assm: 11010603	**Descr:** Enclosed Cir Bkr 600V 100A	**UOM:**	EA		$1,967.78	$2,379.44	$0.00	$4,347.21
		Qty:	3		$5,903	$7,138	$0	$13,042
Assm: 11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA		$1,805.61	$1,767.07	$0.00	$3,572.68
		Qty:	5		$9,028	$8,835	$0	$17,863
Assm: 11010609	**Descr:** Enclosed Cir Bkr 600V 30A	**UOM:**	EA		$260.10	$281.26	$0.00	$541.36
		Qty:	8		$2,081	$2,250	$0	$4,331
Assm: 12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT		$102.32	$374.83	$0.00	$477.15
		Qty:	162		$16,576	$60,723	$0	$77,299
Assm: 12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA		$6,181.75	$3,465.03	$0.00	$9,646.78
		Qty:	1		$6,182	$3,465	$0	$9,647
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA		$42.39	$176.98	$0.00	$219.38
		Qty:	46		$1,950	$8,141	$0	$10,091
Assm: 12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF		$0.03	$0.07	$0.00	$0.10
		Qty:	478388		$14,160	$34,348	$0	$48,509
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA		$222.34	$177.74	$0.00	$400.08
		Qty:	21		$4,669	$3,733	$0	$8,402

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12010602	**Descr:** Time Clock System	**UOM:**	EA		$334.18	$866.03	$0.00	$1,200.22
		Qty:	8		$2,673	$6,928	$0	$9,602
Assm: 12020221	**Descr:** Battery Charger	**UOM:**	EA		$1,043.18	$619.45	$0.00	$1,662.63
		Qty:	29		$30,252	$17,964	$0	$48,216
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	25		$1,964	$3,534	$0	$5,498
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	81		$75,530	$32,541	$0	$108,071

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 48 **Name:** Class Soil Storage Warehouse 2

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 48 **Name:** Class Soil Storage Warehouse 2

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601

FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 48 **Name:** Class Soil Storage Warehouse 2

Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 48 **Name:** Class Soil Storage Warehouse 2

Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	15735		$30,926	$57,972	$0	$88,898
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF		$1.68	$1.66	$0.00	$3.34
		Qty:	117139		$196,630	$194,041	$0	$390,670
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF		$3.37	$1.04	$0.00	$4.41
		Qty:	3269		$11,015	$3,385	$0	$14,400
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF		$35.54	$9.59	$0.00	$45.13
		Qty:	6059		$215,353	$58,102	$0	$273,454
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	9439		$2,711	$6,773	$0	$9,484
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF		$0.04	$0.05	$0.00	$0.08
		Qty:	476740		$17,592	$22,836	$0	$40,428
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF		$0.18	$0.32	$0.00	$0.49
		Qty:	476740		$85,003	$150,602	$0	$235,605
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA		$48.69	$297.44	$0.00	$346.13
		Qty:	201		$9,788	$59,785	$0	$69,573
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	147		$39,271	$77,482	$0	$116,753

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	60		$10,521	$14,178	$0	$24,698
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	780		$156,737	$293,202	$0	$449,939
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	105		$31,155	$49,138	$0	$80,294
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	17		$1,993	$3,613	$0	$5,606

FSA: **ID:** **Name:** Building Shell

Facility Type: Primary **ID:** 49 **Name:** UnClass Waste Storage Warehouse

Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	4622		$51,550	$50,376	$784	$102,709
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	2558		$55,296	$45,684	$748	$101,728
Assm: 01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF		$20.15	$26.26	$0.21	$46.63
		Qty:	4622		$93,158	$121,396	$959	$215,512
Assm: 01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF		$14.13	$21.63	$0.07	$35.83
		Qty:	5116		$72,275	$110,653	$377	$183,305
Assm: 01010201	**Descr:** Spread Footing	**UOM:**	CY		$73.57	$45.75	$2.16	$121.48
		Qty:	1360		$100,050	$62,224	$2,937	$165,211
Assm: 01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA		$87.34	$173.72	$1.69	$262.75
		Qty:	245		$21,399	$42,561	$414	$64,374

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON	$551.26	$645.22	$0.00	$1,196.47
		Qty:	15	$8,164	$9,556	$0	$17,720
Assm: 01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF	$14.64	$18.55	$0.16	$33.35
		Qty:	13991	$204,791	$259,584	$2,262	$466,637
Assm: 01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF	$2.01	$2.62	$0.16	$4.79
		Qty:	570581	$1,146,868	$1,495,550	$91,464	$2,733,882
Assm: 01030115	**Descr:** Loading Dock Apron	**UOM:**	SF	$3.89	$2.31	$0.08	$6.28
		Qty:	36155	$140,715	$83,641	$2,863	$227,220
Assm: 02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF	$5.99	$8.06	$0.09	$14.14
		Qty:	235108	$1,408,438	$1,894,030	$22,194	$3,324,662
Assm: 02020313	**Descr:** Precast/Prestressed Roof Members	**UOM:**	SF	$4.96	$1.19	$0.34	$6.49
		Qty:	634056	$3,145,171	$754,463	$215,325	$4,114,960
Assm: 02020314	**Descr:** 3" Topping Slab	**UOM:**	SF	$0.77	$0.57	$0.04	$1.38
		Qty:	634056	$489,238	$358,812	$25,362	$873,412
Assm: 03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF	$11.02	$1.21	$0.17	$12.40
		Qty:	42194	$465,134	$51,004	$7,215	$523,353
Assm: 03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF	$0.23	$0.36	$0.03	$0.62
		Qty:	42194	$9,679	$15,270	$1,063	$26,013
Assm: 03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF	$0.51	$0.46	$0.00	$0.98
		Qty:	42194	$21,548	$19,612	$0	$41,160
Assm: 03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF	$0.19	$0.53	$0.00	$0.72
		Qty:	42194	$7,819	$22,494	$0	$30,312

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF	$29.84	$12.28	$0.00	$42.12
			Qty:	956	$28,526	$11,738	$0	$40,264
Assm:	03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA	$608.95	$579.12	$0.00	$1,188.07
			Qty:	3	$1,827	$1,737	$0	$3,564
Assm:	03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA	$1,287.09	$468.13	$0.00	$1,755.22
			Qty:	20	$25,742	$9,363	$0	$35,104
Assm:	03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
			Qty:	3	$6,986	$2,204	$0	$9,191
Assm:	03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA	$3,536.29	$1,914.35	$99.90	$5,550.54
			Qty:	38	$134,379	$72,745	$3,796	$210,921
Assm:	04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
			Qty:	634056	$1,287,768	$797,706	$0	$2,085,474
Assm:	04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
			Qty:	634056	$223,378	$152,871	$0	$376,249
Assm:	04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
			Qty:	6071	$143,492	$26,159	$0	$169,652
Assm:	04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
			Qty:	180	$287	$650	$0	$937
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	24	$4,890	$17,297	$0	$22,188
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	13	$1,182	$326	$0	$1,508

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA		$78.67	$82.34	$0.00	$161.01
		Qty:	24		$1,888	$1,976	$0	$3,864
Assm: 08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA		$180.14	$361.88	$0.00	$542.02
		Qty:	30		$5,404	$10,856	$0	$16,261
Assm: 08030202	**Descr:** PVC Vent Piping	**UOM:**	EA		$13.95	$47.57	$0.00	$61.51
		Qty:	30		$418	$1,427	$0	$1,845
Assm: 08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA		$409.55	$63.67	$0.00	$473.21
		Qty:	6		$2,457	$382	$0	$2,839
Assm: 08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA		$299.10	$172.74	$0.00	$471.84
		Qty:	2		$598	$345	$0	$944
Assm: 08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA		$400.59	$43.19	$0.00	$443.77
		Qty:	3		$1,202	$130	$0	$1,331
Assm: 08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA		$2,609.25	$939.01	$0.00	$3,548.25
		Qty:	2		$5,218	$1,878	$0	$7,097
Assm: 08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA		$362.85	$935.23	$0.00	$1,298.08
		Qty:	2		$726	$1,870	$0	$2,596
Assm: 08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA		$1,401.67	$222.85	$0.00	$1,624.52
		Qty:	2		$2,803	$446	$0	$3,249
Assm: 09010211	**Descr:** 18000 MBH Gas Supply	**UOM:**	EA		$10,823.28	$10,577.38	$148.33	$21,548.98
		Qty:	1		$10,823	$10,577	$148	$21,549
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA		$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	112		$337,806	$94,021	$190	$432,017

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09030209	**Descr:** 15 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA		$8,123.97	$3,365.04	$0.00	$11,489.01
		Qty:	2		$16,248	$6,730	$0	$22,978
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM		$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	1		$659	$984	$0	$1,642
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM		$418.17	$71.07	$0.00	$489.24
		Qty:	359		$150,205	$25,530	$0	$175,735
Assm: 09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM		$3,520.33	$790.73	$0.00	$4,311.06
		Qty:	10		$34,781	$7,812	$0	$42,593
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	0		$356	$508	$0	$865
Assm: 09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM		$3,706.36	$4,390.65	$0.00	$8,097.01
		Qty:	2		$8,636	$10,230	$0	$18,866
Assm: 09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM		$1,645.75	$4,920.50	$0.00	$6,566.24
		Qty:	2		$2,847	$8,512	$0	$11,360
Assm: 09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA		$122.32	$58.85	$0.00	$181.17
		Qty:	2		$245	$118	$0	$362
Assm: 09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA		$19,211.52	$29,488.79	$0.00	$48,700.31
		Qty:	1		$19,212	$29,489	$0	$48,700
Assm: 09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA		$0.00	$206.44	$0.00	$206.44
		Qty:	35		$0	$7,225	$0	$7,225
Assm: 09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA		$0.00	$309.73	$0.00	$309.73
		Qty:	58		$0	$17,964	$0	$17,964

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA	$0.00	$413.28	$0.00	$413.28
			Qty:	3	$0	$1,240	$0	$1,240
Assm:	09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA	$39.90	$68.74	$0.00	$108.64
			Qty:	1	$40	$69	$0	$109
Assm:	10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
			Qty:	4962	$238,327	$105,928	$1,089	$345,344
Assm:	10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
			Qty:	4962	$141,102	$404,000	$0	$545,102
Assm:	11010108	**Descr:** Electrical 2500A Main Transformer	**UOM:**	EA	$29,512.44	$4,886.87	$96.72	$34,496.03
			Qty:	1	$29,512	$4,887	$97	$34,496
Assm:	11010211	**Descr:** Electrical 2500A Secondary	**UOM:**	EA	$37,780.63	$23,682.69	$47.01	$61,510.33
			Qty:	1	$37,781	$23,683	$47	$61,510
Assm:	11010311	**Descr:** Electrical 2500A Main Switchboard	**UOM:**	EA	$91,215.75	$9,632.58	$0.00	$100,848.33
			Qty:	1	$91,216	$9,633	$0	$100,848
Assm:	11010403	**Descr:** (45-90 Amps 480V) 75 KVA Dry Type Transformer	**UOM:**	EA	$2,149.90	$1,038.62	$0.00	$3,188.52
			Qty:	9	$19,349	$9,348	$0	$28,697
Assm:	11010502	**Descr:** Panelbd 208V 100A 30 Cir Mlo W/Bkr	**UOM:**	EA	$1,153.60	$899.36	$0.00	$2,052.95
			Qty:	8	$9,229	$7,195	$0	$16,424
Assm:	11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
			Qty:	8	$14,177	$17,881	$0	$32,058
Assm:	11010516	**Descr:** Panelbd 208V 225A MCB 42 Cir W/Bkr	**UOM:**	EA	$2,088.56	$2,391.53	$0.00	$4,480.09
			Qty:	1	$2,089	$2,392	$0	$4,480

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11010561	**Descr:** Panelbd 480V 600A MCB 42 Cir W/Bkr	**UOM:**	EA		$7,082.74	$3,958.17	$0.00	$11,040.92
		Qty:	2		$14,165	$7,916	$0	$22,082
Assm: 11010604	**Descr:** Enclosed Cir Bkr 600V 225A	**UOM:**	EA		$1,805.61	$1,767.07	$0.00	$3,572.68
		Qty:	1		$1,806	$1,767	$0	$3,573
Assm: 12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT		$102.32	$374.83	$0.00	$477.15
		Qty:	192		$19,646	$71,968	$0	$91,614
Assm: 12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA		$6,181.75	$3,465.03	$0.00	$9,646.78
		Qty:	2		$12,363	$6,930	$0	$19,294
Assm: 12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA		$42.39	$176.98	$0.00	$219.38
		Qty:	55		$2,332	$9,734	$0	$12,066
Assm: 12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF		$0.03	$0.07	$0.00	$0.10
		Qty:	570584		$16,889	$40,968	$0	$57,857
Assm: 12010601	**Descr:** Clock System	**UOM:**	EA		$222.34	$177.74	$0.00	$400.08
		Qty:	25		$5,559	$4,444	$0	$10,002
Assm: 12010602	**Descr:** Time Clock System	**UOM:**	EA		$334.18	$866.03	$0.00	$1,200.22
		Qty:	9		$3,008	$7,794	$0	$10,802
Assm: 12020221	**Descr:** Battery Charger	**UOM:**	EA		$1,043.18	$619.45	$0.00	$1,662.63
		Qty:	34		$35,468	$21,061	$0	$56,529
Assm: 12020401	**Descr:** Lightning Protection System	**UOM:**	EA		$78.54	$141.38	$0.00	$219.92
		Qty:	30		$2,356	$4,241	$0	$6,598
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	97		$90,449	$38,969	$0	$129,418

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

					Mat $	Lab $	Eqp $	Ttl $
Facility Type: Primary	**ID:** 49	**Name:** UnClass Waste Storage Warehouse						
Assm: 06039002	**Descr:** Exterior Canopy W/Framing		**UOM:**	SF	$5.76	$6.52	$0.00	$12.29
			Qty:	108	$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount		**UOM:**	EA	$175.34	$236.30	$0.00	$411.64
			Qty:	1	$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture		**UOM:**	EA	$215.09	$246.25	$0.00	$461.34
			Qty:	1	$215	$246	$0	$461
FSA: **ID:** CVT	**Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER							
Facility Type: Primary	**ID:** 49	**Name:** UnClass Waste Storage Warehouse						
Assm: 06039002	**Descr:** Exterior Canopy W/Framing		**UOM:**	SF	$5.76	$6.52	$0.00	$12.29
			Qty:	1061	$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP		**UOM:**	EA	$267.15	$527.09	$0.00	$794.24
			Qty:	1	$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture		**UOM:**	EA	$200.94	$375.90	$0.00	$576.85
			Qty:	4	$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights		**UOM:**	EA	$123.71	$227.24	$0.00	$350.95
			Qty:	2	$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs		**UOM:**	DOCK	$4,942.83	$1,428.71	$40.13	$6,411.67
			Qty:	1	$4,943	$1,429	$40	$6,412
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle		**UOM:**	EA	$483.17	$1,116.94	$1.04	$1,601.14
			Qty:	1	$483	$1,117	$1	$1,601
FSA: **ID:** MEL	**Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT							

					Mat $	Lab $	Eqp $	Ttl $
Facility Type: Primary	**ID:** 49	**Name:** UnClass Waste Storage Warehouse						
Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199
FSA:	**ID:** SRM	**Name:** STOCKROOM						
Facility Type: Primary	**ID:** 49	**Name:** UnClass Waste Storage Warehouse						
Assm: 03010310	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$5.93	$0.59	$0.00	$6.52
		Qty:	51495		$305,365	$30,619	$0	$335,984
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF		$1.97	$3.68	$0.00	$5.65
		Qty:	18778		$36,906	$69,184	$0	$106,090
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF		$1.68	$1.66	$0.00	$3.34
		Qty:	139792		$234,655	$231,565	$0	$466,220

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF	$3.37	$1.04	$0.00	$4.41
		Qty:	3901	$13,144	$4,039	$0	$17,184
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF	$35.54	$9.59	$0.00	$45.13
		Qty:	7231	$257,009	$69,340	$0	$326,349
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF	$0.29	$0.72	$0.00	$1.00
		Qty:	11265	$3,235	$8,084	$0	$11,319
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF	$0.04	$0.05	$0.00	$0.08
		Qty:	568936	$20,994	$27,252	$0	$48,246
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF	$0.18	$0.32	$0.00	$0.49
		Qty:	568936	$101,441	$179,727	$0	$281,168
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA	$48.69	$297.44	$0.00	$346.13
		Qty:	240	$11,687	$71,386	$0	$83,072
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA	$267.15	$527.09	$0.00	$794.24
		Qty:	175	$46,751	$92,240	$0	$138,991
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA	$175.34	$236.30	$0.00	$411.64
		Qty:	72	$12,625	$17,013	$0	$29,638
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA	$200.94	$375.90	$0.00	$576.85
		Qty:	931	$187,080	$349,963	$0	$537,043
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA	$296.72	$467.99	$0.00	$764.70
		Qty:	125	$37,089	$58,498	$0	$95,588
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA	$117.22	$212.56	$0.00	$329.78
		Qty:	21	$2,462	$4,464	$0	$6,925

FSA: **ID:** **Name:** Building Shell

Project Summary Report

Date 07/26/2002

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

					Mat $	Lab $	Eqp $	Ttl $
Assm: 01010103	**Descr:** 1'0" X 3'0" Strip Footing 3000 PSI	**UOM:**	LF		$11.15	$10.90	$0.17	$22.22
		Qty:	843		$9,400	$9,186	$143	$18,729
Assm: 01010105	**Descr:** 1'6" X 4'0" Strip Footing 3000 PSI	**UOM:**	LF		$21.62	$17.86	$0.29	$39.77
		Qty:	466		$10,083	$8,330	$136	$18,550
Assm: 01010112	**Descr:** 1'3" X 2'6" Grade Beam 4000 PSI	**UOM:**	LF		$20.15	$26.26	$0.21	$46.63
		Qty:	843		$16,987	$22,137	$175	$39,299
Assm: 01010117	**Descr:** 16" Masonry Wall Foundation - 24" Deep Wall	**UOM:**	LF		$14.13	$21.63	$0.07	$35.83
		Qty:	933		$13,179	$20,178	$69	$33,426
Assm: 01010201	**Descr:** Spread Footing	**UOM:**	CY		$73.57	$45.75	$2.16	$121.48
		Qty:	100		$7,357	$4,575	$216	$12,148
Assm: 01010212	**Descr:** Column Piers 2'0" X 2'0" X 3'0" High	**UOM:**	EA		$87.34	$173.72	$1.69	$262.75
		Qty:	74		$6,463	$12,855	$125	$19,444
Assm: 01010241	**Descr:** Spread Footing, Reinforcing Steel	**UOM:**	TON		$551.26	$645.22	$0.00	$1,196.47
		Qty:	3		$1,378	$1,613	$0	$2,991
Assm: 01010277	**Descr:** Spread Footing Column Bolts	**UOM:**	EA		$1.22	$4.37	$0.00	$5.59
		Qty:	408		$497	$1,782	$0	$2,279
Assm: 01029050	**Descr:** Tie Beams (Seismic Modification)	**UOM:**	LF		$14.64	$18.55	$0.16	$33.35
		Qty:	2551		$37,343	$47,334	$413	$85,090
Assm: 01030104	**Descr:** 7" Standard Slab On Grade	**UOM:**	SF		$2.01	$2.62	$0.16	$4.79
		Qty:	104043		$209,126	$272,707	$16,678	$498,512
Assm: 01030115	**Descr:** Loading Dock Apron	**UOM:**	SF		$3.89	$2.31	$0.08	$6.28
		Qty:	6593		$25,660	$15,252	$522	$41,434

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 02020112	**Descr:** Lrg Span, Structural Stl, Hv Ld, Roof Frame	**UOM:**	SF		$4.48	$1.48	$0.34	$6.30
		Qty:	115618		$518,061	$170,976	$39,449	$728,486
Assm: 02020137	**Descr:** Structural Steel, Hv Load, Columns	**UOM:**	SF		$0.74	$0.24	$0.06	$1.04
		Qty:	83917		$62,132	$20,509	$4,733	$87,374
Assm: 02020204	**Descr:** 8 X 12 X 16 Load Brg Reinforced Conc. Masonry Unit Wall	**UOM:**	SF		$5.99	$8.06	$0.09	$14.14
		Qty:	42871		$256,823	$345,369	$4,047	$606,239
Assm: 02020315	**Descr:** Concrete Roof Deck	**UOM:**	SF		$2.56	$2.79	$0.05	$5.40
		Qty:	115618		$296,202	$322,736	$5,619	$624,557
Assm: 02020320	**Descr:** Concrete Deck Reinforcing Steel	**UOM:**	TON		$551.26	$645.22	$0.00	$1,196.47
		Qty:	335		$184,832	$216,334	$0	$401,166
Assm: 03010103	**Descr:** Tilt-Up Wall Panel 5-1/2" Thick	**UOM:**	SF		$11.02	$1.21	$0.17	$12.40
		Qty:	18017		$198,614	$21,779	$3,081	$223,474
Assm: 03010147	**Descr:** Additional Vertical Reinforcement And Grouting; Seismic	**UOM:**	SF		$0.23	$0.36	$0.03	$0.62
		Qty:	18017		$4,133	$6,520	$454	$11,107
Assm: 03010205	**Descr:** Loose Fill 8" Block Insulation	**UOM:**	SF		$0.51	$0.46	$0.00	$0.98
		Qty:	18017		$9,201	$8,374	$0	$17,576
Assm: 03010312	**Descr:** Paint CMU/Concrete	**UOM:**	SF		$0.19	$0.53	$0.00	$0.72
		Qty:	18017		$3,339	$9,605	$0	$12,943
Assm: 03010501	**Descr:** Fixed Blade Exterior Louver With Baked Enamel Finish	**UOM:**	SF		$29.84	$12.28	$0.00	$42.12
		Qty:	408		$12,174	$5,010	$0	$17,184
Assm: 03030101	**Descr:** 3'0" X 7'0" Aluminum And Glass Door	**UOM:**	EA		$608.95	$579.12	$0.00	$1,188.07
		Qty:	1		$609	$579	$0	$1,188

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	03030202	**Descr:** 3'0" X 7'0" Hollow Metal Door W/Frame	**UOM:**	EA	$1,287.09	$468.13	$0.00	$1,755.22
			Qty:	3	$3,861	$1,404	$0	$5,266
Assm:	03030204	**Descr:** 6'0" X 7'0" Pair Hollow Metal Doors W/Frame	**UOM:**	EA	$2,328.71	$734.80	$0.00	$3,063.51
			Qty:	1	$2,329	$735	$0	$3,064
Assm:	03040103	**Descr:** 20'0" X 14'0" Metal Overhead Door	**UOM:**	EA	$3,536.29	$1,914.35	$99.90	$5,550.54
			Qty:	7	$24,754	$13,400	$699	$38,854
Assm:	04010108	**Descr:** Standing Seam Metal Roof	**UOM:**	SF	$2.03	$1.26	$0.00	$3.29
			Qty:	115618	$234,820	$145,459	$0	$380,279
Assm:	04010302	**Descr:** Rigid Insulation 1-1/2" Thick	**UOM:**	SF	$0.35	$0.24	$0.00	$0.59
			Qty:	115618	$40,732	$27,875	$0	$68,608
Assm:	04010503	**Descr:** Skylights, Plastic Insulated Domes	**UOM:**	SF	$23.64	$4.31	$0.00	$27.94
			Qty:	1107	$26,165	$4,770	$0	$30,935
Assm:	04010601	**Descr:** 5" Box Gutters With Downspouts	**UOM:**	LF	$1.59	$3.61	$0.00	$5.20
			Qty:	114	$181	$410	$0	$591
Assm:	08020101	**Descr:** Copper Pipe & Fittings	**UOM:**	EA	$203.76	$720.72	$0.00	$924.48
			Qty:	4	$815	$2,883	$0	$3,698
Assm:	08020201	**Descr:** Valves & Hydrants	**UOM:**	EA	$90.94	$25.08	$0.00	$116.03
			Qty:	2	$182	$50	$0	$232
Assm:	08020401	**Descr:** Fiberglass 1-1/2" Pipe Insulation With Vapor Barrier	**UOM:**	EA	$78.67	$82.34	$0.00	$161.01
			Qty:	4	$315	$329	$0	$644
Assm:	08030101	**Descr:** Waste Pipe & Fittings	**UOM:**	EA	$180.14	$361.88	$0.00	$542.02
			Qty:	6	$1,081	$2,171	$0	$3,252

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 08030202	**Descr:** PVC Vent Piping	**UOM:**	EA		$13.95	$47.57	$0.00	$61.51
		Qty:	6		$84	$285	$0	$369
Assm: 08030305	**Descr:** Heavy Duty Cast Iron Floor Drains	**UOM:**	EA		$409.55	$63.67	$0.00	$473.21
		Qty:	1		$410	$64	$0	$473
Assm: 08050102	**Descr:** Domestic Water Supply Equip - 50 Gal. Elec, Hot Water	**UOM:**	EA		$299.10	$172.74	$0.00	$471.84
		Qty:	1		$299	$173	$0	$472
Assm: 08050108	**Descr:** Dom Water Sup Equip, 1 1/2" Water Meter Brnze Disc Type	**UOM:**	EA		$400.59	$43.19	$0.00	$443.77
		Qty:	1		$401	$43	$0	$444
Assm: 08060201	**Descr:** Acid Waste System For Battery & Acid Rooms	**UOM:**	EA		$2,609.25	$939.01	$0.00	$3,548.25
		Qty:	1		$2,609	$939	$0	$3,548
Assm: 08060204	**Descr:** Special Plumbing For Battery And Acid Rooms	**UOM:**	EA		$362.85	$935.23	$0.00	$1,298.08
		Qty:	1		$363	$935	$0	$1,298
Assm: 08060304	**Descr:** Interceptors For Battery & Acid Rooms	**UOM:**	EA		$1,401.67	$222.85	$0.00	$1,624.52
		Qty:	1		$1,402	$223	$0	$1,625
Assm: 09010208	**Descr:** 1998 MBH Gas Supply	**UOM:**	EA		$3,367.39	$2,292.17	$148.33	$5,807.88
		Qty:	1		$3,367	$2,292	$148	$5,808
Assm: 09020403	**Descr:** Gas Fired Unit Heater, 300 MBH, Spark Ignition	**UOM:**	EA		$3,016.12	$839.47	$1.70	$3,857.29
		Qty:	15		$45,242	$12,592	$25	$57,859
Assm: 09030203	**Descr:** 4 Ton Condensing Unit With Refrigerant Piping	**UOM:**	EA		$2,738.13	$2,106.03	$0.00	$4,844.16
		Qty:	1		$2,738	$2,106	$0	$4,844
Assm: 09040703	**Descr:** Toilet Exhaust .2 MCFM	**UOM:**	MCFM		$1,116.15	$1,667.16	$0.00	$2,783.31
		Qty:	0		$89	$133	$0	$223

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 09040727	**Descr:** Ventilation System, 64.8 MCFM	**UOM:**	MCFM		$418.17	$71.07	$0.00	$489.24
		Qty:	48		$20,273	$3,446	$0	$23,718
Assm: 09040765	**Descr:** 14.7 MCFM Exhaust Sys For Batry Storage & Charging Area	**UOM:**	MCFM		$3,520.33	$790.73	$0.00	$4,311.06
		Qty:	1		$4,682	$1,052	$0	$5,734
Assm: 09049907	**Descr:** Air Dist Sys .3 - .8 MCFM Vav With Hot Water Heating	**UOM:**	MCFM		$1,370.16	$1,955.73	$0.00	$3,325.89
		Qty:	0		$41	$59	$0	$100
Assm: 09049921	**Descr:** 2.0 MCFM Air Dist Sys With Heat Pump	**UOM:**	MCFM		$3,706.36	$4,390.65	$0.00	$8,097.01
		Qty:	0		$1,149	$1,361	$0	$2,510
Assm: 09049923	**Descr:** 2.7 MCFM AIR DIST SYS W/2 HEAT PUMP AHU'S	**UOM:**	MCFM		$1,645.75	$4,920.50	$0.00	$6,566.24
		Qty:	0		$379	$1,132	$0	$1,510
Assm: 09060107	**Descr:** Control System For Cooling Unit	**UOM:**	EA		$122.32	$58.85	$0.00	$181.17
		Qty:	1		$122	$59	$0	$181
Assm: 09060182	**Descr:** Controls For Ventilating System	**UOM:**	EA		$19,211.52	$29,488.79	$0.00	$48,700.31
		Qty:	1		$19,212	$29,489	$0	$48,700
Assm: 09070201	**Descr:** Test & Balance, Cent Fan/Utility Set	**UOM:**	EA		$0.00	$206.44	$0.00	$206.44
		Qty:	5		$0	$1,032	$0	$1,032
Assm: 09070202	**Descr:** Test & Balance H&V Unit/In Line Fan	**UOM:**	EA		$0.00	$309.73	$0.00	$309.73
		Qty:	8		$0	$2,478	$0	$2,478
Assm: 09070206	**Descr:** Test & Balance Air Handler, Low Pressure	**UOM:**	EA		$0.00	$413.28	$0.00	$413.28
		Qty:	1		$0	$413	$0	$413
Assm: 09070211	**Descr:** Test & Balance Vav Box	**UOM:**	EA		$39.90	$68.74	$0.00	$108.64
		Qty:	1		$40	$69	$0	$109

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	10010104	**Descr:** Fire Prot Water Supply, (40'H) Ord Haz Fac	**UOM:**	EA	$48.03	$21.35	$0.22	$69.60
			Qty:	905	$43,468	$19,320	$199	$62,986
Assm:	10020101	**Descr:** Exposed Sprinkler System For A Lg Facility - Ord. Haz.	**UOM:**	EA	$28.44	$81.42	$0.00	$109.86
			Qty:	905	$25,735	$73,684	$0	$99,419
Assm:	11010102	**Descr:** Ungrd 400 Amp Main Transformer	**UOM:**	EA	$12,302.04	$2,719.04	$54.41	$15,075.49
			Qty:	1	$12,302	$2,719	$54	$15,075
Assm:	11010205	**Descr:** Ungrd 400 Amp Secondary	**UOM:**	EA	$3,411.78	$2,187.03	$10.07	$5,608.88
			Qty:	1	$3,412	$2,187	$10	$5,609
Assm:	11010305	**Descr:** Ungrd 400 Amp Main Switchboard	**UOM:**	EA	$22,577.91	$3,342.16	$0.00	$25,920.07
			Qty:	1	$22,578	$3,342	$0	$25,920
Assm:	11010401	**Descr:** (10-30 Amps 480V) 25 KVA Dry Type Transformer	**UOM:**	EA	$1,291.40	$674.69	$0.00	$1,966.09
			Qty:	2	$2,583	$1,349	$0	$3,932
Assm:	11010402	**Descr:** (30-45 Amps 480V) 37.5 KVA Dry Type Transformer	**UOM:**	EA	$1,367.54	$843.36	$0.00	$2,210.90
			Qty:	2	$2,735	$1,687	$0	$4,422
Assm:	11010501	**Descr:** Panelbd 208V 100A 24 Cir Mlo W/Bkr	**UOM:**	EA	$882.61	$1,140.56	$0.00	$2,023.17
			Qty:	2	$1,765	$2,281	$0	$4,046
Assm:	11010506	**Descr:** Panelbd 208V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$1,554.41	$2,086.31	$0.00	$3,640.72
			Qty:	1	$1,554	$2,086	$0	$3,641
Assm:	11010507	**Descr:** Panelbd 208V 225A 42 Cir Mlo W/Bkr	**UOM:**	EA	$1,772.16	$2,235.15	$0.00	$4,007.30
			Qty:	1	$1,772	$2,235	$0	$4,007
Assm:	11010536	**Descr:** Panelbd 480V 225A 36 Cir Mlo W/Bkr	**UOM:**	EA	$2,296.82	$2,123.79	$0.00	$4,420.61
			Qty:	1	$2,297	$2,124	$0	$4,421

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm:	11010602	**Descr:** Enclosed Cir Bkr 600V 60A	**UOM:**	EA	$691.57	$1,188.21	$0.00	$1,879.78
			Qty:	1	$692	$1,188	$0	$1,880
Assm:	11010609	**Descr:** Enclosed Cir Bkr 600V 30A	**UOM:**	EA	$260.10	$281.26	$0.00	$541.36
			Qty:	2	$520	$563	$0	$1,083
Assm:	11010611	**Descr:** Enclosed Cir Bkr 600V 100A	**UOM:**	EA	$539.76	$481.77	$0.00	$1,021.53
			Qty:	2	$1,080	$964	$0	$2,043
Assm:	12010102	**Descr:** Fire Alarm System - Rate Of Rise Heat Detectors	**UOM:**	OUT	$102.32	$374.83	$0.00	$477.15
			Qty:	35	$3,581	$13,119	$0	$16,700
Assm:	12010119	**Descr:** 16 Zone FACP, Annun And Transmitter	**UOM:**	EA	$6,181.75	$3,465.03	$0.00	$9,646.78
			Qty:	1	$6,182	$3,465	$0	$9,647
Assm:	12010301	**Descr:** Telephone System, 2 Pair	**UOM:**	EA	$42.39	$176.98	$0.00	$219.38
			Qty:	10	$424	$1,770	$0	$2,194
Assm:	12010402	**Descr:** Public Address For Large Warehouse	**UOM:**	SF	$0.03	$0.07	$0.00	$0.10
			Qty:	104044	$3,080	$7,470	$0	$10,550
Assm:	12010601	**Descr:** Clock System	**UOM:**	EA	$222.34	$177.74	$0.00	$400.08
			Qty:	4	$889	$711	$0	$1,600
Assm:	12010602	**Descr:** Time Clock System	**UOM:**	EA	$334.18	$866.03	$0.00	$1,200.22
			Qty:	2	$668	$1,732	$0	$2,400
Assm:	12020221	**Descr:** Battery Charger	**UOM:**	EA	$1,043.18	$619.45	$0.00	$1,662.63
			Qty:	6	$6,259	$3,717	$0	$9,976
Assm:	12020401	**Descr:** Lightning Protection System	**UOM:**	EA	$78.54	$141.38	$0.00	$219.92
			Qty:	5	$393	$707	$0	$1,100

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 12020601	**Descr:** Energy Management Control System	**UOM:**	PTS		$932.47	$401.74	$0.00	$1,334.21
		Qty:	18		$16,784	$7,231	$0	$24,016

FSA: **ID:** CVN **Name:** COVERED EXTERIOR ENTRYWAY

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	108		$623	$705	$0	$1,327
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA		$175.34	$236.30	$0.00	$411.64
		Qty:	1		$175	$236	$0	$412
Assm: 11020235	**Descr:** 150 Watt Hps Recessed Fixture	**UOM:**	EA		$215.09	$246.25	$0.00	$461.34
		Qty:	1		$215	$246	$0	$461

FSA: **ID:** CVT **Name:** COVERED EXTERIOR LOADING DOCK W/LEVELER

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

Assm: 06039002	**Descr:** Exterior Canopy W/Framing	**UOM:**	SF		$5.76	$6.52	$0.00	$12.29
		Qty:	1061		$6,117	$6,923	$0	$13,039
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA		$267.15	$527.09	$0.00	$794.24
		Qty:	1		$267	$527	$0	$794
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA		$200.94	$375.90	$0.00	$576.85
		Qty:	4		$804	$1,504	$0	$2,307
Assm: 11020280	**Descr:** Dock Lights	**UOM:**	EA		$123.71	$227.24	$0.00	$350.95
		Qty:	2		$247	$454	$0	$702
Assm: 13010602	**Descr:** 6'0" X 8'0" Long 10 Ton Capacity With Stairs	**UOM:**	DOCK		$4,942.83	$1,428.71	$40.13	$6,411.67
		Qty:	1		$4,943	$1,429	$40	$6,412

					Mat $	Lab $	Eqp $	Ttl $
Assm: 13010606	**Descr:** 24" Deep Dock Leveler Pit Wall W/Stl Angle	**UOM:**	EA		$483.17	$1,116.94	$1.04	$1,601.14
		Qty:	1		$483	$1,117	$1	$1,601

FSA: **ID:** MEL **Name:** MECHANICAL, ELECTRICAL, & BUILDING SUPPORT

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010114	**Descr:** Non-Load Bearing 8 X 8 X 16 Concrete Block	**UOM:**	SF		$2.34	$5.03	$0.00	$7.37
		Qty:	337		$788	$1,695	$0	$2,483
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF		$0.29	$0.72	$0.00	$1.00
		Qty:	668		$192	$479	$0	$671
Assm: 06030301	**Descr:** 5/8" Gypsum Wallboard Ceiling, 1 Layer, Fire Rated	**UOM:**	SF		$0.32	$0.59	$0.00	$0.92
		Qty:	56		$18	$33	$0	$51
Assm: 06030704	**Descr:** Suspension System For Gypsum Board Ceiling	**UOM:**	SF		$0.75	$4.08	$0.00	$4.83
		Qty:	56		$42	$228	$0	$270
Assm: 11020102	**Descr:** 120 Volt, 20 Amp Duplex Receptacle - Masonry Partition	**UOM:**	EA		$31.01	$170.59	$0.00	$201.60
		Qty:	2		$62	$341	$0	$403
Assm: 11020156	**Descr:** 120V 20A Single Pole Switch	**UOM:**	EA		$25.89	$148.76	$0.00	$174.65
		Qty:	1		$26	$149	$0	$175
Assm: 11020276	**Descr:** Porcelain Lamp Holder	**UOM:**	EA		$21.47	$177.99	$0.00	$199.46
		Qty:	1		$21	$178	$0	$199

FSA: **ID:** SRM **Name:** STOCKROOM

Facility Type: Primary **ID:** 50 **Name:** Classified Waste Storage Warehouse

					Mat $	Lab $	Eqp $	Ttl $
Assm: 03010310	**Descr:** 5/8" Gypsum Board/Installed/Taped & Finished	**UOM:**	SF		$5.93	$0.59	$0.00	$6.52
		Qty:	21837		$129,493	$12,984	$0	$142,478

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 05010112	**Descr:** Non-Load Brg Partition Of 8 X 6 X 16 Concrete	**UOM:**	SF	$1.97	$3.68	$0.00	$5.65
		Qty:	3380	$6,643	$12,453	$0	$19,096
Assm: 05010126	**Descr:** Ribbed Metal Panel (22 Ga) With 3-1/2 Batt Insulation	**UOM:**	SF	$1.68	$1.66	$0.00	$3.34
		Qty:	25159	$42,232	$41,676	$0	$83,908
Assm: 05010127	**Descr:** Wire Mesh Partitions, 4' Wide X 20' High	**UOM:**	SF	$3.37	$1.04	$0.00	$4.41
		Qty:	702	$2,365	$727	$0	$3,092
Assm: 05039014	**Descr:** Sliding Metal Clad Door (With Motor)	**UOM:**	SF	$35.54	$9.59	$0.00	$45.13
		Qty:	1301	$46,241	$12,476	$0	$58,717
Assm: 06010502	**Descr:** Paint To Concrete Block Using Brushes, Two Coats	**UOM:**	SF	$0.29	$0.72	$0.00	$1.00
		Qty:	2027	$582	$1,455	$0	$2,037
Assm: 06029001	**Descr:** Concrete Floor Sealer	**UOM:**	SF	$0.04	$0.05	$0.00	$0.08
		Qty:	102396	$3,778	$4,905	$0	$8,683
Assm: 06029003	**Descr:** Floor Hardener, Non-Metallic Light Service	**UOM:**	SF	$0.18	$0.32	$0.00	$0.49
		Qty:	102396	$18,257	$32,347	$0	$50,604
Assm: 11020103	**Descr:** Duplex Receptacle Long Run	**UOM:**	EA	$48.69	$297.44	$0.00	$346.13
		Qty:	43	$2,094	$12,790	$0	$14,884
Assm: 11020136	**Descr:** Equipment Connections For Up To 5 HP	**UOM:**	EA	$267.15	$527.09	$0.00	$794.24
		Qty:	32	$8,549	$16,867	$0	$25,416
Assm: 11020229	**Descr:** 100W Hps Wall Mount	**UOM:**	EA	$175.34	$236.30	$0.00	$411.64
		Qty:	13	$2,279	$3,072	$0	$5,351
Assm: 11020254	**Descr:** High Bay 400W Hps Fixture	**UOM:**	EA	$200.94	$375.90	$0.00	$576.85
		Qty:	168	$33,759	$63,151	$0	$96,910

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 11020255	**Descr:** High Bay 400W Hps Fixture With Quartz Standby	**UOM:**	EA		$296.72	$467.99	$0.00	$764.70
		Qty:	23		$6,824	$10,764	$0	$17,588
Assm: 11020272	**Descr:** Exit Light With Battery Backup	**UOM:**	EA		$117.22	$212.56	$0.00	$329.78
		Qty:	4		$469	$850	$0	$1,319

FSA: **ID:** PRK **Name:** Parking Lots

Facility Type: Supporting **ID:** 12 **Name:** Parking Lots 1

Assm: 17010106	**Descr:** Heavy Brush, Light Trees, Clear, Grub, Haul	**UOM:**	ACRE		$0.00	$2,002.62	$921.83	$2,924.44
		Qty:	0		$0	$941	$433	$1,374

FSA: **ID:** GAD **Name:** Gas Distribution

Facility Type: Supporting **ID:** 12 **Name:** Gas Distribution 1

Assm: 17020401	**Descr:** Dump Charge	**UOM:**	CY		$15.00	$0.00	$0.00	$15.00
		Qty:	111		$1,666	$0	$0	$1,666

FSA: **ID:** WTD **Name:** Water Distribution

Facility Type: Supporting **ID:** 12 **Name:** Water Distribution 1

Assm: 17020401	**Descr:** Dump Charge	**UOM:**	CY		$15.00	$0.00	$0.00	$15.00
		Qty:	303		$4,539	$0	$0	$4,539

FSA: **ID:** SAN **Name:** Sanitary Sewer

Facility Type: Supporting **ID:** 12 **Name:** Sanitary Sewer 1

Assm: 17020401	**Descr:** Dump Charge	**UOM:**	CY		$15.00	$0.00	$0.00	$15.00
		Qty:	61		$912	$0	$0	$912

FSA: **ID:** PRK **Name:** Parking Lots

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Facility Type: Supporting	**ID:** 12	**Name:** Parking Lots 1						
Assm: 17030102	**Descr:** Rough Grading, 12G, 1 Pass		**UOM:**	SY	$0.00	$0.20	$0.17	$0.37
			Qty:	3433	$0	$681	$583	$1,264
FSA:	**ID:** ARD	**Name:** Access Roads						
Facility Type: Supporting	**ID:** 12	**Name:** Access Roads 1						
Assm: 17030103	**Descr:** ROUGH GRADING, 14G, 1 PASS		**UOM:**	SY	$0.00	$0.30	$0.25	$0.54
			Qty:	86720	$0	$25,799	$21,264	$47,063
FSA:	**ID:** PRK	**Name:** Parking Lots						
Facility Type: Supporting	**ID:** 12	**Name:** Parking Lots 1						
Assm: 17030107	**Descr:** Fine Grading, 120G, 2 Passes		**UOM:**	SY	$0.00	$0.09	$0.07	$0.15
			Qty:	3433	$0	$302	$227	$529
FSA:	**ID:** ARD	**Name:** Access Roads						
Facility Type: Supporting	**ID:** 12	**Name:** Access Roads 1						
Assm: 17030108	**Descr:** Fine Grading, 130G, 2 Passes		**UOM:**	SY	$0.00	$0.09	$0.07	$0.15
			Qty:	37940	$0	$3,343	$2,504	$5,847
Assm: 17030202	**Descr:** Ditch Excavation, Normal Soil, Hauloff Spoil 1 Mile		**UOM:**	CY	$0.00	$1.98	$2.08	$4.06
			Qty:	12044	$0	$23,885	$24,992	$48,878
Assm: 17030203	**Descr:** Roadway Soil Excavation, W/Scraper, Load & Haul Spoil		**UOM:**	CY	$0.00	$1.86	$2.04	$3.90
			Qty:	10539	$0	$19,622	$21,471	$41,093
FSA:	**ID:** PRK	**Name:** Parking Lots						
Facility Type: Supporting	**ID:** 12	**Name:** Parking Lots 1						

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 17030203	**Descr:** Roadway Soil Excavation, W/Scraper, Load & Haul Spoil	**UOM:**	CY	$0.00	$1.86	$2.04	$3.90
		Qty:	381	$0	$710	$777	$1,487

FSA: **ID:** GAD **Name:** Gas Distribution

Facility Type: Supporting **ID:** 12 **Name:** Gas Distribution 1

Assm: 17030220	**Descr:** 910, 1.25 CY, Wheel Loader	**UOM:**	HR	$0.00	$35.90	$19.54	$55.45
		Qty:	3	$0	$108	$59	$166

FSA: **ID:** SAN **Name:** Sanitary Sewer

Facility Type: Supporting **ID:** 12 **Name:** Sanitary Sewer 1

Assm: 17030220	**Descr:** 910, 1.25 CY, Wheel Loader	**UOM:**	HR	$0.00	$35.90	$19.54	$55.45
		Qty:	2	$0	$72	$39	$111

FSA: **ID:** WTD **Name:** Water Distribution

Facility Type: Supporting **ID:** 12 **Name:** Water Distribution 1

Assm: 17030220	**Descr:** 910, 1.25 CY, Wheel Loader	**UOM:**	HR	$0.00	$35.90	$19.54	$55.45
		Qty:	7	$0	$251	$137	$388

FSA: **ID:** LTG **Name:** Lighting-Interstate, Roadway, Parking

Facility Type: Supporting **ID:** 12 **Name:** Lighting-Interstate, Roadway, Parking 1

Assm: 17030255	**Descr:** Trenching To 48" Dp, Inc Bkfl & Compaction	**UOM:**	CY	$0.00	$5.57	$1.02	$6.59
		Qty:	2820	$0	$15,720	$2,873	$18,593

FSA: **ID:** PRK **Name:** Parking Lots

Facility Type: Supporting **ID:** 12 **Name:** Parking Lots 1

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 17030257	**Descr:** Cat 215, 1 CY, Soil, Shallow, Trenching	**UOM:**	CY		$0.00	$0.32	$0.31	$0.63
		Qty:	50		$0	$16	$15	$31
FSA:	**ID:** COM	**Name:**	Communications					
Facility Type:	Supporting	**ID:** 12	**Name:**	Communications 1				
Assm: 17030259	**Descr:** Cat 225, 1.5 CY, Soil/Sand, Trenching	**UOM:**	CY		$0.00	$0.24	$0.28	$0.53
		Qty:	195		$0	$47	$55	$102
FSA:	**ID:** SAN	**Name:**	Sanitary Sewer					
Facility Type:	Supporting	**ID:** 12	**Name:**	Sanitary Sewer 1				
Assm: 17030259	**Descr:** Cat 225, 1.5 CY, Soil/Sand, Trenching	**UOM:**	CY		$0.00	$0.24	$0.28	$0.53
		Qty:	294		$0	$71	$83	$154
FSA:	**ID:** UND	**Name:**	Underground Electrical Distribution					
Facility Type:	Supporting	**ID:** 12	**Name:**	Underground Electrical Distribution 1				
Assm: 17030259	**Descr:** Cat 225, 1.5 CY, Soil/Sand, Trenching	**UOM:**	CY		$0.00	$0.24	$0.28	$0.53
		Qty:	260		$0	$63	$74	$137
FSA:	**ID:** WTD	**Name:**	Water Distribution					
Facility Type:	Supporting	**ID:** 12	**Name:**	Water Distribution 1				
Assm: 17030259	**Descr:** Cat 225, 1.5 CY, Soil/Sand, Trenching	**UOM:**	CY		$0.00	$0.24	$0.28	$0.53
		Qty:	1640		$0	$398	$464	$862
FSA:	**ID:** GAD	**Name:**	Gas Distribution					
Facility Type:	Supporting	**ID:** 12	**Name:**	Gas Distribution 1				

				Mat $	Lab $	Eqp $	Ttl $
Assm: 17030259 **Descr:** Cat 225, 1.5 CY, Soil/Sand, Trenching	**UOM:**	CY	$0.00	$0.24	$0.28	$0.53
	Qty:	545	$0	$132	$154	$286
FSA: **ID:** SAN **Name:** Sanitary Sewer						
Facility Type: Supporting **ID:** 12 **Name:** Sanitary Sewer 1						
Assm: 17030284 **Descr:** 8 CY, Dump Truck	**UOM:**	HR	$0.00	$29.10	$36.46	$65.56
	Qty:	5	$0	$145	$182	$328
FSA: **ID:** WTD **Name:** Water Distribution						
Facility Type: Supporting **ID:** 12 **Name:** Water Distribution 1						
Assm: 17030284 **Descr:** 8 CY, Dump Truck	**UOM:**	HR	$0.00	$29.10	$36.46	$65.56
	Qty:	23	$0	$669	$839	$1,508
FSA: **ID:** GAD **Name:** Gas Distribution						
Facility Type: Supporting **ID:** 12 **Name:** Gas Distribution 1						
Assm: 17030284 **Descr:** 8 CY, Dump Truck	**UOM:**	HR	$0.00	$29.10	$36.46	$65.56
	Qty:	9	$0	$262	$328	$590
Assm: 17030401 **Descr:** 950, 3 CY, Backfill W/Excavated Material	**UOM:**	CY	$0.00	$0.51	$0.59	$1.10
	Qty:	391	$0	$198	$232	$430
FSA: **ID:** COM **Name:** Communications						
Facility Type: Supporting **ID:** 12 **Name:** Communications 1						
Assm: 17030401 **Descr:** 950, 3 CY, Backfill W/Excavated Material	**UOM:**	CY	$0.00	$0.51	$0.59	$1.10
	Qty:	112	$0	$57	$67	$123
FSA: **ID:** SAN **Name:** Sanitary Sewer						

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Facility Type: Supporting	**ID:** 12	**Name:** Sanitary Sewer 1						
Assm: 17030401	**Descr:** 950, 3 CY, Backfill W/Excavated Material		**UOM:**	CY	$0.00	$0.51	$0.59	$1.10
			Qty:	245	$0	$124	$146	$270
FSA:	**ID:** UND	**Name:** Underground Electrical Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Underground Electrical Distribution 1						
Assm: 17030401	**Descr:** 950, 3 CY, Backfill W/Excavated Material		**UOM:**	CY	$0.00	$0.51	$0.59	$1.10
			Qty:	149	$0	$76	$89	$164
FSA:	**ID:** WTD	**Name:** Water Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Water Distribution 1						
Assm: 17030401	**Descr:** 950, 3 CY, Backfill W/Excavated Material		**UOM:**	CY	$0.00	$0.51	$0.59	$1.10
			Qty:	1398	$0	$709	$831	$1,539
FSA:	**ID:** COM	**Name:** Communications						
Facility Type: Supporting	**ID:** 12	**Name:** Communications 1						
Assm: 17030405	**Descr:** 950, 3 CY, Delivered & Dumped, Backfill W/Sand		**UOM:**	CY	$20.09	$2.14	$2.08	$24.30
			Qty:	32	$643	$68	$66	$778
FSA:	**ID:** GAD	**Name:** Gas Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Gas Distribution 1						
Assm: 17030405	**Descr:** 950, 3 CY, Delivered & Dumped, Backfill W/Sand		**UOM:**	CY	$20.09	$2.14	$2.08	$24.30
			Qty:	97	$1,949	$207	$201	$2,357
FSA:	**ID:** UND	**Name:** Underground Electrical Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Underground Electrical Distribution 1						

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 17030405	**Descr:** 950, 3 CY, Delivered & Dumped, Backfill W/Sand	**UOM:**	CY	$20.09	$2.14	$2.08	$24.30
		Qty:	43	$864	$92	$89	$1,045

FSA: **ID:** SAN **Name:** Sanitary Sewer

Facility Type: Supporting **ID:** 12 **Name:** Sanitary Sewer 1

Assm: 17030405	**Descr:** 950, 3 CY, Delivered & Dumped, Backfill W/Sand	**UOM:**	CY	$20.09	$2.14	$2.08	$24.30
		Qty:	47	$935	$99	$97	$1,131

FSA: **ID:** WTD **Name:** Water Distribution

Facility Type: Supporting **ID:** 12 **Name:** Water Distribution 1

Assm: 17030405	**Descr:** 950, 3 CY, Delivered & Dumped, Backfill W/Sand	**UOM:**	CY	$20.09	$2.14	$2.08	$24.30
		Qty:	245	$4,922	$524	$508	$5,954

FSA: **ID:** ARD **Name:** Access Roads

Facility Type: Supporting **ID:** 12 **Name:** Access Roads 1

Assm: 17030501	**Descr:** Compact Subgrade, 2 Lifts	**UOM:**	CY	$0.00	$1.51	$0.04	$1.55
		Qty:	14453	$0	$21,814	$545	$22,359

FSA: **ID:** PRK **Name:** Parking Lots

Facility Type: Supporting **ID:** 12 **Name:** Parking Lots 1

Assm: 17030501	**Descr:** Compact Subgrade, 2 Lifts	**UOM:**	CY	$0.00	$1.51	$0.04	$1.55
		Qty:	477	$0	$720	$18	$738
Assm: 17030510	**Descr:** Dry Roll Gravel, Steel Roller	**UOM:**	SY	$0.00	$0.47	$0.19	$0.66
		Qty:	1717	$0	$813	$324	$1,137

FSA: **ID:** COM **Name:** Communications

Paces

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Facility Type: Supporting	**ID:** 12	**Name:** Communications 1						
Assm: 17030511	**Descr:** Compact Soil W/Vibrating Plate		**UOM:**	CY	$0.00	$1.19	$0.08	$1.27
			Qty:	112	$0	$133	$10	$143
FSA:	**ID:** UND	**Name:** Underground Electrical Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Underground Electrical Distribution 1						
Assm: 17030511	**Descr:** Compact Soil W/Vibrating Plate		**UOM:**	CY	$0.00	$1.19	$0.08	$1.27
			Qty:	149	$0	$177	$13	$190
FSA:	**ID:** WTD	**Name:** Water Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Water Distribution 1						
Assm: 17030511	**Descr:** Compact Soil W/Vibrating Plate		**UOM:**	CY	$0.00	$1.19	$0.08	$1.27
			Qty:	1398	$0	$1,663	$119	$1,782
FSA:	**ID:** GAD	**Name:** Gas Distribution						
Facility Type: Supporting	**ID:** 12	**Name:** Gas Distribution 1						
Assm: 17030511	**Descr:** Compact Soil W/Vibrating Plate		**UOM:**	CY	$0.00	$1.19	$0.08	$1.27
			Qty:	456	$0	$543	$39	$581
FSA:	**ID:** SAN	**Name:** Sanitary Sewer						
Facility Type: Supporting	**ID:** 12	**Name:** Sanitary Sewer 1						
Assm: 17030511	**Descr:** Compact Soil W/Vibrating Plate		**UOM:**	CY	$0.00	$1.19	$0.08	$1.27
			Qty:	245	$0	$292	$21	$312
FSA:	**ID:** COM	**Name:** Communications						
Facility Type: Supporting	**ID:** 12	**Name:** Communications 1						

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	32		$0	$202	$13	$215

FSA: **ID:** SAN **Name:** Sanitary Sewer

Facility Type: Supporting **ID:** 12 **Name:** Sanitary Sewer 1

Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	47		$0	$294	$19	$313

FSA: **ID:** WTD **Name:** Water Distribution

Facility Type: Supporting **ID:** 12 **Name:** Water Distribution 1

Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	245		$0	$1,549	$99	$1,649

FSA: **ID:** UND **Name:** Underground Electrical Distribution

Facility Type: Supporting **ID:** 12 **Name:** Underground Electrical Distribution 1

Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	43		$0	$272	$17	$289

FSA: **ID:** GAD **Name:** Gas Distribution

Facility Type: Supporting **ID:** 12 **Name:** Gas Distribution 1

Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	97		$0	$613	$39	$653

FSA: **ID:** PRK **Name:** Parking Lots

Facility Type: Supporting **ID:** 12 **Name:** Parking Lots 1

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 17030515	**Descr:** Compact With Pogosticks	**UOM:**	CY		$0.00	$6.32	$0.41	$6.73
		Qty:	26		$0	$164	$11	$175
FSA:	**ID:** COM	**Name:**	Communications					
Facility Type:	Supporting	**ID:** 12	**Name:**	Communications 1				
Assm: 17031002	**Descr:** 2" Dia Contractor's Trash Pump, 75 GPM	**UOM:**	DAY		$37.68	$7.38	$0.00	$45.06
		Qty:	3		$113	$22	$0	$135
FSA:	**ID:** ARD	**Name:**	Access Roads					
Facility Type:	Supporting	**ID:** 12	**Name:**	Access Roads 1				
Assm: 18010102	**Descr:** Gravel, Delivered & Dumped	**UOM:**	CY		$14.43	$1.60	$1.09	$17.12
		Qty:	10539		$152,070	$16,836	$11,531	$180,436
FSA:	**ID:** PRK	**Name:**	Parking Lots					
Facility Type:	Supporting	**ID:** 12	**Name:**	Parking Lots 1				
Assm: 18010102	**Descr:** Gravel, Delivered & Dumped	**UOM:**	CY		$14.43	$1.60	$1.09	$17.12
		Qty:	381		$5,505	$609	$417	$6,531
Assm: 18010202	**Descr:** Concrete Curb & Gutter, 6" x 24", Formed	**UOM:**	LF		$10.55	$4.78	$0.00	$15.33
		Qty:	495		$5,221	$2,366	$0	$7,587
Assm: 18010310	**Descr:** Prime Coat	**UOM:**	SY		$0.29	$0.02	$0.01	$0.33
		Qty:	1717		$500	$36	$25	$560
FSA:	**ID:** ARD	**Name:**	Access Roads					
Facility Type:	Supporting	**ID:** 12	**Name:**	Access Roads 1				
Assm: 18010310	**Descr:** Prime Coat	**UOM:**	SY		$0.29	$0.02	$0.01	$0.33
		Qty:	28907		$8,415	$601	$416	$9,432

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
FSA:	**ID:** PRK	**Name:** Parking Lots						
Facility Type:	Supporting	**ID:** 12	**Name:** Parking Lots 1					
Assm: 18010312	**Descr:** Asphalt Wearing Course,1 Pass (Line Item Incl 5% Waste)		**UOM:**	TON	$29.51	$4.14	$1.63	$35.29
			Qty:	140	$4,132	$580	$229	$4,941
FSA:	**ID:** ARD	**Name:** Access Roads						
Facility Type:	Supporting	**ID:** 12	**Name:** Access Roads 1					
Assm: 18010312	**Descr:** Asphalt Wearing Course,1 Pass (Line Item Incl 5% Waste)		**UOM:**	TON	$29.51	$4.14	$1.63	$35.29
			Qty:	3930	$115,967	$16,273	$6,421	$138,662
FSA:	**ID:** PRK	**Name:** Parking Lots						
Facility Type:	Supporting	**ID:** 12	**Name:** Parking Lots 1					
Assm: 18020205	**Descr:** 24" Dia, 5' Deep Precast Area Drain W/Grate		**UOM:**	EA	$1,032.79	$1,059.68	$8.15	$2,100.62
			Qty:	3	$3,098	$3,179	$24	$6,302
Assm: 18020401	**Descr:** Parking Space Striping		**UOM:**	EA	$2.56	$3.26	$0.62	$6.45
			Qty:	34	$87	$111	$21	$219
FSA:	**ID:** FEA	**Name:** Fencing						
Facility Type:	Supporting	**ID:** 12	**Name:** Fencing 1					
Assm: 18040105	**Descr:** Boundary Fence, 5' Galv		**UOM:**	LF	$1.08	$2.80	$0.98	$4.86
			Qty:	9880	$10,692	$27,647	$9,691	$48,031
FSA:	**ID:** WTD	**Name:** Water Distribution						
Facility Type:	Supporting	**ID:** 12	**Name:** Water Distribution 1					

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 19010211	**Descr:** 6", Class 150, PVC Piping	**UOM:**	LF	$4.19	$5.97	$0.35	$10.51
		Qty:	3000	$12,573	$17,914	$1,047	$31,533
FSA: **ID:** SAN	**Name:** Sanitary Sewer						
Facility Type: Supporting	**ID:** 12 **Name:** Sanitary Sewer 1						
Assm: 19020127	**Descr:** 8" PVC Pipe Sanitary	**UOM:**	LF	$5.02	$4.42	$0.64	$10.08
		Qty:	500	$2,510	$2,209	$321	$5,040
Assm: 19020201	**Descr:** Precast, CIP Base, 4' Dia, 6' Deep, Manhole	**UOM:**	EA	$466.14	$423.30	$56.61	$946.05
		Qty:	2	$932	$847	$113	$1,892
FSA: **ID:** PRK	**Name:** Parking Lots						
Facility Type: Supporting	**ID:** 12 **Name:** Parking Lots 1						
Assm: 19030174	**Descr:** 12" RCP, Class 4, With Gaskets	**UOM:**	LF	$11.59	$7.13	$0.46	$19.18
		Qty:	99	$1,143	$703	$46	$1,891
Assm: 19030176	**Descr:** 18" RCP, Class 4, With Gaskets	**UOM:**	LF	$14.46	$11.51	$0.75	$26.73
		Qty:	37	$541	$431	$28	$1,000
FSA: **ID:** ARD	**Name:** Access Roads						
Facility Type: Supporting	**ID:** 12 **Name:** Access Roads 1						
Assm: 19030402	**Descr:** 34' Complete, 24" CMP Culvert W/Headwalls	**UOM:**	EA	$2,687.02	$1,776.01	$519.28	$4,982.31
		Qty:	7	$18,809	$12,432	$3,635	$34,876
FSA: **ID:** GAD	**Name:** Gas Distribution						
Facility Type: Supporting	**ID:** 12 **Name:** Gas Distribution 1						
Assm: 19070104	**Descr:** 4" Black Steel Pipe, Welded T & C Sch 40	**UOM:**	LF	$3.90	$2.54	$0.02	$6.47
		Qty:	1500	$5,857	$3,817	$28	$9,702

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
FSA:	**ID:** LTG	**Name:**	Lighting-Interstate, Roadway, Parking					
Facility Type:	Supporting	**ID:** 12	**Name:**	Lighting-Interstate, Roadway, Parking 1				
Assm:	20020501	**Descr:**	1/C #4 Copper Grd 600V DB, Wire	**UOM:**	LF	$0.55	$0.64	$0.00	$1.19
				Qty:	29256	$16,012	$18,855	$0	$34,867
Assm:	20020502	**Descr:**	1/C #6 Copper Grd 600V DB, Wire	**UOM:**	LF	$0.38	$0.64	$0.00	$1.03
				Qty:	20018	$7,621	$12,902	$0	$20,522
Assm:	20020503	**Descr:**	3/C #6, W/#6 Grd 5KV DB, Wire	**UOM:**	LF	$3.42	$2.86	$0.35	$6.64
				Qty:	17862	$61,090	$51,153	$6,303	$118,547
FSA:	**ID:** UND	**Name:**	Underground Electrical Distribution					
Facility Type:	Supporting	**ID:** 12	**Name:**	Underground Electrical Distribution 1				
Assm:	20020521	**Descr:**	15 KV, 3/0, Shielded Cable, Copper	**UOM:**	LF	$2.61	$1.60	$0.20	$4.41
				Qty:	4500	$11,760	$7,187	$886	$19,833
Assm:	20020546	**Descr:**	15 KV, 1/0 To 4/0 Conductor, Terminations & Splicing	**UOM:**	EA	$131.16	$413.79	$0.00	$544.95
				Qty:	6	$787	$2,483	$0	$3,270
FSA:	**ID:** COM	**Name:**	Communications					
Facility Type:	Supporting	**ID:** 12	**Name:**	Communications 1				
Assm:	20020610	**Descr:**	2" PVC Conduit	**UOM:**	LF	$1.10	$1.97	$0.00	$3.08
				Qty:	3000	$3,314	$5,916	$0	$9,230
FSA:	**ID:** UND	**Name:**	Underground Electrical Distribution					
Facility Type:	Supporting	**ID:** 12	**Name:**	Underground Electrical Distribution 1				
Assm:	20020612	**Descr:**	4" PVC Conduit	**UOM:**	LF	$3.02	$4.43	$0.00	$7.45
				Qty:	3000	$9,053	$13,286	$0	$22,340

Project Summary Report

Date 07/26/2002

					Mat $	Lab $	Eqp $	Ttl $
Assm: 20020615	**Descr:** Concrete Encasement For Ductbank	**UOM:**	CY		$93.61	$80.85	$6.86	$181.32
		Qty:	75		$7,020	$6,064	$514	$13,599

FSA: **ID:** COM **Name:** Communications

Facility Type: Supporting **ID:** 12 **Name:** Communications 1

Assm: 20020615	**Descr:** Concrete Encasement For Ductbank	**UOM:**	CY		$93.61	$80.85	$6.86	$181.32
		Qty:	56		$5,242	$4,528	$384	$10,154

FSA: **ID:** LTG **Name:** Lighting-Interstate, Roadway, Parking

Facility Type: Supporting **ID:** 12 **Name:** Lighting-Interstate, Roadway, Parking 1

Assm: 20030102	**Descr:** 5/15KV - 277/480V, 75KVA Transformer, Oil, Pad Mtd	**UOM:**	EA		$8,561.20	$1,004.21	$20.33	$9,585.74
		Qty:	8		$68,490	$8,034	$163	$76,686
Assm: 20030303	**Descr:** 20' Brushed Aluminum Pole (Single Arm) W/Base	**UOM:**	EA		$964.98	$368.06	$35.10	$1,368.13
		Qty:	93		$89,743	$34,229	$3,264	$127,236
Assm: 20030601	**Descr:** 150W Hps Fixture	**UOM:**	EA		$235.46	$118.98	$0.00	$354.44
		Qty:	93		$21,897	$11,065	$0	$32,963

FSA: **ID:** COM **Name:** Communications

Facility Type: Supporting **ID:** 12 **Name:** Communications 1

Assm: 20040102	**Descr:** 51 Pair No. 22 Awg Wire, Comm Cable	**UOM:**	LF		$3.93	$1.35	$0.00	$5.28
		Qty:	3000		$11,793	$4,037	$0	$15,830

FSA: **ID:** GAD **Name:** Gas Distribution

Facility Type: Supporting **ID:** 12 **Name:** Gas Distribution 1

Assm: 20060101	**Descr:** 3-9 Lb Magnesium Anodes, Cathodic Protection Point	**UOM:**	EA		$191.69	$614.75	$41.48	$847.92
		Qty:	5		$958	$3,074	$207	$4,240

Paces

Project Summary Report

Date 07/26/2002

	Mat $	Lab $	Eqp $	Ttl $
Project Direct Cost: (M, L,E, T)	$70,551,246	$52,646,952	$2,362,893	$125,561,091

Pavement			$0
Site			$0
Utilities			$0
Markups			$52,096,620
Contingencies	5	%	$8,882,886
SIOH	5.7	%	$10,632,810
Total Project Cost:			$197,173,400
Design Costs:	0	%	$0
Total Project Cost With Design:			$197,173,400