DOE/EIS-0380D
June 2006

Draft
Site-Wide Environmental Impact Statement for Continued Operation of Los Alamos National Laboratory Los Alamos, New Mexico

Volume 2 Book 2

National Nuclear Security Administration

Los Alamos NATIONAL LABORATORY

AVAILABILITY OF
THE DRAFT SITE-WIDE ENVIRONMENTAL IMPACT STATEMENT FOR CONTINUED OPERATION OF LOS ALAMOS NATIONAL LABORATORY, LOS ALAMOS, NEW MEXICO

To submit general questions regarding this EIS, or to request a copy, please contact:

Elizabeth Withers, EIS Document Manager
Los Alamos Site Office
National Nuclear Security Administration
U.S. Department of Energy
528 35th Street
Los Alamos, NM 87544-2201
Telephone: 505-845-4984

Printed with soy ink on recycled paper

DOE/EIS-0380D
June 2006

Draft
Site-Wide Environmental Impact Statement for Continued Operation of Los Alamos National Laboratory Los Alamos, New Mexico

Volume 2 Book 2

National Nuclear Security Administration

Los Alamos NATIONAL LABORATORY

COVER SHEET

Responsible Agency: U.S. Department of Energy (DOE)
National Nuclear Security Administration (NNSA)

Title: *Draft Site-Wide Environmental Impact Statement for Continued Operation of Los Alamos National Laboratory, Los Alamos, New Mexico* (SWEIS) (DOE/EIS-0380D)

Location: Los Alamos, New Mexico

For additional information or for copies of this draft SWEIS, contact:

Elizabeth Withers, EIS Document Manager
Los Alamos Site Office
National Nuclear Security Administration
U.S. Department of Energy
538 35th Street
Los Alamos, NM 87544-2201
Telephone: 505-845-4984

For general information on the DOE National Environmental Policy Act (NEPA) process, contact:

Carol M. Borgstrom, Director
Office of NEPA Policy and Compliance
Office of Environment, Safety and Health
U.S. Department of Energy
1000 Independence Avenue, SW
Washington, DC 20585-1290
Telephone: 202-586-4600, or leave a message at 1-800-472-2756

This document is available on the NNSA Los Alamos Site Office website (http://www.doeal.gov/LASO) for viewing and downloading.

***Abstract*:** NNSA proposes to continue operating the Los Alamos National Laboratory (LANL) located in Los Alamos County, in north-central New Mexico. NNSA has identified and assessed three alternatives for continued operation of LANL: (1) No Action, (2) Reduced Operations, and (3) Expanded Operations. Expanded Operations is NNSA's Preferred Alternative. In the No Action Alternative, NNSA would continue the historical mission support activities LANL has conducted at currently approved operational levels. Under the Reduced Operations Alternative, NNSA would eliminate selected activities and limit the operations of other selected activities. In the Expanded Operations Alternative, NNSA would operate LANL at the highest levels of activity currently foreseeable, including full implementation of the mission assignments. Under all of the alternatives, the affected environment is primarily within 50 miles (80 kilometers) of LANL. Analyses indicate little difference in the environmental impacts among alternatives for many resource areas. The primary discriminators are: public risk due to radiation exposure, collective worker risk due to radiation exposure, socioeconomic effects due to LANL employment changes, electrical power and water demand, waste management and transportation.

Public Comments: In preparation of this Draft SWEIS, NNSA considered comments received from the public during the scoping period (January 19, 2005 to February 17, 2005). Locations and times of public hearings on this document will be announced in the *Federal Register* in June 2006. Comments on this Draft SWEIS will be accepted at the address listed above for a period of 60 days following its issuance and will be considered for preparation of the Final SWEIS. Any comments received after the 60-day period will be considered to the extent practicable for the preparation of the Final EIS.

TABLE OF CONTENTS

TABLE OF CONTENTS

Cover Sheet iii

Table of Contents vii

List of Figures xviii

List of Tables xxi

Acronyms, Abbreviations, and Conversion Charts xxxi

Volume 2 Book 1
Appendices A through H

Appendix A
Federal Register Notices

Appendix B
Nonradiological Air Quality

B.1 Introduction B-1
- B.1.1 Assumptions, Data Sources, Standards, and Models B-1
  - B.1.1.1 Applicable Guidelines and Standards and Emission Sources B-1
  - B.1.1.2 Receptors and Receptor Sets B-4
  - B.1.1.3 Air Quality Dispersion B-5
- B.1.2 Criteria Pollutants – General Approach B-5
  - B.1.2.1 Criteria Pollutants – Methodology B-6
  - B.1.2.2 Results of Criteria Pollutant Analysis B-6
- B.1.3 Toxic Air Pollutants – General Approach B-6
  - B.1.3.1 Toxic Pollutants – Methodology for Individual Pollutants B-8
  - B.1.3.2 Toxic Pollutants – Results of Individual Pollutants Analysis B-9
  - B.1.3.3 Toxic Pollutants – Methodology for Combined Impacts Analyses B-10
  - B.1.3.4 Toxic Pollutants – Results of Combined Impact Analysis B-11

B.2 References B-12

Appendix C
Evaluation of Human Health Impacts from Normal Operations

C.1 Impacts on Human Health from Radiological Exposure C-1
- C.1.1 About Radiation and Radioactivity C-2
  - C.1.1.1 What Is Radiation? C-2
  - C.1.1.2 Units of Radiation Measure C-3
  - C.1.1.3 Sources of Radiation C-4
  - C.1.1.4 Exposure Pathways C-5
  - C.1.1.5 Limits of Radiation Exposure C-6
- C.1.2 Health Effects C-6
  - C.1.2.1 Health Effect Risk Estimators Used in this SWEIS C-9
  - C.1.2.2 Material of Interest at Los Alamos National Laboratory C-10

C.1.3 Methods Used to Estimate Radiological Impacts from Normal Operations C-11
C.1.3.1 Key Facilities Modeled C-11
C.1.3.2 CAP-88 Model C-12
C.1.3.3 Model Input Parameters C-13
C.1.3.4 Results of Analyses C-21
C.1.4 Impacts to Offsite Resident, Recreational User and Special Pathways Receptors from Radionuclides and Chemical Contaminants in the Environment C-26
C.1.4.1 Methodology C-26
C.1.4.2 Estimates of Ingestion Pathway Radiation Dose and Risk C-29

C.2 Impacts on Human Health from Nonradioactive Contaminants in the Environment C-40
C.2.1 Methods Used to Estimate Risks from Ingestion of Nonradioactive Contaminants C-41

C.3 Impacts on Human Health from Biological Agents C-57
C.3.1 Introduction C-57
C.3.2 Principles of Biosafety C-57
C.3.2.1 Safety Equipment (Primary Barriers) C-58
C.3.2.2 Facility Design and Construction (Secondary Barriers) C-58
C.3.2.3 Waste C-58
C.3.2.4 Biological Release C-59
C.3.3 Biosafety Levels C-59
C.3.3.1 Biosafety Level 1 ..... C-59
C.3.3.2 Biosafety Level 2 ..... C-59
C.3.3.3 Biosafety Level 3 ..... C-60
C.3.3.4 Biosafety Level 4 ..... C-60
C.3.4 Detection C-61
C.3.5 Select Biological Agents C-62
C.3.6 Transmission C-62

C.4 Key Differences Between Biological, Radiological, and Chemical Agents C-63

C.5 References C-64

Appendix D
Evaluation of Human Health Impacts from Facility Accidents

D.1 Introduction D-1

D.2 Data and Analysis Changes from the *1999 SWEIS* D-1

D.3 Radiological and Chemical Accidents D-2
D.3.1 Radiological and Chemical Scenarios and Source Terms D-10
D.3.2 Radiological Accident Impacts D-10
D.3.2.1 No Action Alternative D-16
D.3.2.2 Reduced Operations Alternative D-16
D.3.2.3 Expanded Operations Alternative D-16
D.3.3 Chemical Accident Impacts D-23
D.3.3.1 No Action Alternative D-25
D.3.3.2 Reduced Operations Alternative D-25
D.3.3.3 Expanded Operations Alternative D-25

D.4 Site-wide Seismic Impacts D-26
D.4.1 Source Term Data D-27
D.4.2 No Action Alternative Impacts D-27
D.4.2.1 Site-wide Seismic 1 – Radiological Impacts D-27
D.4.2.2 Site-wide Seismic 2 – Radiological Impacts D-32
D.4.2.3 Site-wide Seismic 1 – Chemical Impacts D-33
D.4.2.4 Site-wide Seismic 2 – Chemical Impacts D-34
D.4.3 Reduced Operations Alternative Impacts D-37

D.4.4 Expanded Operations Alternative Impacts D-37
D.4.4.1 Site-wide Seismic 1 – Radiological Impacts D-37
D.4.4.2 Site-wide Seismic 2– Radiological Impacts D-37
D.4.4.3 Site-wide Seismic 1 – Chemical Impacts D-38
D.4.4.4 Site-wide Seismic 2 – Chemical Impacts D-38

D.5 Wildfire Accidents D-38
D.5.1 Background D-38
D.5.1.1 Consuming Combustible Structures and Vegetation D-38
D.5.1.2 Recent Widespread Environmental Changes D-39
D.5.1.3 Wildfire Occurrence D-40
D.5.1.3.1 General Approach D-40
D.5.1.3.2 Region of Interest D-41
D.5.1.3.3 Lightning Strike Densities and Intensities D-41
D.5.1.3.4 Modeled Fire Polygons D-41
D.5.1.3.5 Fuel Conditions D-42
D.5.1.3.6 Wildfire Model Development D-42
D.5.1.3.7 Wildfire Model Results D-43
D.5.2 Current Wildfire Hazard Conditions D-43
D.5.2.1 Changes to the Fuels and Fire Hazard Conditions in the Past 5 Years D-43
D.5.2.2 Potential Wildfire Scenarios D-46
D.5.2.3 Frequency of Wildfires D-47
D.5.2.4 Conditions that Favor Wildfire D-48
D.5.2.5 Determining the Joint Probability of Occurrence of Weather and Fire Danger Conditions D-48
D.5.3 General Wildfire Scenario D-49
D.5.3.1 Description D-49
D.5.3.2 Dispersion Meteorology, Thermal Energy, and Soil Resuspension Following the Fire D-50
D.5.3.3 Exposures from Burning Vegetation and Suspended Soil D-51
D.5.4 Methodology D-53
D.5.4.1 Evaluation of Building Fires D-53
D.5.4.2 Public Exposure from Burning Buildings D-55
D.5.4.3 Effects of Hazardous Chemicals D-56
D.5.4.4 Onsite Workers and Offsite Population D-56
D.5.5 Wildfire Accident Impacts Analysis D-57
D.5.5.1 Facility Source Terms D-57
D.5.5.2 Radiological Impacts D-57
D.5.5.3 Chemical D-62
D.5.5.4 Additional Environmental Effects D-63
D.5.6 Mitigation D-66

D.6 Involved Worker Hazards D-66

D.7 Maximally Exposed Individual-Type Doses versus Distance D-67

D.8 MACCS2 Code Description D-73

D.9 ALOHA Code Description D-75

D.10 References D-78

Appendix E
Current Understanding of the Groundwater Regime at Los Alamos National Laboratory

E.1 Introduction E-1

E.2 Regional Setting E-2

E.3 Structural Setting E-3

E.4 Volcanic Setting E-5

E.5 Stratigraphic Framework of the Pajarito Plateau E-7
E.5.1 Santa Fe Group E-8
E.5.2 Upper Pliocene and Quaternary Units E-12

E.6 Hydrogeology E-15
E.6.1 Comparison of the Bedrock Geologic Framework with the Hydrologic Framework E-15
E.6.2 Groundwater Occurrence E-15
E.6.2.1 Alluvial Groundwater E-18
E.6.2.2 Deep Perched Groundwater E-18
E.6.2.3 Regional Groundwater E-19
E.6.3 Hydrogeologic Units E-20

E.7 Conceptual Models E-22
E.7.1 Geochemical Conceptual Model E-23
E.7.1.1 Contaminant Distributions E-27
E.7.2 Geohydrologic Conceptual Model E-29

E.8 Numerical Modeling Studies E-31
E.8.1 A Vadose Zone Flow and Transport Model for Los Alamos Canyon, Los Alamos, New Mexico E-31
E.8.2 Hydrologic Behavior of Unsaturated, Fractured Tuff: Interpretation and Modeling of a Wellbore Injection Test E-32
E.8.3 Development and Application of Numerical Models to Estimate Fluxes through the Regional Aquifer beneath the Pajarito Plateau E-33
E.8.4 Observations and Modeling of Deep Perched Water beneath the Pajarito Plateau E-35

E.9 References E-37

Appendix F
Environmental Sample Data

F.1 Environmental Monitoring Selection F-1

F.2 Evaluation of Los Alamos National Laboratory Environmental Sampling Data F-1

F.3 Environmental Sample Data F-19

F.4 References F-59

Appendix G
Impacts Analyses of Projects to Maintain Existing Los Alamos National Laboratory Operations and Capabilities

G.1 Center for Weapons Physics Research Construction and Operation Impact Assessment G-8
G.1.1 Introduction G-9
G.1.2 Options Considered G-9
G.1.2.1 No Action Option G-9
G.1.2.2 Proposed Project G-10
G.1.3 Affected Environment and Environmental Consequences G-11
G.1.3.1 No Action Option G-12
G.1.3.2 Proposed Project G-12

G.2 Replacement Office Buildings Impact Assessment G-20
G.2.1 Introduction G-20
G.2.2 Options Considered G-21
G.2.2.1 No Action Option G-21
G.2.2.2 Proposed Project G-21

G.2.3 Affected Environment and Environmental Consequences G-22
G.2.3.1 No Action Option G-23
G.2.3.2 Proposed Project G-23

G.3 Radiological Sciences Institute, Including Phase I – The Institute for Nuclear Nonproliferation Science and Technology Impact Assessment G-29
G.3.1 Introduction G-30
G.3.2 Options Considered G-30
G.3.2.1 No Action Option G-31
G.3.2.2 Proposed Project G-33
G.3.3 Affected Environment and Environmental Consequences G-34
G.3.3.1 No Action Option G-35
G.3.3.2 Proposed Project G-40

G.4 Radioactive Liquid Waste Treatment Facility Upgrade Impact Assessment G-60
G.4.1 Introduction G-60
G.4.2 Options Considered G-63
G.4.2.1 No Action Option G-63
G.4.2.2 Option 1: Single Liquid Waste Treatment Building Option – Proposed Project G-65
G.4.2.3 Option 2: Two Liquid Waste Treatment Buildings Option G-66
G.4.2.4 Option 3: Two Liquid Waste Treatment Buildings and Renovation Option G-69
G.4.2.5 Auxiliary Actions G-70
G.4.2.6 Options Considered but Dismissed G-70
G.4.3 Affected Environment and Environmental Consequences G-70
G.4.3.1 No Action Option G-71
G.4.3.2 Option 1: Single Liquid Waste Treatment Building Option – Proposed Project G-72
G.4.3.3 Option 2: Two Liquid Waste Treatment Buildings Option G-81
G.4.3.4 Option 3: Two Liquid Waste Treatment Buildings and Renovation Option G-85

G.5 Los Alamos Neutron Science Center (LANSCE) Refurbishment Impacts Assessment G-88
G.5.1 Introduction G-88
G.5.2 Options Considered G-89
G.5.2.1 No Action Option G-89
G.5.2.2 Proposed Project G-89
G.5.2.3 Options Considered but Dismissed G-91
G.5.3 Affected Environment and Environmental Consequences G-91
G.5.3.1 No Action Option G-93
G.5.3.2 Proposed Project G-93

G.6 Technical Area 55 Radiography Facility Impacts Assessment G-97
G.6.1 Introduction G-97
G.6.2 Options Considered G-98
G.6.2.1 No Action Option G-98
G.6.2.2 Option 1: New Radiography Building Option G-99
G.6.2.3 Option 2: Hybrid Option G-99
G.6.2.4 Option 3: Renovation Option G-100
G.6.2.5 Options Considered but Dismissed G-100
G.6.3 Affected Environment and Environmental Consequences G-101
G.6.3.1 No Action Option G-102
G.6.3.2 Option 1: New Radiography Building Option G-103
G.6.3.3 Option 2: Hybrid Option G-108
G.6.3.4 Option 3: Renovation Option G-109

G.7 Plutonium Facility Complex Refurbishment Project Impact Assessment G-110
G.7.1 Introduction G-110
G.7.2 Options Considered G-112
G.7.2.1 No Action Option G-112
G.7.2.2 Proposed Project G-112

G.7.2.3 Options Considered but Dismissed G-115
G.7.3 Affected Environment and Environmental Consequences G-115
G.7.3.1 No Action Option G-116
G.7.3.2 Proposed Project G-117

G.8 Science Complex Impact Assessment G-124
G.8.1 Introduction G-124
G.8.2 Options Considered G-125
G.8.2.1 No Action Option G-125
G.8.2.2 Option 1: Northwest Technical Area 62 Site Option G-125
G.8.2.3 Option 2: Research Park Site Option G-126
G.8.2.4 Option 3: South Technical Area 3 Site Option G-127
G.8.2.5 Options Considered but Dismissed G-127
G.8.3 Affected Environment and Environmental Consequences G-127
G.8.3.1 No Action Option G-128
G.8.3.2 Option 1: Northwest Technical Area 62 Site Option G-128
G.8.3.3 Option 2: Research Park Site Option G-136
G.8.3.4 Option 3: South TA-3 Site Option G-139

G.9 Remote Warehouse and Truck Inspection Station Impact Assessment G-144
G.9.1 Introduction G-144
G.9.2 Options Considered G-145
G.9.2.1 No Action Option G-145
G.9.2.2 Proposed Project G-145
G.9.2.3 Options Considered but Dismissed G-147
G.9.3 Affected Environment and Environmental Consequences G-147
G.9.3.1 No Action Option G-147
G.9.3.2 Proposed Project G-148

G.10 References G-155

Appendix H
Impacts Analyses of Closure and Remediation Actions

H.1 Technical Area 18 Closure, Including Remaining Operations Relocation, and Structure Decontamination, Decommissioning, and Demolition Impacts Assessment H-4
H.1.1 Introduction and Purpose and Need for Agency Action H-4
H.1.2 Options Description H-10
H.1.2.1 Disposition of Remaining Security Category III and IV H-11
H.1.2.2 Disposition of Technical Area 18 Facilities H-11
H.1.3 Affected Environment and Environmental Consequences H-12
H.1.3.1 Disposition of Remaining Security Category III and IV Capabilities and Materials H-12
H.1.3.2 Disposition of Technical Area 18 Buildings and Structures H-13

H.2 Technical Area 21 Structure Decontamination, Decommissioning, and Demolition Project Impact Assessment H-22
H.2.1 Introduction and Purpose and Need for Agency Action H-22
H.2.2 Options Description H-30
H.2.2.1 No Action Option H-31
H.2.2.2 Technical Area 21 Complete Decontamination, Decommissioning, and Demolition Option H-31
H.2.2.3 Compliance Support Option – Partial Decontamination, Decommissioning, and Demolition to Allow Consent Order Compliance H-32
H.2.3 Affected Environment and Environmental Consequences H-34
H.2.3.1 No Action Option H-34
H.2.3.2 Technical Area 21 Complete Decontamination, Decommissioning, and Demolition Option H-35

H.2.3.3 Compliance Support Option – Decontamination, Decommissioning, and Demolition to Support the Consent Order Activities H-55

H.3 Waste Management Facilities Transition Impacts Assessment H-59
H.3.1 Introduction and Purpose and Need for Agency Action H-59
H.3.2 Options Description H-64
H.3.2.1 No Action Option H-64
H.3.2.2 Option 1: Accelerated Actions for Meeting the Consent Order H-64
H.3.2.3 Option 2: Interim Actions Necessary for Meeting Consent Order and Other Options H-73
H.3.2.4 Options Considered but Eliminated H-74
H.3.3 Affected Environment and Environmental Consequences H-75
H.3.3.1 No Action Option H-76
H.3.3.2 Option 1: Accelerated Actions for Meeting the Consent Order H-76
H.3.3.3 Option 2: Interim Actions Necessary for Meeting Consent Order and Other Alternatives H-103

H.4 References H-109

Volume 2 Book 2
Appendices I through M

Appendix I
Major Material Disposal Area Remediation, Canyon Cleanups, and Other Consent Order Actions

I.1 Introduction I-1
I.1.1 Need for Agency Action I-1
I.1.2 Purpose and Approach I-2
I.1.3 Options Considered in This Project-Specific Analysis I-5
1.1.4 Related National Environmental Policy Act Analyses I-6

I.2 Background I-7
I.2.1 General Setting I-7
I.2.2 The Los Alamos National Laboratory Environmental Restoration Project I-7
I.2.2.1 The Los Alamos National Laboratory Environmental Restoration Project Background I-7
I.2.2.2 Consent Order I-9
I.2.3 Firing Sites and Other PRSs within Testing Hazard Zones I-10
I.2.3.1 Technical Area 15: Firing Site E-F I-11
I.2.3.2 Firing Site R-44 ..... I-15
I.2.3.3 Technical Area 6: Material Disposal Area F I-16
I.2.3.4 Technical Area 15: Material Disposal Area Z I-19
I.2.3.5 Technical Area 36: Material Disposal Area AA I-19
I.2.3.6 Technical Area 39: Material Disposal Area Y I-20
I.2.3.7 Technical Area 49: Material Disposal Area AB I-20
I.2.4 Canyons I-20
I.2.5 Technical Area Investigations I-21
I.2.5.1 Technical Area 10: Bayo Canyon Site I-21
I.2.5.2 Technical Area 21: Material Disposal Areas A, B, T, and U I-22
I.2.5.3 Technical Area 49: Material Disposal Area AB I-41
I.2.5.4 Technical Area 50: Material Disposal Area C I-50
I.2.5.5 Technical Area 54: Material Disposal Areas G, H, and L I-55
I.2.6 Other Solid Waste Management Units and Areas of Concern, Including Aggregate Areas I-70
I.2.7 Continuing Investigations I-70
I.2.7.1 Solid Waste Management Unit 3-010(a): Vacuum Oil Disposal Area I-72
I.2.7.2 Solid Waste Management Unit 16-003(O): Fish Ladder Site I-72

I.2.7.3 Solid Waste Management Unit 16-008(a): Inactive Pond I-72
I.2.7.4 Solid Waste Management Unit 16-018 (Material Disposal Area P) and Technical Area 16-387 ..... I-73
I.2.7.5 Solid Waste Management Units 16-021(c) and 16-003(k): 260 Outfall I-73
I.2.7.6 Solid Waste Management Unit 21-001(k): Technical Area 21 Outfall I-75
I.2.7.7 Technical Area 35 (Middle Mortandad–Ten Site Aggregate Area) I-76
I.2.7.8 Technical Area 49: Areas 5, 6, and 10 ..... I-78
I.2.7.9 Solid Waste Management Unit 53-002 (a and b): Impoundments I-78
I.2.7.10 Solid Waste Management Unit 73-001 (a–d) and 73-004 (d): Airport Landfill I-79
I.2.7.11 Solid Waste Management Unit 73-002: Incinerator Ash Pile I-79
I.2.8 Additional Material Disposal Areas I-80
I.2.8.1 Technical Area 8: Material Disposal Area Q I-80
I.2.8.2 Technical Area 9: Material Disposal Area M I-80
I.2.8.3 Technical Area 15: Material Disposal Area N I-81
I.2.8.4 Technical Area 16: Material Disposal Area R I-81
I.2.8.5 Technical Area 33: Material Disposal Areas D, E, and K I-82

I.3 Description of Options I-84
I.3.1 Overview of Options I-84
I.3.2 Continuing Environmental Restoration Work I-85
I.3.2.1 Existing Waste Forecasts I-85
I.3.2.2 Investigations I-88
I.3.2.3 Maintenance of Nuclear Environmental Sites I-90
I.3.3 Remediation of Material Disposal Areas I-92
I.3.3.1 Corrective Measure Technologies Possibly Suitable for Material Disposal Areas I-93
I.3.3.2 Options for Remediation of Material Disposal Areas I-111
I.3.4 Remediation of PRSs other than Material Disposal Areas I-167
I.3.4.1 Possible Treatment Technologies I-167
I.3.4.2 Remediation of Representative PRSs I-168
I.3.4.3 Waste Generation Estimates I-171
I.3.5 Waste Transportation and Disposal Assumptions I-171
I.3.6 Waste, Materials, Shipment, and Personnel Projections Under Options I-174
I.3.6.1 Waste Generation I-174
I.3.6.2 Transportation and Disposal of Waste I-176
I.3.6.3 Cover Materials, Excavated Soil, and Materials Transport I-179
I.3.6.4 Equipment, Emissions, and Personnel Assumptions I-184
I.3.6.5 Affected Area Assumptions I-191

I.4 Affected Environment I-193
I.4.1 Land Resources I-193
I.4.1.1 Land Use I-193
I.4.1.2 Visual Environment I-197
I.4.2 Geology and Soils I-200
I.4.3 Water Resources I-200
I.4.4 Air Quality and Noise I-203
I.4.4.1 Climatology and Meteorology I-203
I.4.4.2 Air Quality and Visibility I-204
I.4.4.3 Noise, Air Blasts, and Vibration I-204
I.4.5 Ecological Resources I-205
I.4.6 Human Health I-211
I.4.7 Cultural Resources I-211
I.4.7.1 Archaeological Resources and Historic Buildings and Structures I-211
I.4.7.2 Traditional Cultural Properties I-214
I.4.8 Socioeconomics and Infrastructure I-214
I.4.8.1 Socioeconomics I-214
I.4.8.2 Infrastructure I-214
I.4.9 Waste Management I-215

I.4.10 Transportation I-215
I.4.11 Environmental Justice I-219

I.5 Environmental Consequences I-219
I.5.1 Land Resources I-219
I.5.1.1 No Action Option I-219
I.5.1.2 Capping Option I-220
I.5.1.3 Removal Option I-223
I.5.2 Geology and Soils I-225
I.5.2.1 No Action Option I-225
I.5.2.2 Capping Option I-226
I.5.2.3 Removal Option I-226
I.5.3 Water Resources I-227
I.5.3.1 No Action Option I-227
I.5.3.2 Capping Option I-230
I.5.3.3 Removal Option I-233
I.5.4 Air Quality and Noise I-234
I.5.4.1 No Action Option I-234
I.5.4.2 Capping Option I-236
I.5.4.3 Removal Option I-240
I.5.5 Ecological Resources I-243
I.5.5.1 No Action Option I-243
I.5.5.2 Capping Option I-244
I.5.5.3 Removal Option I-245
I.5.6 Human Health I-246
I.5.6.1 No Action Option I-246
I.5.6.2 Capping Option I-247
I.5.6.3 Removal Option I-248
I.5.7 Cultural Resources I-254
I.5.7.1 No Action Option I-254
I.5.7.2 Capping Option I-254
I.5.7.3 Removal Option I-255
I.5.8 Socioeconomics and Infrastructure I-255
I.5.8.1 No Action Option I-255
I.5.8.2 Capping Option I-255
I.5.8.3 Removal Option I-256
I.5.9 Waste Management I-256
I.5.9.1 No Action Option I-256
I.5.9.2 Capping Option I-257
I.5.9.3 Removal Option I-257
I.5.10 Transportation I-258
I.5.10.1 No Action Option I-258
I.5.10.2 Capping Option I-260
I.5.10.3 Removal Option I-263
I.5.11 Environmental Justice I-266
I.5.11.1 No Action Option I-266
I.5.11.2 Capping Option I-266
I.5.11.3 Removal Option I-267
I.5.12 Accidents I-267
I.5.12.1 Risks to Public I-268
I.5.12.2 Risks to Workers I-275
I.5.13 Cumulative Effects I-276

I.6 References I-279

Appendix J
Impacts Analyses of Projects Associated with New Infrastructure or Levels of Operation

J.1 Security-Driven Transportation Modifications Impacts Assessment J-3
J.1.1 Introduction, Purpose, and Need for Agency Action J-3
J.1.2 Options Descriptions J-6
J.1.2.1 No Action Option J-6
J.1.2.2 Proposed Project: Construct Security-Driven Transportation Modifications in the Pajarito Corridor West J-6
J.1.3 Affected Environment and Environmental Consequences J-14
J.1.3.1 No Action Option J-15
J.1.3.2 Proposed Project: Construct Security-Driven Transportation Modifications in the Pajarito Corridor West J-15
J.1.3.3 Auxiliary Action A: Construct a Bridge from Technical Area 35 to Sigma Mesa and a New Road toward Technical Area 3 ..... J-30
J.1.3.4 Auxiliary Action B: Construct a Bridge from Sigma Mesa to Technical Area 61 and a Road to Connect with East Jemez Road J-34

J.2 Metropolis Center Increase in Levels of Operation Impacts Assessment J-38
J.2.1 Introduction, Purpose, and Need for Agency Action J-38
J.2.2 Options Descriptions J-40
J.2.2.1 No Action Option: Continue Metropolis Center Operations Using the Existing Computing Platform J-40
J.2.2.2 Proposed Project: Modify and Operate the Metropolis Center at an Expanded Computing Platform J-40
J.2.3 Affected Environment and Environmental Consequences J-40
J.2.3.1 No Action Option J-41
J.2.3.2 Proposed Project: Modify and Operate the Metropolis Center at an Expanded Computing Platform J-42

J.3 Increase in the Type and Quantity of Sealed Sources Managed at Los Alamos National Laboratory by the Off-Site Source Recovery Project Impacts Assessment J-43
J.3.1 Introduction, Purpose, and Need for Agency Action J-44
J.3.2 Options Descriptions J-47
J.3.2.1 No Action Option J-47
J.3.2.2 Proposed Project: Increase in the Type and Quantity of Sealed Sources Managed at Los Alamos National Laboratory by the Off-Site Source Recovery Project J-48
J.3.3 Affected Environment and Environmental Consequences J-49
J.3.3.1 No Action Option J-50
J.3.3.2 Proposed Project: Increase in the Type and Quantity of Sealed Sources Managed at Los Alamos National Laboratory by the Off-Site Source Recovery Project J-51

J.4 References J-59

Appendix K
Evaluation of Human Health Effects from Transportation

K.1 Introduction K-1

K.2 Scope of Assessment K-1
K.2.1 Transportation-related Activities K-1
K.2.2 Radiological Impacts K-2
K.2.3 Nonradiological Impacts K-2
K.2.4 Transportation Modes K-2
K.2.5 Receptors K-2

K.3 Packaging and Transportation Regulations K-3
K.3.1 Packaging Regulations K-3
K.3.2 Transportation Regulations K-5

K.4 Transportation Analysis Impact Methodology K-6
K.4.1 Transportation Routes K-8
K.4.2 Radioactive Material Shipments K-11

K.5 Incident-Free Transportation Risks K-12
K.5.1 Radiological Risk K-12
K.5.2 Nonradiological Risk K-14
K.5.3 Maximally Exposed Individual Exposure Scenarios K-14

K.6 Transportation Accident Risks and Maximum Reasonably Foreseeable Consequences K-15
K.6.1 Methodology K-15
K.6.2 Accident Rates K-15
K.6.3 Accident Severity Categories and Conditional Probabilities K-16
K.6.4 Atmospheric Conditions K-17
K.6.5 Radioactive Release Characteristics K-18
K.6.6 Acts of Sabotage or Terrorism K-19

K.7 Risk Analysis Results K-19

K.8 Impact of Construction and Hazardous Material Transport K-26

K.9 Conclusions K-27

K.10 Long-Term Impacts of Transportation K-27
K.10.1 Uncertainty and Conservatism in Estimated Impacts K-28
K.10.2 Uncertainties in Material Inventory and Characterization K-29
K.10.3 Uncertainties in Containers, Shipment Capacities, and Number of Shipments K-29
K.10.4 Uncertainties in Route Determination K-30
K.10.5 Uncertainties in the Calculation of Radiation Doses K-30

K.11 References K-31

Appendix L
Categorical Exclusion Summary

Appendix M
Contractor Disclosure Statement

LIST OF FIGURES

Appendix D

Figure D–1 Relative Risk of Wildfire in the Los Alamos Region (1999) D-44
Figure D–2 Relative Risk of Wildfire in the Los Alamos Region (2002) D-44

Appendix E

Figure E–1 Location Map of the Central Pajarito Plateau E-2
Figure E–2 Locations of Major Structural and Geologic Elements in the Vicinity of Los Alamos National Laboratory E-4
Figure E–3 Location Map of the Jemez Mountains and Valles Caldera with Respect to the Jemez Volcanic Lineament, the Colorado Plateau and the Rio Grande Rift E-5
Figure E–4 Pajarito Plateau Stratigraphy and Hydrogeologic Units E-8
Figure E–5 Deep Canyon Exposures E-9
Figure E–6 Outcrop of Totavi Lentil Along SR 304 ..... E-11
Figure E–7 Conceptual Cross-Section Across the Pajarito Plateau Along Los Alamos Canyon E-16
Figure E–8 Conceptual Cross-Section Across the Pajarito Plateau Along Pajarito Canyon E-17
Figure E–9 Average Spatial Distribution (n=6) for Key Analytes in Los Alamos National Laboratory Background Wells and Springs E-24
Figure E–10 Major Liquid Release Sources that have Potentially Affected Groundwater at Los Alamos National Laboratory. Most of these are now inactive. E-28
Figure E–11 Outcrop of Cerros del Rio Basalt at White Rock Overlook (East of Los Alamos National Laboratory) E-30

Appendix F

Figure F–1 Americium-241 Measured Mean Concentration Value in Groundwater F-3
Figure F–2 Cesium-137 Measured Mean Concentration Value in Groundwater F-3
Figure F–3 Plutonium-238 Measured Mean Concentration Value in Groundwater F-4
Figure F–4 Plutonium-239 and Plutonium-240 Measured Mean Concentration Value in Groundwater F-4
Figure F–5 Strontium-90 Measured Mean Concentration Value in Groundwater F-5
Figure F–6 Tritium Measured Mean Concentration Value in Groundwater F-5
Figure F–7 Americium-241 Measured Mean Concentration Value in Sediment F-6
Figure F–8 Cesium-137 Measured Mean Concentration Value in Sediment F-7
Figure F–9 Plutonium-238 Measured Mean Concentration Value in Sediment F-7
Figure F–10 Plutonium-239 and Plutonium-240 Measured Mean Concentration Value in Sediment F-8
Figure F–11 Strontium-90 Measured Mean Concentration Value in Sediment F-8
Figure F–12 Tritium Measured Mean Concentration Value in Sediment F-9
Figure F–13 Americium-241 Measured Mean Concentration Value for Storm Water Runoff F-10
Figure F–14 Cesium-137 Measured Mean Concentration Value for Storm Water Runoff F-10
Figure F–15 Plutonium-238 Measured Mean Concentration Value for Storm Water Runoff F-11
Figure F–16 Plutonium-239 and Plutonium-240 Measured Mean Concentration Value for Storm Water Runoff F-11
Figure F–17 Strontium-90 Measured Mean Concentration Value for Storm Water Runoff F-12
Figure F–18 Tritium Measured Mean Concentration Value for Storm Water Runoff F-12
Figure F–19 Americium-241 Measured Mean Concentration Value for Soils F-13
Figure F–20 Cesium-137 Measured Mean Concentration Value for Soils F-13
Figure F–21 Plutonium-238 Measured Mean Concentration Value for Soils F-14
Figure F–22 Plutonium-239 and Plutonium-240 Measured Mean Concentration Value for Soils F-14
Figure F–23 Tritium Measured Mean Concentration Value for Soils F-15

Appendix G

Figure G–1 Proposed Timeframes for Construction and Operation of Projects to Maintain Existing Los Alamos National Laboratory Operations and Capabilities G-2
Figure G–2 Proposed Location for the Center for Weapons Physics Research G-10
Figure G–3 Replacement Office Building Complex Proposed Layout G-22
Figure G–4 Existing Radioactive Liquid Waste Treatment Facility G-61
Figure G–5 Existing Treatment Processes for Transuranic Waste G-64
Figure G–6 Proposed Project Location G-65
Figure G–7 Proposed Low-Level Radioactive Waste Treatment Process G-67
Figure G–8 Proposed Transuranic Waste Treatment Process G-68
Figure G–9 Proposed Layout under the Two Liquid Waste Treatment Buildings Option G-69
Figure G–10 Location of Los Alamos Neutron Science Center at Technical Area 53 ..... G-92
Figure G–11 Location of Building 55-41 Relative to Building 55-4 at Technical Area 55 ..... G-99
Figure G–12 Conceptual Layout of the Science Complex at the Northwest Technical Area 62 Site G-126
Figure G–13 Technical Area 72 Remote Warehouse and Truck Inspection Station Conceptual Layout G-146

Appendix H

Figure H–1 Proposed Timeframes for Construction and Operation of Closure and Remediation Actions H-1
Figure H–2 Technical Area 18 Pajarito Site H-7
Figure H–3 Technical Area 21 Map of DP West Buildings and Solid Waste Management Units H-23
Figure H–4 Technical Area 21 Map of DP East Buildings and Solid Waste Management Units H-24
Figure H–5 Aerial Photograph of the DP East and DP West Sites, Looking West (1995) H-25
Figure H–6 Land Transfer H-28

Appendix I

Figure I–1 Los Alamos National Laboratory Technical Area Locations I-8
Figure I–2 Technical Area 15 Firing Sites and Other Facilities I-14
Figure I–3 Material Disposal Area F I-18
Figure I–4 Material Disposal Area A I-23
Figure I–5 General's Tanks within Material Disposal Area A I-24
Figure I–6 Material Disposal Area B Base Map Showing Estimated Disposal Trench Locations I-27
Figure I–7 Material Disposal Area B Base Map Showing Estimated Disposal Trench Locations I-29
Figure I–8 Material Disposal Area T I-31
Figure I–9 Absorption Bed and Distribution Pipe Cross-Section I-32
Figure I–10 Location of Lines Discharging to Absorption Beds at Material Disposal Area T Before 1952 ..... I-33
Figure I–11 Material Disposal Area U Showing Pipelines for Liquid Effluents I-39
Figure I–12 Technical Area 49 Shaft Areas and Other Solid Waste Management Units I-42
Figure I–13 Material Disposal Area C Within Technical Area 50 ..... I-50
Figure I–14 Material Disposal Area Locations of Technical Area-54 ..... I-56
Figure I–15 Waste Management Areas within Area G of Technical Area-54 ..... I-58
Figure I–16 Material Disposal Area L Inactive Waste Unit Locations I-65
Figure I–17 Material Disposal Area L Operational Waste Management Units I-69
Figure I–18 260 Outfall Within Technical Area-16 ..... I-74
Figure I–19 Closeup View of Conceptual Site Changes to Facilitate Complete Excavation and Removal Corrective Measure Option I-109
Figure I–20 Example of a Remotely Operated Dismantling System and Inspection Station I-110
Figure I–21 Conceptual Geologic Model of Operable Unit 1114 ..... I-137
Figure I–22 Aerial Illustrations of Borrow Pit I-138
Figure I–23 View to the East from within the Technical Area 61 Borrow Pit I-138
Figure I–24 Material Disposal Area B Investigative Sections I-162
Figure I–25 Major Transportation Routes within Los Alamos National Laboratory I-217
Figure I–26 Major Transportation Routes Outside of Los Alamos National Laboratory I-218

Appendix J

Figure J–1 Proposed Timeframes for Construction and Operation of Projects to Add New Infrastructure or Increase Levels of Operation J-1
Figure J–2 Proposed Pajarito Corridor West Security-Driven Transportation Plan J-4
Figure J–3 Proposed Technical Area 48 Security-Driven Transportation Modifications J-8
Figure J–4 Proposed Technical Area 35 and Technical Area 63 Security-Driven Transportation Modifications J-10
Figure J–5 Photograph of Canyon to be Bridged between Technical Area 35 and Technical Area 63 ..... J-11
Figure J–6 General Locations of the Auxiliary Action Bridges and Roadways to Technical Area 60 and Technical Area 61 ..... J-13
Figure J–7 Photograph Looking North Across Mortandad Canyon in the Area of the Bridge for Proposed Auxiliary Action A J-14

Appendix K

Figure K–1 Transportation Risk Assessment K-7
Figure K–2 Analyzed Truck Routes K-10

LIST OF TABLES

Appendix B

Table B–1 Criteria Pollutant Standards B-2
Table B–2 Criteria Pollutant Emissions Summary B-7

Appendix C

Table C–1 Exposure Limits for Members of the Public and Radiation Workers C-6
Table C–2 Nominal Health Risk Estimators Associated with Exposure to 1 Rem of Ionizing Radiation C-8
Table C–3 Los Alamos National Laboratory Key Facilities C-12
Table C–4 Radiological Air Emissions from Technical Area 3-29 (Chemistry and Metallurgy Research Building) C-15
Table C–5 Radiological Air Emissions from Technical Area 3-66 (Sigma Complex) C-15
Table C–6 Radiological Air Emissions from Technical Area 3-102 (Machine Shops) C-15
Table C–7 Radiological Air Emissions from Technical Area 11 (High Explosives Processing) C-16
Table C–8 Radiological Air Emissions from Technical Area 15 and Technical Area 36 (High Explosives Testing) C-16
Table C–9 Radiological Air Emissions from Technical Area 16 (Tritium Facility) C-16
Table C–10 Radiological Air Emissions from Technical Area 18 (Pajarito Site) C-17
Table C–11 Radiological Air Emissions from Technical Area 48 (Radiochemistry Facility) C-17
Table C–12 Radiological Air Emissions from Technical Area 53 (Los Alamos Neutron Science Center) C-18
Table C–13 Radiological Air Emissions from Technical Area 54 (Waste Management Operations) C-19
Table C–14 Radiological Air Emissions from Technical Area 55 (Plutonium Facility Complex) C-19
Table C–15 Radiological Air Emissions from Non-Key Facilities (Technical Area 21) C-20
Table C–16 Summary of Facility-Specific Maximally Exposed Individual Dose C-22
Table C–17 Maximally Exposed Individual Dose for the No Action Alternative C-23
Table C–18 Maximally Exposed Individual Dose for the Reduced Operations Alternative C-24
Table C–19 Maximally Exposed Individual Dose for the Expanded Operations Alternative C-25
Table C–20 Collective Population Dose Summary C-26
Table C–21 Ingestion Exposure Pathway Components Evaluated for Offsite Resident, Recreational User, and Special Pathways Receptors C-29
Table C–22 Dose from the Consumption of Produce C-30
Table C–23 Dose from the Consumption of Free Range Beef C-30
Table C–24 Dose from the Consumption of Milk C-31
Table C–25 Dose from the Consumption of Fish C-31
Table C–26 Dose from the Consumption of Elk C-32
Table C–27 Dose from the Consumption of Deer C-32
Table C–28 Dose from the Consumption of Honey C-33
Table C–29 Dose from the Consumption of Piñon Nuts C-33
Table C–30 Dose from the Consumption of Groundwater C-34
Table C–31 Dose from the Consumption of Soil C-34
Table C–32 Dose from the Consumption of Sediment C-35
Table C–33 Dose to the Recreational User Receptor from the Consumption of Surface Water C-35
Table C–34 Dose to the Recreational User Receptor from the Consumption of Soil C-36
Table C–35 Dose to the Recreational User Receptor from the Consumption of Sediment C-36
Table C–36 Dose to the Special Pathways Receptor from the Consumption of Fish C-37
Table C–37 Dose to the Special Pathways Receptor from the Consumption of Elk Heart and Liver C-37
Table C–38 Dose to the Special Pathways Receptor from the Consumption of Indian Tea (Cota) C-38
Table C–39 Summary of Ingestion Pathway Doses for Offsite Resident, Recreational User, and Special Pathways Receptors C-38
Table C–40 Hazard Index and Cancer Risk to the Offsite Resident Receptor from the Ingestion of Nonradioactive Contaminants in Groundwater C-44

Table C–41 Hazard Index and Cancer Risk to the Recreational User Receptor from the Ingestion of Nonradioactive Contaminants in Surface Water C-48
Table C–42 Hazard Index and Cancer Risk to the Recreational User Receptor from the Ingestion of Nonradioactive Contaminants in Sediment C-49
Table C–43 Hazard Index and Cancer Risk to the Offsite Resident Receptor from the Ingestion of Nonradioactive Contaminants in Sediment C-51
Table C–44 Hazard Index and Cancer Risk to the Offsite Resident Receptor from the Ingestion of Nonradioactive Contaminants in Soil C-52
Table C–45 Hazard Index and Cancer Risk to the Recreational User Receptor from the Ingestion of Nonradioactive Contaminants in Soil C-52
Table C–46 Hazard Index and Cancer Risk to the Offsite Resident Receptor from the Ingestion of Nonradioactive Contaminants in Produce C-55
Table C–47 Hazard Index and Cancer Risk to the Offsite Resident Receptor from the Ingestion of Nonradioactive Contaminants in Fish C-55
Table C–48 Hazard Index and Cancer Risk to the Special Pathways Receptor from the Ingestion of Nonradioactive Contaminants in Fish C-56
Table C–49 Containment Design Practices and Levels of Biological Agents for Each Biosafety Level Facility C-61

Appendix D

Table D–1 Evaluation of Accident Data from the *1999 SWEIS* D-3
Table D–2 General Analysis Assumptions Independent of Scenario D-6
Table D–3 Facility Accident Source Term Data D-11
Table D–4 Radiological Accident Offsite Population Consequences for the No Action Alternative D-17
Table D–5 Radiological Accident Onsite Worker Consequences for the No Action Alternative D-18
Table D–6 Radiological Accident Offsite Population and Worker Risks for the No Action Alternative D-19
Table D–7 Radiological Accident Offsite Population Consequences for the Expanded Operations Alternative D-20
Table D–8 Radiological Accident Onsite Worker Consequences for the Expanded Operations Alternative D-21
Table D–9 Radiological Accident Offsite Population and Worker Risks for the Expanded Operations Alternative D-22
Table D–10 Chemical Accident Impacts D-24
Table D–11 Chemical Accident Impacts for the Expanded Operations Alternative D-26
Table D–12 Site-wide Earthquake Source Term Data D-28
Table D–13 Site-wide Seismic 1 Radiological Accident Offsite Population Consequences for the No Action Alternative D-31
Table D–14 Site-wide Seismic 1 Radiological Accident Onsite Worker Consequences for the No Action Alternative D-31
Table D–15 Site-wide Seismic 1 Radiological Accident Offsite Population and Worker Risks for the No Action Alternative D-32
Table D–16 Site-wide Seismic 2 Radiological Accident Offsite Population Consequences for the No Action Alternative D-33
Table D–17 Site-wide Seismic 2 Radiological Accident Onsite Worker Consequences for the No Action Alternative D-34
Table D–18 Site-wide Seismic 2 Radiological Accident Offsite Population and Worker Risks for the No Action Alternative D-35
Table D–19 Chemical Accident Impacts Under Seismic 1 Conditions D-35
Table D–20 Chemical Accident Impacts Under Seismic 2 Conditions D-36
Table D–21 Evaluation of Vulnerability of Los Alamos National Laboratory Buildings to Wildfire D-55
Table D–22 Wildfire Accident Source Term Data D-58
Table D–23 Radiological Accident Offsite Population Consequences for a Wildfire Accident D-60
Table D–24 Radiological Accident Onsite Worker Consequences for a Wildfire Accident D-60
Table D–25 Radiological Accident Offsite Population and Worker Risks for a Wildfire Accident D-61
Table D–26 Chemical Accident Impacts under Wildfire Conditions D-62
Table D–27 Maximally Exposed Individual-Type Doses versus Downwind Distance by Accident Scenario D-69

Appendix E

Table E–1 Summary of Jemez Mountain Volcanic Field Names, Rock Types, and Rock Ages E-7

Appendix F

Table F–1 Groundwater Data Set Comparison F-2
Table F–2 Sediment Data Set Comparison F-6
Table F–3 Storm Water Data Set Comparison F-9
Table F–4 Comparison of Measured 2001 through 2004 Radioisotope Groundwater Data to 1991 through 1996 Data.....F-16
Table F–5 Comparison of Measured 2001 through 2004 Radioisotope Sediment Data to 1991 through 1996 Data.....F-16
Table F–6 Comparison of Measured 2001 through 2004 Radioisotope Storm Water Runoff or Surface Water Data to 1991 through 1996 Data F-17
Table F–7 Comparison of Measured 2001 through 2004 Radioisotope Soil Data to 1991 through 1996 Data.....F-18
Table F–8 Key Parameters of Radioisotopes Measured at the Los Alamos National Laboratory Environment.....F-18
Table F–9 Number of Detectable Radiological Data Samples at Los Alamos National Laboratory F-21
Table F–10 Radiochemical Statistical Analysis of Groundwater – Canyon Alluvial Groundwater Systems F-21
Table F–11 Radiochemical Statistical Analysis of Groundwater – Pueblo/Los Alamos/Sandia Canyon Area Perched System In Conglomerates and Basalt F-24
Table F–12 Radiochemical Statistical Analysis of Groundwater – Regional Aquifer Springs F-25
Table F–13 Radiochemical Statistical Analysis of Groundwater – Test Wells.....F-28
Table F–14 Radiochemical Statistical Analysis of Groundwater – Other Springs.....F-30
Table F–15 Radiochemical Statistical Analysis of Groundwater – Perched Groundwater System in Volcanics F-32
Table F–16 Radiochemical Statistical Analysis of Groundwater – Intermediate Perched Groundwater Systems Pueblo/Los Alamos/Sandia Canyon Area Perched Systems in Conglomerates and Basalt F-33
Table F–17 Radiochemical Statistical Analysis of Groundwater – Regional Aquifer Wells Hydrogeologic Characterization Wells.....F-34
Table F–18 Radiochemical Statistical Analysis of Groundwater – Water Supply Wells.....F-37
Table F–19 Radiochemical Statistical Analysis of Groundwater – Santa Fe Water Supply Wells.....F-40
Table F–20 Radiochemical Statistical Analysis of Sediment from 2001 through 2004.....F-41
Table F–21 Radiochemical Statistical Analysis of Surface Water or Storm Water Runoff.....F-49
Table F–22 Radiochemical Statistical Analysis of Soil Composite from 2001 through 2003 .....F-55
Table F–23 Benchmark Concentrations for Analyzed Radionuclides for Groundwater, Surface Water or Storm Water Runoff.....F-56
Table F–24 Perchlorate Statistical Analysis of Groundwater from 2002 through 2004.....F-57

Appendix G

Table G–1 Estimated Waste Volumes from Center for Weapons Physics Research Decontamination, Decommissioning, and Demolition Activities G-18
Table G–2 Incident-Free Transportation Impacts – Center for Weapons Physics Research G-19
Table G–3 Transportation Accident Impacts – Center for Weapons Physics Research G-20
Table G–4 Summary of Los Alamos National Laboratory Radiological Buildings Proposed for Decontamination, Decommissioning, and Demolition Radiological Sciences Institute Project.....G-31
Table G–5 Name, Function, and Number of Employees of Permanent Buildings Proposed for Decontamination, Decommissioning, and Demolition by the Radiological Sciences Institute Project G-32
Table G–6 Annual Radiological Impacts on the Public from Operations under the Radiological Sciences Institute Project No Action Option G-36
Table G–7 Bounding Radiological Accident Scenarios under the Radiological Sciences Institute Project No Action Option.....G-38

Table G–8 Radiological Accident Offsite Population Consequences under the Radiological Sciences Institute Project No Action Option G-38
Table G–9 Radiological Incident Onsite Worker Consequences under the Radiological Sciences Institute Project No Action Option G-39
Table G–10 Radiological Accident Offsite Population and Worker Risks under the Radiological Sciences Institute Project No Action Option G-39
Table G–11 Nonradiological Air Pollutant Emissions at Technical Area 48 – 2002 ..... G-44
Table G–12 Nonradiological Air Pollutant Emissions at Technical Area 3 Machine Shops and Technical Area 18 – 2002 ..... G-44
Table G–13 Radiological Air Emissions from the Radiological Sciences Institute G-46
Table G–14 Annual Radiological Impacts on the Public from Radiological Sciences Institute Operations G-50
Table G–15 Affected Cultural Resource Sites – Radiological Sciences Institute G-52
Table G–16 Waste Generation for the Radiochemistry Facility, Pajarito Site, Sigma Complex, and Machine Shops at Technical Area 3 (1998 to 2003) G-55
Table G–17 Decontamination, Decommissioning, and Demolition of Waste Volumes for Buildings to be Replaced by the Radiological Sciences Institute G-56
Table G–18 Incident-Free Transportation Impacts – Radiological Sciences Institute G-57
Table G–19 Transportation Accident Impacts – Radiological Sciences Institute G-57
Table G–20 Bounding Radiological Accident Scenarios – Radiological Sciences Institute G-58
Table G–21 Radiological Accident Offsite Consequences – Radiological Sciences Institute G-59
Table G–22 Radiological Accident Onsite Worker Consequences – Radiological Sciences Institute G-59
Table G–23 Radiological Accident Offsite Population and Worker Risks – Radiological Sciences Institute G-60
Table G–24 Design Basis Influent Volumes – Radioactive Liquid Waste Treatment Facility Upgrade G-62
Table G–25 Incident-Free Transportation – for Single Liquid Waste Treatment Building Option Impacts G-80
Table G–26 Transportation Accident Impacts – for Single Liquid Waste Treatment Building Option G-81
Table G–27 Decontamination, Decommissioning, and Demolition Contaminated Construction Waste Volumes – Two Liquid Waste Treatment Buildings Option G-84
Table G–28 Incident-Free Transportation Impacts – Two Liquid Waste Treatment Buildings Option G-85
Table G–29 Transportation Incident Impacts – Two Liquid Waste Treatment Building Option G-85
Table G–30 Decontamination, Decommissioning, and Demolition Contaminated Construction Waste Volumes – Two Liquid Waste Treatment Buildings and Renovation Option G-87
Table G–31 Incident-Free Transportation Impacts – Two Liquid Waste Treatment Buildings and Renovation Option G-88
Table G–32 Transportation Incident Impacts – Two Liquid Waste Treatment Building and Renovation Option G-88
Table G–33 Waste Generation from Existing Los Alamos Neutron Science Center Operations at Technical Area 53 ..... G-96
Table G–34 Toxic and Hazardous Pollutant Air Emissions from Existing Operations at Technical Area 55 ..... G-119
Table G–35 Waste Generation from Existing Operations at Technical Area 55 ..... G-121
Table G–36 Total Waste Generation from Implementation of the Plutonium Facility Complex Refurbishment Project at Technical Area 55 ..... G-122
Table G–37 Incident-Free Transportation Impacts – Plutonium Facility Complex Refurbishment G-123
Table G–38 Transportation Incident Impacts – Plutonium Facility Complex Refurbishment G-124

Appendix H

Table H–1 Estimated Waste Volumes H-20
Table H–2 Incident-Free Transportation Impacts – Technical Area 18 Decontamination, Decommissioning, and Demolition H-21
Table H–3 Transportation Accident Impacts – Technical Area 18 Decontamination, Decommissioning, and Demolition H-22
Table H–4 Technical Area 21 Buildings to Undergo Decontamination, Decommissioning, and Demolition for the Compliance Support Option H-33
Table H–5 Volume of Technical Area 21 National Pollutant Discharge Elimination System Outfalls H-37
Table H–6 Calculated Actual Emissions for Regulated Pollutants Reported to the New Mexico Environment Department for 2004 ..... H-39
Table H–7 Technical Area 21 Radiological Point Source Emissions H-40

Table H–8 Technical Area 21 Ambient Air Monitoring H-41
Table H–9 Maximally Exposed Individual Average Radiological Doses from Technical Area 21 Point Source Emissions H-44
Table H–10 Radiological Doses (above background) Measured at Technical Area 21 and the East Gate Locations, Based on Ambient Air Monitoring H-44
Table H–11 Waste Generation Ranges and Annual Average Generation Rates from Technical Area 21 Facilities H-51
Table H–12 Waste Generation under the Proposed Action and Compliance Response Alternatives H-52
Table H–13 Incident-Free Transportation Impacts – Technical Area 21 Decontamination, Decommissioning, and Demolition H-54
Table H–14 Transportation Accident Impacts – Technical Area 21 Decontamination, Decommissioning, and Demolition H-55
Table H–15 Area L Container Storage Units and Associated Storage Volumes H-72
Table H–16 Nonradiological Air Pollutant Emissions at Solid Radioactive and Chemical Waste Management Key Facility – 2004 ..... H-82
Table H–17 Radiological Air Emissions from Each Waste Management Facility H-83
Table H–18 Potential Radiation Dose from Current Technical Area 54 Operations H-87
Table H–19 Waste Generation Ranges and Annual Average Generation Rates for the Solid Radioactive and Chemical Waste Facilities H-91
Table H–20 Estimated Waste Volumes from Decontamination, Decommissioning and Demolition Activities H-92
Table H–21 2004 Traffic Counts Along Pajarito Road Immediately East of Technical Area 63 ..... H-93
Table H–22 Incident-Free Transportation Impacts – Waste Management Facility Transition Decontamination, Decommissioning and Demolition Activities H-94
Table H–23 Transportation Accident Impacts – Waste Management Facility Transition Decontamination, Decommissioning and Demolition Activities H-94
Table H–24 Alternative Site Seismic Source Terms H-97
Table H–25 Alternative Site Seismic Radiological Accident Consequences H-101
Table H–26 Alternative Site Seismic Radiological Accident Onsite Worker Consequences H-101
Table H–27 Alternative Site Radiological Accident Offsite Population and Worker Risks H-102

Appendix I

Table I–1 Large Material Disposal Areas Considered in This Project-Specific Analysis I-4
Table I–2 Updated Corrective Measure Report Schedules for Large Material Disposal Areas I-4
Table I–3 Additional Material Disposal Areas Considered in This Project-Specific Analysis I-5
Table I–4 Examples of Potential Release Sites Being Addressed Under the Consent Order I-5
Table I–5 Non-Deferred Sites Within Testing Hazard Zones I-12
Table I–6 Deferred Sites in Testing Hazard Zones I-13
Table I–7 Material Disposal Area T Waste Disposal Shaft Depths and Diameters I-34
Table I–8 Plutonium-239 Disposed of in Material Disposal Area T Shaft Bathyspheres I-36
Table I–9 Radionuclide Inventories and Cement Paste Volume by Shaft I-36
Table I–10 Material Disposal Area AB Principal Radionuclides Inventories I-46
Table I–11 Material Disposal Area AB Test and Support Shaft Depths I-48
Table I–12 Approximate Dimensions of Material Disposal Area C Disposal Units I-51
Table I–13 Los Alamos Scientific Laboratory Logbook Citations of Wastes Placed in Pits and Shafts I-53
Table I–14 Material Disposal Area C Estimated Radionuclide Inventories as of January 1989 ..... I-54
Table I–15 Material Disposal Area G Pits I-59
Table I–16 Material Disposal Area G Trench Information I-61
Table I–17 Material Disposal Area G Summary Shaft Information I-61
Table I–18 Material Disposal Area G Solid Waste Management Unit Groupings I-61
Table I–19 Material Disposal Area G Hazardous Chemical Inventories I-63
Table I–20 Material Disposal Area L Pit and Impoundment Dimensions and Operation Dates I-66
Table I–21 Material Disposal Area L Shaft Dimensions and Operation Dates I-66
Table I–22 Aggregate Areas and Watersheds I-71
Table I–23 Solid Waste Management Units Requiring Continuing Investigation I-71

Table I–24 Potential Release Sites Considered in the Middle Mortandad–Ten Site Aggregate Sampling and Analysis Plan I-77
Table I–25 Projections of Environmental Restoration Project Wastes from Fiscal Year 2006 through Fiscal Year 2012 ..... I-86
Table I–26 Waste Types Considered I-87
Table I–27 Hazard Categories and Descriptions of Nuclear Environmental Sites I-91
Table I–28 Possible Technologies for Containment and in Situ Treatment I-94
Table I–29 Typical Removal Activities I-100
Table I–30 Equipment Commonly Used for Standard Removals I-101
Table I–31 Examples of Specialized Excavators and Other Equipment I-101
Table I–32 Example Contamination Control Options I-102
Table I–33 Hazardous Waste Operations Near Los Alamos National Laboratory I-105
Table I–34 Belowground Storage and Disposal Units at Area G I-115
Table I–35 Closure Phases for Area G I-116
Table I–36 Inadvertent Future Intruder Impact Summary I-119
Table I–37 Maximum Lifetime Maximally Exposed Individual and Population Impacts after Assumed Loss of Institutional Control I-119
Table I–38 Estimated Cover Materials for Material Disposal Area G I-120
Table I–39 Summary of Waste Management Units at Area L I-121
Table I–40 Bulk Materials for Material Disposal Area L Final Cover I-122
Table I–41 Solid Waste Generation during Capping of Large Material Disposal Areas I-124
Table I–42 Asphalt or Concrete Removal from Material Disposal Areas I-125
Table I–43 Bulk Materials for Material Disposal Area C Final Cover I-125
Table I–44 Summary of Material Disposal Area C Retaining Wall Quantities I-126
Table I–45 Cover Materials for Selected Material Disposal Areas I-127
Table I–46 One-Way Shipments for Delivery of Cover Materials for Selected Material Disposal Areas I-127
Table I–47 Cover Assumptions for Remaining Material Disposal Areas I-128
Table I–48 One-Way Shipments of Cover Materials for Remaining Material Disposal Areas I-128
Table I–49 Waste Generation through Fiscal Year 2016 from Capping Additional Material Disposal Areas I-129
Table I–50 Cover Assumptions for Technical Area 49 Contaminated Areas I-129
Table I–51 One-Way Shipments for Technical Area 49 Contaminated Areas I-129
Table I–52 Temporal Assumptions for Capping Large Material Disposal Areas I-135
Table I–53 Volumes of Transuranic-Contaminated Materials Estimated to Be within Los Alamos National Laboratory Material Disposal Areas I-143
Table I–54 Waste Volumes and Shipments for Removal of Material Disposal Areas A, B, C, G, L, T, U, and AB I-144
Table I–55 Volumes and Shipments of Bulk Materials for Removal of Material Disposal Areas A, B, C, G, L, T, U, and AB I-145
Table I–56 Liquid Waste Volumes and Shipments from Large-Material-Disposal-Area Exhumation I-145
Table I–57 Waste Projections for Removing Remaining Material Disposal Areas I-157
Table I–58 One-Way Shipments from Exhuming Remaining Material Disposal Areas I-158
Table I–59 Soil and Similar Materials for Removal of Remaining Material Disposal Areas I-158
Table I–60 One-Way Shipments of Soil and Similar Materials for Removal of Remaining Material Disposal Areas I-159
Table I–61 Temporal Assumptions for Removing Large Material Disposal Areas I-160
Table I–62 Estimated Waste Volume by Section at Material Disposal Area B I-161
Table I–63 Treatment Group Examples I-169
Table I–64 Alternative Corrective Measures for the 260 Outfall I-170
Table I–65 Annual Waste Generation from Remediating Additional Potential Release Sites I-171
Table I–66 Container and Shipment Assumptions I-173
Table I–67 Transportation Dose and Risk Assessment Results I-175
Table I–68 Annual Waste Generation Rates for No Action Option I-175
Table I–69 Capping Option Annual Waste Generation Rates I-177
Table I–70 Removal Option Annual Waste Generation Rates I-178
Table I–71 No Action Option Annual Waste Shipments I-179

Table I–72 Capping Option Annual Waste Shipments I-180
Table I–73 Removal Option Annual Waste Shipments I-181
Table I–74 Materials and Shipments for Capping All Material Disposal Areas I-182
Table I–75 Materials and Shipments for Removing All Material Disposal Areas I-183
Table I–76 Summary of Labor, Equipment Hours, and Fuel Use for Remediation Case Studies I-185
Table I–77 Remediation Case Study Total Equipment and Fuel Use and Pollutant Emissions I-186
Table I–78 Remediation Case Study Total Industrial Risks I-187
Table I–79 Case Studies Applied to Material Disposal Area Removal I-190
Table I–80 Approximate Sizes of Material Disposal Areas and Selected Potential Release Sites I-194
Table I–81 Watersheds and Depth to Regional Water by Material Disposal Area I-202
Table I–82 Comparative Summaries for Los Alamos National Laboratory Meteorological Stations with Nearby Material Disposal Areas I-204
Table I–83 Summary of Material Disposal Area and Potential Release Sites Vegetation Zones I-205
Table I–84 Principal Access Routes to Material Disposal Areas and Selected Solid Waste Management Units I-216
Table I–85 Material Disposal Area G Performance Assessment and Composite Analysis Summary Results I-228
Table I–86 No Action Option Projected Pollutant Releases to Air from Heavy Machinery Operation I-235
Table I–87 Capping Option Projected Pollutant Releases to Air from Heavy Machinery Operation I-236
Table I–88 Projected Pollutant Releases to Air from Heavy Machinery Operation from Capping Material Disposal Area G and Combined Material Disposal Areas A, B, T, and U I-237
Table I–89 Capping Option Projected Pollutant Releases to Air from Technical Area 61 Borrow Pit Heavy-Machinery Operation I-238
Table I–90 Removal Option Projected Pollutant Releases to Air from Heavy-Machinery Operation I-241
Table I–91 Projected Pollutant Releases to Air from Heavy-Machinery Operation from Removal of Material Disposal Areas G and Material Disposal Areas A, B, T, and U I-241
Table I–92 Removal Option Projected Pollutant Releases to Air from Technical Area 61 Borrow Pit Heavy-Machinery Operation I-242
Table I–93 Screened Inventories of Radionuclides Within Large Material Disposal Areas and the Combined Potential Release Site Area I-250
Table I–94 Annual Dose Estimates from Complete Removal of Large Material Disposal Areas I-253
Table I–95 No Action Option Transportation Impacts Summary I-259
Table I–96 No Action Option Comparison of On- and Offsite Radioactive Waste Disposal Transportation Impacts (Fiscal Year 2007 through Fiscal Year 2016) I-260
Table I–97 Capping Option Shipments of Waste and Bulk Materials into and out of Technical Area 21 ..... I-261
Table I–98 Capping Option Transportation Impacts Summary I-262
Table I–99 Capping Option Comparison of On- and Offsite Radioactive Waste Disposal Transportation Impacts (Fiscal Year 2007 through Fiscal Year 2016) I-263
Table I–100 Removal Option Shipments of Waste and Bulk Materials into and out of Technical Area 21 ..... I-264
Table I–101 Removal Option Transportation Impacts Summary I-265
Table I–102 Removal Option Comparison of On- and Offsite Radioactive Waste Disposal Transportation Impacts (Fiscal Year 2007 through Fiscal Year 2016) I-266
Table I–103 Analytical Parameters for Assumed Accidents at Material Disposal Area G and Material Disposal Area B I-271
Table I–104 Material Disposal Area Explosion or Fire: Radiological Accident Consequences I-273
Table I–105 Material Disposal Area Explosion or Fire: Radiological Accident Risks I-273
Table I–106 Material Disposal Area B Waste Retrieval Chemical Accident Consequences I-275
Table I–107 Industrial Accident Risks for Project-Specific Analysis Options I-276
Table I–108 Industrial Accident Risks for Technical Area 61 Borrow Pit Operations I-277
Table I–109 Industrial Accident Risks for Removal of Material Disposal Area G and Combined Material Disposal Areas A, B, T, and U I-277

Appendix J

Table J–1 Land Use Designations and Development Areas for Technical Areas that Comprise the Pajarito Corridor West J-16
Table J–2 2004 Traffic Counts Along Pajarito Road at Technical Area 48 and Technical Area 64 ..... J-29
Table J–3 2004 Traffic Counts Along Pajarito Road Immediately East of Technical Area 63 ..... J-29
Table J–4 Metropolis Center Operating Requirements J-41
Table J–5 Projected Annual Volumes of Waste with No Disposal Path for Duration of the Off-Site Source Recovery Project J-48
Table J–6 Additional Sources Registered with the Off-Site Source Recovery Project – Newly Eligible Materials J-48
Table J–7 Anticipated Volume of Greater-Than-Class C Actinide Waste with No Disposal Path over the Life of the Project J-51
Table J–8 Currently Stored Material with No Disposal Path J-51
Table J–9 Maximum Allowable Sealed Source Radioisotope Inventory at Technical Area 54 Area G J-53
Table J–10 Maximum Allowable Sealed Source Radioisotope Inventory at Chemistry and Metallurgy Research Building Wing 9 ..... J-53
Table J–11 Sealed Source Aircraft Impact Crash Accident at Technical Area 54 Area G Dome Airborne Release Source Term for MACCS2 Calculation J-54
Table J–12 Sealed Source Aircraft Impact Crash Accident at Technical Area 54 Area G Dome Air Release and Direct Radiation Source Terms J-54
Table J–13 Dose and Risk Consequences of Sealed Source Aircraft Impact Crash Accident at Technical Area 54 Area G Dome J-55
Table J–14 Sealed Source Severe Earthquake and Fire Accident at Chemistry and Metallurgy Research Building Wing 9 Air Release and Direct Radiation Source Terms J-56
Table J–15 Sealed Source Severe Earthquake Collapse and Fire Accident at Chemistry and Metallurgy Research Building Wing 9 Dose and Risk Consequences at Technical Area 3 Location J-56
Table J–16 Sealed Source Severe Earthquake Collapse and Fire Accident Dose and Risk Consequences at Technical Area 48 Location J-56
Table J–17 Total Accident Doses and Risks From Sealed Sources at Technical Area 3, Technical Area 48, and Technical Area 54 ..... J-57

Appendix K

Table K–1 Offsite Transport Truck Route Characteristics K-9
Table K–2 Radioactive Material Type and Container Characteristics K-11
Table K–3 Risk Factors per Truck Shipment of Radioactive Material K-20
Table K–4 Risk Factors per Truck-Shipment of Radioactive Material at Nearby Routes K-21
Table K–5 Estimates of the Number of Radioactive Shipments Under Each Alternative K-23
Table K–6 Risks of Transporting Radioactive Materials Under Each Alternative K-24
Table K–7 Estimated Dose to Maximally Exposed Individuals During Incident-Free Transportation Conditions K-25
Table K–8 Estimated Dose to the Population and to Maximally Exposed Individuals during Most Severe Accident Conditions K-26
Table K–9 Estimated Impacts of Construction and Operational Material Transport K-27
Table K–10 Cumulative Transportation-related Radiological Collective Doses and Latent Cancer Fatalities (1943 to 2047) K-28

ACRONYMS, ABBREVIATIONS, AND CONVERSION CHARTS

ACRONYMS, ABBREVIATIONS, AND CONVERSION CHARTS

ALARA	as low as reasonably achievable
AOC	area of concern
BEIR	Biological Effects of Ionizing Radiation
CAP-88	Clean Air Act Assessment Package, 1988
CASA	Critical Assembly Storage Area
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	*Code of Federal Regulations*
CME	corrective measure evaluation
CMR	Chemistry and Metallurgy Research (Building)
CMRR	Chemistry and Metallurgy Research Building Replacement Project
CSU	container storage unit
DARHT	Dual Axis Radiographic Hydrodynamic Test (Facility)
dB	decibel
dBA	decibel A-weighted
D&D	decontamination and decommissioning
DD&D	decontamination, decommissioning, and demolition
DOE	U.S. Department of Energy
DOT	U.S. Department of Transportation
DVRS	Decontamination and Volume Reduction System
EIS	environmental impact statement
EPA	U.S. Environmental Protection Agency
ERPG	Emergency Response Planning Guidelines
FONSI	Finding of No Significant Impact
FR	*Federal Register*
FY	fiscal year
GIS	geographical information system
HDPE	high-density polyethylene
HEPA	high-efficiency particulate air (filter)
HSWA	Hazardous and Solid Waste Amendments
HTO	tritiated water
ISCORS	Interagency Steering Committee on Radiation Standards
ISCST3	Industrial Source Complex Air Quality Dispersion Model
LANL	Los Alamos National Laboratory
LANL SWEIS	*Site-Wide Environmental Impact Statement for the Continued Operation of the Los Alamos National Laboratory, Los Alamos, New Mexico*
LANSCE	Los Alamos Neutron Science Center
LASL	Los Alamos Scientific Laboratory (now LANL)
LCF	latent cancer fatality
LEED	Leadership in Energy and Environmental Design

LLW	low-level radioactive waste
LOC	level-of-concern
MAR	material at risk
MDA	material disposal area
MEI	maximally exposed individual
NEPA	National Environmental Policy Act of 1969
NESHAP	National Emission Standards for Hazardous Air Pollutants
NMAC	New Mexico Administrative Code
NMED	New Mexico Environment Department
NNSA	National Nuclear Security Administration
NOEL	No Observed Effect Level
NPDES	National Pollutant Discharge Elimination System
NRC	U.S. Nuclear Regulatory Commission
NTS	Nevada Test Site
PC	performance category
PCB	polychlorinated biphenyl
PEL	permissible exposure limit
PHERMEX	Pulsed High Energy Radiographic Machine Emitting X Rays
PM_n	particulate matter less than or equal to *n* microns in aerodynamic diameter
PRS	potential release site
PSVE	passive soil vapor extraction
RCRA	Resource Conservation and Recovery Act
rad	radiation absorbed dose
RANT	Radioactive Assay and Nondestructive Test
rem	roentgen equivalent man
RFI	RCRA facility investigation
RLWTF	Radioactive Liquid Waste Treatment Facility
ROD	Record of Decision
SA	supplement analysis
SAL	Screening Action Level
SHEBA	Solution High-Energy Burst Assembly
SLEV/Q	screening level emission value by the estimated emission rate
SNM	special nuclear material
SST	safe secure transport
SVE	soil vapor extraction
SWEIS	Site-Wide Environmental Impact Statement
SWMU	solid waste management unit
TA	technical area
TEDE	total effective dose equivalent
TEELs	Temporary Emergency Exposure Limits
teraops	a trillion floating point operations per second

TRAGIS	Transportation Routing Analysis Geographic Information System
TSFF	Tritium Science and Fabrication Facility
TSCA	Toxic Substances Control Act
TSTA	Tritium Systems Test Assembly
TWCF	Transuranic Waste Consolidation Facility
UCL	upper confidence limit
USGS	U.S. Geologic Survey
VOC	volatile organic compound
WCRR	Waste Characterization, Reduction, and Repackaging Facility
WETF	Weapons Engineering Tritium Facility
WIPP	Waste Isolation Pilot Plant

CONVERSIONS

METRIC TO ENGLISH			ENGLISH TO METRIC		
Multiply	**by**	**To get**	**Multiply**	**by**	**To get**
Area					
Square meters	10.764	Square feet	Square feet	0.092903	Square meters
Square kilometers	247.1	Acres	Acres	0.0040469	Square kilometers
Square kilometers	0.3861	Square miles	Square miles	2.59	Square kilometers
Hectares	2.471	Acres	Acres	0.40469	Hectares
Concentration					
Kilograms/square meter	0.16667	Tons/acre	Tons/acre	0.5999	Kilograms/square meter
Milligrams/liter	1 [a]	Parts/million	Parts/million	1 [a]	Milligrams/liter
Micrograms/liter	1 [a]	Parts/billion	Parts/billion	1 [a]	Micrograms/liter
Micrograms/cubic meter	1 [a]	Parts/trillion	Parts/trillion	1 [a]	Micrograms/cubic meter
Density					
Grams/cubic centimeter	62.428	Pounds/cubic feet	Pounds/cubic feet	0.016018	Grams/cubic centimeter
Grams/cubic meter	0.0000624	Pounds/cubic feet	Pounds/cubic feet	16,025.6	Grams/cubic meter
Length					
Centimeters	0.3937	Inches	Inches	2.54	Centimeters
Meters	3.2808	Feet	Feet	0.3048	Meters
Kilometers	0.62137	Miles	Miles	1.6093	Kilometers
Temperature					
Absolute					
Degrees C + 17.78	1.8	Degrees F	Degrees F - 32	0.55556	Degrees C
Relative					
Degrees C	1.8	Degrees F	Degrees F	0.55556	Degrees C
Velocity/Rate					
Cubic meters/second	2118.9	Cubic feet/minute	Cubic feet/minute	0.00047195	Cubic meters/second
Grams/second	7.9366	Pounds/hour	Pounds/hour	0.126	Grams/second
Meters/second	2.237	Miles/hour	Miles/hour	0.44704	Meters/second
Volume					
Liters	0.26418	Gallons	Gallons	3.78533	Liters
Liters	0.035316	Cubic feet	Cubic feet	28.316	Liters
Liters	0.001308	Cubic yards	Cubic yards	764.54	Liters
Cubic meters	264.17	Gallons	Gallons	0.0037854	Cubic meters
Cubic meters	35.314	Cubic feet	Cubic feet	0.028317	Cubic meters
Cubic meters	1.3079	Cubic yards	Cubic yards	0.76456	Cubic meters
Cubic meters	0.0008107	Acre-feet	Acre-feet	1233.49	Cubic meters
Weight/Mass					
Grams	0.035274	Ounces	Ounces	28.35	Grams
Kilograms	2.2046	Pounds	Pounds	0.45359	Kilograms
Kilograms	0.0011023	Tons (short)	Tons (short)	907.18	Kilograms
Metric tons	1.1023	Tons (short)	Tons (short)	0.90718	Metric tons
ENGLISH TO ENGLISH					
Acre-feet	325,850.7	Gallons	Gallons	0.000003046	Acre-feet
Acres	43,560	Square feet	Square feet	0.000022957	Acres
Square miles	640	Acres	Acres	0.0015625	Square miles

a. This conversion is only valid for concentrations of contaminants (or other materials) in water.

METRIC PREFIXES

Prefix	Symbol	Multiplication factor
exa-	E	1,000,000,000,000,000,000 = 10^{18}
peta-	P	1,000,000,000,000,000 = 10^{15}
tera-	T	1,000,000,000,000 = 10^{12}
giga-	G	1,000,000,000 = 10^{9}
mega-	M	1,000,000 = 10^{6}
kilo-	k	1,000 = 10^{3}
deca-	D	10 = 10^{1}
deci-	d	0.1 = 10^{-1}
centi-	c	0.01 = 10^{-2}
milli-	m	0.001 = 10^{-3}
micro-	µ	0.000 001 = 10^{-6}
nano-	n	0.000 000 001 = 10^{-9}
pico-	p	0.000 000 000 001 = 10^{-12}